



SOUTH FLORIDA WATER MANAGEMENT DISTRICT

3301 Gun Club Road, West Palm Beach, Florida 33406 • (561) 686-8800 • FL WATS 1-800-432-2045 • TDD (561) 697-2574
Mailing Address: P.O. Box 24680, West Palm Beach, FL 33416-4680 • www.sfwmd.gov

September 26, 2006

ADDENDUM NO. 1

RFB 60000000022/PB05

LAKE TRAFFORD DREDGING, PHASE II - NEARSHORE, COLLIER COUNTY, FLORIDA

1. BID OPENING DATE:

This is to advise that the deadline for the Bid remains: **Tuesday, October 3, 2006 at 2:30 p.m.**

2. QUESTION & ANSWERS:

Please see the attached questions and answers.

3. CLARIFICATION ITEMS:

Please see the attached clarification items.

Please acknowledge receipt of this **ADDENDUM NO. 1** by signing in the space indicated below and returning a copy with your Bid submitted in response to this solicitation. Please direct any questions to the undersigned at (561) 682-2813.

Sincerely,

A handwritten signature in black ink, appearing to read "C. Richards", is written over the typed name.

Catherine E. Richards, CPPB
Sr. Contract Specialist

ADDENDUM NO. 1 received on _____ by _____
Date Company Name

GOVERNING BOARD

Kevin McCarty, *Chair*
Irela M. Bagué, *Vice-Chair*
Pamela Brooks-Thomas

Alice J. Carlson
Michael Collins
Nicolás J. Gutiérrez, Jr., Esq.

Lennart E. Lindahl, P.E.
Harkley R. Thornton
Malcolm S. Wade, Jr.

EXECUTIVE OFFICE

Henry Dean, *Executive Director*

QUESTIONS AND ANSWERS:

1. SECTION 02375: Page 123: 1.08: Closure Plan: Part 2: Are the "shallow drainage ditches" inside the CDF required to be filled upon completion of the CDF closure?
Answer: Yes, the Contractor shall comply with all items in the Closure Plan.
2. SECTION 02375: Page 123: 1.08: Closure Plan: Part 5: Is the contractor required to flatten the entire CDF area, or will interior remain in the post dredge condition?
Answer: The perimeter and interior levees shall be degraded and fill material placed over the spoil or the post dredge surface.
3. SECTION 02375: Page 123: 1.08: Closure Plan: Part 6: Is contractor to assume that only the "degraded embankment areas" are to be seeded, and not all of the interior portions of the CDF? Are there any requirements concerning the existing vegetation in the CDF?
Answer: All areas disturbed by the Contractor during construction shall be seeded.
4. Drawing Sheet 6 of 8: This drawing depicts the use of geotextile fabric at the outfall pipe(s). Was fabric used over the levee slopes?
Answer: No
5. If so, to remain in place during the degradation of the levee.
Not applicable

CLARIFICATION ITEMS:

General Terms and Conditions, Page 00700-2-16, Article 6.02 Labor; Working Hours, Item B. shall now read:

"Except as otherwise required for the safety or protection of persons or the Work or property at the Site or adjacent thereto, and except as otherwise stated in the CONTRACT Documents, all Work at the Site shall be performed either during regular working hours, or twenty four hours a day/seven days a week (subject to any local ordinances which may apply), and CONTRACTOR will not permit overtime work or the performance of Work on Saturday, Sunday, or any legal holiday without DISTRICT's written consent and 48 hours notice."

General Terms and Conditions, Page 00700-2-4, Article 2.07 Initial Acceptance of Schedules, Item 4. shall now read:

"Price for mobilization and demobilization shall be distributed such that the mobilization and demobilization charges are equal. Demobilization may be paid either at the time of actual demobilization or in the last Application for Payment."