

DLT X /MAT Item Synopsis (check one)

Contract/Purchase Order Number: CN060951 - Ab09
 Project Title: Packingham/Buttermilk Sloughs Restoration Features
 Contractor: LJ Clark Construction

Project Manager Name: Tanya Barnes
 Project Manager Phone Extension: 6855
 Contract Specialist/Purchasing Agent: Cathy Richards

Department Approval: [Signature]
 (Use this space for signatures instead of an internal approval routing sheet)

DED Approval: _____*
 (This signature is only required for retroactive transactions)

A.

DOCUMENT	NEW ACTION?	SCOPE CHANGE?	DOLLAR INCREASE?	TIME EXTENSION?	RETROACTIVE?*	ON-SITE WORKERS?	TERM EXCEEDS 3 YEARS?
Contract	Yes					Yes	No
Work Order							
Change Order							
Purchase Order							
Amendment							

B. ORIGINAL ACTION OR NEW ACTION INFORMATION (Contract, Work Order, Purchase Order)

Original Start Date	Original End Date	Original Project Price
TBD	TBD	\$749,000

C. HISTORY OF CHANGES MADE:

Number of Changes to Date	Current End Date	Current Project Price

D. THIS CHANGE REQUEST

Amend/WO/CO #	New End Date	New Project Price

E. JUSTIFICATIONS:

- Project Background and Objectives.** The objective of this project is to restore the pre-channelization hydroperiod to the floodplain in the area of Packingham and Buttermilk Sloughs. It involves construction of a levee, emergency concrete spillway and gated culvert to restore and manage wetlands. This project is intended to be a wetland restoration project.

The project design has been coordinated with the Kissimmee River Restoration project team to ensure complete compatibility with that project and to ensure that there are no adverse upstream impacts to private land owners.

Construction cost for this project will be funded from a NRCS grant. The District will provide a 25% cost match through in-kind services.

- Why this action is necessary?** This project is necessary to restore the Packingham and Buttermilk Slough areas to natural wetlands.
- Can this work be placed in a new contract? (Only applicable to changes to existing actions.)** N/A
- Why is this change a retroactive action (if this applies, the DED signature is required above):** N/A

SECTION 01010 SUMMARY OF WORK

PART 1 - GENERAL

1.01 SUMMARY: This section summarizes the Work of the Project as covered in detail in the complete Contract Documents. This is a general summary and is not intended to be complete and all inclusive of the required Work items.

1.02 PROJECT DESCRIPTION:

- A. Description of Total Project: The work under this contract includes:
 - 1. Leveling Baseline "A" and removing three existing 4-ft diameter culverts; earthwork to be pushed into existing swales and degraded overall;
 - 2. Installing new levee alignment (Baseline "B") from just west of the existing boat ramp south to the spoil area;
 - 3. Construction a new levee alignment at the southeast corner of Buttermilk Slough; (East section of Baseline "C")
 - 4. Building one 20-ft long emergency spillway with a crest elevation of 51' and a 4-ft diameter gated culvert at the southeast corner of Baseline "C" to allow discharge to Kissimmee River;
 - 5. Construct ditch plugs at some strategic points at Packingham and Buttermilk Sloughs to maintain sheet flow so that hydroperiod to the floodplain will be restored;
- B. Access to the project site will require coordination with SFWMD to obtain key from the field office

1.03 RELATED CONTRACT ACTIVITIES:

- A. The Contractor shall furnish all shop drawings, working drawings, labor, materials, equipment, tools, services and incidentals necessary to complete all work required by the Specifications and as shown on the Contract drawings.
- B. The Contractor shall perform the work complete, in place and ready for continuous service and shall include any repairs, replacements, and/or restoration required as a result of damages caused prior to acceptance by the Owner.
- C. The Contractor shall furnish and install all materials, equipment and labor which is reasonably and properly inferable and necessary for the proper completion of the work, whether specifically indicated in the Contract Documents or not.

1.04 WORK PERFORMED BY OTHERS:

- A. None

1.05 CONTRACTOR'S USE OF PREMISES: See General Terms & Conditions Article 6.11.

1.06 DISTRICT'S USE OF PREMISES:

- A. Partial District Occupancy: The District reserves the right to occupy and to place and install equipment in areas of the Project, prior to Substantial Completion provided that such occupancy does not interfere with completion of the Work. Such placing of equipment and partial occupancy shall not constitute acceptance of the Work.

1.07 WORK SEQUENCE, COORDINATION ACTIVITIES AND SCHEDULED DATES:

- A. General: The CONTRACTOR will coordinate its work with other adjacent contractors, landowners and District activities, with specific attention to access and staging areas. Construction sequence shall be determined by Contractor subject to the following needs for continuous access and operation by others.
 - 1. All work done under this Contract shall be done with a minimum of inconvenience to the users of the system or facility. The Contractor shall coordinate his work with private property owners such that existing utility services are maintained to all users to the maximum extent possible.
 - 2. The Contractor shall, if necessary and feasible, construct the work in stages to accommodate the Owner's use of the premises during the construction period; coordinate the construction schedule and operations with the Owner's Representative.
 - 3. The Contractor shall, where feasible, construct the Work in stages to provide for public convenience and not close off public use of any facility until completion of construction or provide alternative usage.

1.08 COPIES OF DOCUMENTS: See General Terms & Conditions Article 2.02

1.09 LIST OF DRAWINGS:

- A. Contract Drawings:
 - 1. CN060951 Packingham/Buttermilk Sloughs Restoration Features, Sheets 1-11
- B. Reference Materials:
 - 1. The following reference Materials are available for inspection at the offices of the District: Packingham Slough Topographic Survey, Sheets 1-13

END OF SECTION