

SURVEYOR'S REPORT

**Specific Purpose Survey of
Weather Tower Wet Prairie
Monroe County, Florida**

Prepared for:

South Florida Water Management District

Prepared by:



301 East Atlantic Boulevard

Pompano Beach, Florida 33060-6643

Ph. (954) 788-3400 Fax (954) 788-3500

Licensed Business (L.B.) 6860

South Florida Water Management District's

Purchase Order number 4500012430

Keith and Associates project number 07050.02,

Task 001

Report Date: September 4, 2007

Submittal: First

SURVEYOR'S REPORT

TABLE OF CONTENTS

Purpose	1
Project location	1
Deliverables	2
Datum	2
Leveling Methods	2
Vertical Control	3-6
Site Photos	7-9
Project Results	10
Site Drawing	11
Comments	12
Surveyor's Certificate	12


SURVEYOR'S REPORT

PURPOSE

To establish (NAVD 1988 and NGVD 1929) vertical data at the site.
Set a site benchmark and elevate the well.

LOCATION OF PROJECT

The project is located in Monroe County, Florida.



SURVEYOR'S REPORT

ITEMS DELIVERED TO THE DISTRICT

1. Electronic copy of field notes.
2. Electronic copy of all computation sheets.
3. CORPSMET 95 file.
4. Site photographs.
5. Surveyor's Report.
6. District Benchmark Sheet.
7. AutoCad drawing.

DATUM FOR THE PROJECT

The vertical datum for the project is National Geodetic Vertical Datum (NGVD) of 1929 and North American Vertical Datum (NAVD) of 1988. NGVD 1929 elevations and offset were derived using the NGVD 1929.txt file supplied by the South Florida Water Management District. Horizontal datum is NAD (North American Datum) 1983/03.

LEVELING METHODS


Site Benchmark "WET 2007" is a 3-1/2" SFWMD brass disk set in poured concrete near the Wet Prairie weather tower. A level loop was run starting at NGS benchmark D-557, through site Benchmark "Small 2007" (at the Small Cypress antenna site) through NGS Benchmark F-557, through site Benchmark "Wet 2007" (at the Wet Prairie antenna site), through NGS benchmark Pinecrest and back to D-557. Site Benchmark "Wet 2007" was used to as-built the well and obtain the site elevations. A Leica NA2 conventional level was used for the level run and the site As-Built. The level run meets or exceeds the closure requirement of "the square root of the level run in miles x 0.03'.

HORIZONTAL LOCATIONS

Horizontal locations were obtained using a Trimble 5700 receiver and RTK cellular link.


SURVEYOR'S REPORT

VERTICAL CONTROL

D-557		Elevation:	NAVD 1988	7.218'	NGVD 1929	8.700'
PID AJ8943		Latitude	25°45'39" (Scaled)		From NGVD 29.txt file	
State/County FL/Monroe		Longitude	-80°53'45" (Scaled)			
USGS QUAD Fiftymile Bend (1995)						
Vertical Order First Class II		The mark is about 37.8 mi west of Miami, 4.4 mi west of Fortymile Bend, in estimated Section 23, Township 53 South, Range 35 East. To reach the mark from the junction of County Road 997 (Krome Avenue SW 177th Ave) and U.S. Highway 41 (Tamiami Trail, SW 8th Street) about 10.0 miles southwest of Hialeah, go west on U.S. Highway 41 (Tamiami Trail, SW 8th Street) for 21.2 mi to Flood Control Structure S-12A, continue west on U.S. Highway 41 for 0.35 mi to the junction of Loop Road (State Highway 94) on the left, turn left on Loop Road (State Highway 94) and go south then west for 4.35 mi to the mark on the left, set in the top of a round concrete monument flush with the ground and level with loop road. Located 175.0 ft west of a power pole, 23.4 ft east of a 10-inch cypress tree, 14.9 ft south of the approximate centerline of Loop Road, 7.4 ft north of the south side of the canal and 1.5 ft north of a carsonite witness post. Note a magnet was imbedded in the ground on the south side of the monument.				
						



SURVEYOR'S REPORT

VERTICAL CONTROL (CONTINUED)

F-557		Elevation:	NAVD 1988	7.247'	NGVD 1929	8.729'
PID AJ8945	Latitude		25°45'29" (Scaled)		From NGVD 29.txt file	
State/County FL/Monroe	Longitude		-80°55'42" (Scaled)			
USGS QUAD Fiftymile Bend (1995)						
Vertical Order Class	First II		<p>The mark is about 39.9 mi west of Miami, 6.5 mi west of Fortymile bend, in estimated Section 21, Township 54 South, Range 34 East. To reach the mark from the junction of County Road 997 (Krome Avenue SW 177th Ave) and U.S. highway 41 (Tamiami Trail, SW 8th Street) about 10.0 miles southwest of Hialeah, go west on U.S. highway 41 (Tamiami Trail, SW 8th street) for 21.2 mi to Flood Control Structure S-12A, continue west on U.S. Highway 41 for 0.35 mi to the junction of Loop Road (State Highway 94) on the left, turn left on Loop Road (State Highway 94) and go south then west for 6.45 mi to the mark on the left, set in the top of a round concrete monument flush with the ground and level with Loop Road. Located 67.7 ft southeast of power pole number 37-10, 20.3 ft south of the approximate centerline of Loop Road, 17.2 ft southwest of the west end of a slough headwall and 1.3 ft north of a carsonite witness post. Note a magnet was imbedded in the ground on the south side of the monument.</p>			
						



SURVEYOR'S REPORT

VERTICAL CONTROL (CONTINUED)

PINECREST		Elevation:	NAVD 1988	6.834'	NGVD 1929	8.315'
PID AC4455	Latitude		25°44'46.71348"		From NGVD 29.txt file	
State/County FL/Monroe	Longitude		-80°56'2243678"			
USGS QUAD Lostmans Trail (1972)						
Vertical Order First Class II Horizontal Order A			The mark is about 41.1 mi west of Miami, 7.6 mi west of Fortymile Bend, in estimated Section 29, Township 54 South, Range 34 East. To reach the mark from the junction of County Road 997 (Krome Avenue SW 177th Ave) and U.S. Highway 41 (Tamiami Trail, SW 8th Street) about 10.0 miles southwest of Hialeah, go west on U.S. Highway 41 (Tamiami Trail, SW 8th Street) for 21.2 mi to flood control structure S-12A, continue west on U.S. Highway 41 for 0.35 mi to the junction of Loop Road (State Highway 94) on the left, turn left on Loop Road (State Highway 94) and go south then west for 7.65 mi to a curve right and the mark on the left, set in the top of a square concrete monument projecting 0.3 ft above the level of the ground and above the level of Loop Road. Located 172.2 ft southwest of power pole number 25-40, 57.1 ft west of a warning o.r.v. permit required sign, 27.2 ft south of the approximate centerline of Loop Road, 1.3 ft south of a metal witness post and 1.0 ft north of a metal witness post. Note a magnet was imbedded in the ground on the south side of the monument.			
 <p style="text-align: center;">Benchmark Pinecrest</p>						
						


SURVEYOR'S REPORT

VERTICAL CONTROL (CONTINUED)

WET 2007	Elevation:	NAVD 1988	5.569'	NGVD 1929	7.050'
	Latitude	25°44'41.8"	Elevation derived from the level run described above.		Elevation derived from the level run described above.
State/County FL/Monroe	Longitude	-80°56'28.8"			
USGS QUAD Lostmans Trail (1972)					
Vertical Order Third Horizontal Order Third		The mark is about 39.9 mi west of Miami, 6.5 mi west of Fortymile Bend, in estimated Section 29, Township 54 South, Range 34 East. To reach the mark from the junction of County Road 997 (Krome Avenue SW 177th Ave) and U.S. Highway 41 (Tamiami Trail, SW 8th Street) about 10.0 miles southwest of Hialeah, go west on U.S. Highway 41 (Tamiami Trail, SW 8th Street) for 21.2 mi to flood control structure S-12A, continue west on U.S. Highway 41 for 0.35 mi to the junction of Loop Road (State Highway 94) on the left, turn left on Loop Road (State Highway 94) and go south, then west, then south for 7.5 miles to the mark on the right. The mark is a 3-1/2" SFWMD brass disk in poured concrete approximately 7.6 miles west-southwest of Tamiami Trail along Loop Road (East) and 500' +/- south of Loop Road, 7.4' south of the sw corner of the tower base and 11.1' east of the rain gauge.			
					
					

SURVEYOR'S REPORT

SITE PHOTOS



Wet Prairie Tower

SURVEYOR'S REPORT

SITE PHOTOS (CONTINUED)



Wet Prairie Well

SURVEYOR'S REPORT
SITE PHOTOS (CONTINUED)



Wet Prairie Rain Gauge

SURVEYOR'S REPORT

PROJECT RESULTS

Well Site Wet Prairie

Reference mark: **Fnd. X-Cut on PVC pipe.**

New Information at the site:

Mark El. **10.53'** (NGVD 29).

Mark El. **9.05'** (NAVD 88).

Initials: **K&A**

Date: **06/18/07**

Offset : **1.48'**

Previous Information at the site:

None

Reference Mark Elevation(s)

El. **N/A**

Date: **N/A**

Initials: **N/A**

Reference Mark location

N/A

DTW (Distance to water inside well)

Reference mark:


Same as Fnd. Mark above

Measurement to water: **4.45'**


El. **6.1'** (NGVD 29)

Date: **06/21/07**

Time: **10:26 a.m.**



SCALE: 1" = 20'



NOTE:
ELEVATIONS SHOWN HEREON ARE NGVD 1929 UNLESS OTHERWISE NOTED.
HORIZONTAL DATUM SHOWN HEREON IS NAD 1983 WITH THE
1990 ADJUSTMENT APPLIED (83/90)

- LEGEND:
- B.M. = BENCHMARK
 - LAT. = LATITUDE
 - LONG. = LONGITUDE
 - NAD = NORTH AMERICAN DATUM
 - NAVD = NORTH AMERICAN VERTICAL DATUM
 - NGVD = NATIONAL GEODETIC VERTICAL DATUM
 - SFWMD
 - ~~7.5'~~ = EXISTING ELEVATION

WET PRAIRIE
TOWER AND EQUIPMENT
LOCATIONS

KEITH
ASSOCIATES, INC.
consulting engineers
301 EAST ATLANTIC BOULEVARD
POMPANO BEACH, FLORIDA 33060-6643
(954) 788-3400 FAX (954) 788-3500
EMAIL: mail@keith-associates.com LB NO. 6860

SHEET 1 OF 1
DRAWING NO. _____

DATE 9/3/07
SCALE 1"=20'
FIELD BK. 268
DWNG. BY MMM
CHK. BY AMK

DATE	REVISIONS

SURVEYOR'S REPORT

Comments

Elevations shown hereon are NGVD 1929 datum unless noted otherwise.

Party Chief: A. McKinney Field Book: 268 Pages 3-19, 74-75

Bench Mark: "WET 2007" El. 5.569', Vertical Datum: NAVD1988

El. 7.050', Vertical Datum: NGVD1929

Offset: 1.481' SFWMD VALUE (subtract this value to convert to NAVD 1988)

Offset: 1.481' NGS VALUE (subtract this value to convert to NAVD 1988)

The offset values referred to as "SFWMD VALUE" and "NGS VALUE" were derived by subtracting the published NAVD 1988 elevation from the NGVD 29.txt file value at Benchmark "PINECREST".

NAVD 88 - North American Vertical Datum of 1988

NGVD29 -National Geodetic Vertical Datum of 1929

NAD 83 -99 (Horizontal Datum) North American Datum

NGS - National Geodetic Survey

SFWMD - South Florida Water Management District

PVC - Polyvinyl Chloride

L.B. - Licensed Business

SURVEYOR'S CERTIFICATION

I hereby certify that this Specific Purpose Survey meets applicable portions of the Minimum Technical Standards set forth by the Florida Board of Professional Surveyors and Mappers in Chapter 61-G17, Florida Administrative Code. This report is prepared for the sole and specific use of the South Florida Water Management District and is not assignable.

Keith and Associates, Inc.

L.B. number 6860

By:


Michael M. Mossey, PSM

Professional Surveyor and Mapper

State of Florida

Certificate No. 5660

Date of Survey
September 3, 2007