




CH2MHILL



CH2M HILL
3011 S.W. Williston Road
Gainesville, FL
32608-3928
Mailing address:
P.O. Box 147009
Gainesville, FL
32614-7009
Tel 352.335.7991
Fax 352.335.2959

March 16, 1999

Mr. Duane Watroba, UIC TAC Chairman
Florida Department of Environmental Protection - Central District
3319 Maguire Boulevard
Suite 232
Orlando, FL 32803-3767

Subject: Cocoa - Drilling and Testing Report for New ASR Wells

Dear Mr. Watroba:

On behalf of the City of the Cocoa, we are submitting to the TAC four copies of our report entitled "Results of Aquifer Storage and Recovery Well Drilling and Testing - Wells R-7, R-8, R-9 and R-10." The report documents the construction and aquifer testing of four new ASR wells drilled under UIC permit no. UC48-294600.

As described in the report, we propose to do an initial performance acceptance test (PAT) of the four well system in June 1999, as part of the start up of the entire Dyal plant expansion project. A more extensive "Cycle Test" or "Operational Test" is proposed for October 1999.

The initial performance acceptance test, and the cycle testing to be conducted in October, will serve as the "step injection tests" described in the UIC permit. A cycle testing plan will be submitted to FDEP after completion of the PAT. Written notice will be provided to FDEP for both tests.

Please contact me if you have any questions or concerns regarding this report.

Sincerely,

CH2M HILL

For
D. Edward Davis, P.E.
Project Manager

GNVDocument3

c: Ed Wegerif/Cocoa
Carl Larrabee/Cocoa
Mike Dykes/CH2M HILL
Ross Sproul/CH2M HILL

Results of Aquifer Storage and Recovery Well Drilling and Testing

Wells R-7, R-8, R-9, and R-10


Prepared for the



Prepared by



March 1999
140312.A1.AS



Contents

| | | |
|-----------|---|------------|
| 1. | Introduction..... | 1-1 |
| 1.1 | Scope..... | 1-1 |
| 1.2 | Project Background | 1-1 |
| 1.3 | Location and Site Description..... | 1-1 |
| 1.4 | Local Geology | 1-3 |
| 2. | ASR Facility Expansion Construction..... | 2-1 |
| 2.1 | Summary of Construction Program..... | 2-1 |
| 2.2 | Summary of Construction Methods | 2-1 |
| 2.3 | Construction of Well R-7 | 2-2 |
| 2.4 | Construction of Well R-8 | 2-2 |
| 2.5 | Construction of Well R-9 | 2-4 |
| 2.6 | Construction of Well R-10 | 2-4 |
| 3. | Well Performance Testing | 3-1 |
| 3.1 | Description of Testing..... | 3-1 |
| 3.2 | Step Pumping Tests..... | 3-2 |
| 3.3 | Constant Rate Pumping Tests..... | 3-3 |
| 3.4 | Geophysical Logging | 3-3 |
| 3.5 | Water Quality Testing..... | 3-3 |
| 4. | Summary and Discussion of Results..... | 4-1 |
| 4.1 | Hydraulic Response of the Aquifer | 4-1 |
| 4.2 | Water Quality Observations | 4-2 |
| 4.3 | Assessment of ASR Potential | 4-2 |
| 5. | Recommendations..... | 5-1 |
| 6. | Works Cited..... | 6-1 |

Exhibits

| | |
|-----|--|
| 1-1 | Cocoa ASR System |
| 2-1 | Completion Details for Well R-7 |
| 2-2 | Completion Details for Well R-8 |
| 2-3 | Completion Details for Well R-9 |
| 2-4 | Completion Details for Well R-10 |
| 3-1 | Summary of Six-Hour Step Test Results |
| 3-2 | Summary of Calculated Aquifer Properties |
| 3-3 | Drawdowns Observed During the R-7 Constant Rate Test |
| 3-4 | Drawdowns Observed During the R-8 Constant Rate Test |
| 3-5 | Drawdowns Observed During the R-9 Constant Rate Test |

Exhibits, Continued

- 3-6 Drawdowns Observed During the R-10 Constant Rate Test
- 3-7 Summary of Geophysical Logs for Well R-7
- 3-8 Summary of Geophysical Logs for Well R-8
- 3-9 Summary of Geophysical Logs for Well R-9
- 3-10 Summary of Geophysical Logs for Well R-10
- 4-1 Target Recharge and Recovery Rates
- 4-2 Native Water Quality Summary

Appendixes

- A Water Quality Data
 - A-1 Water Quality Results During Drilling & Pumping Tests
 - A-2 FDEP Primary and Secondary Drinking Water Analyses
- B Well Construction and Testing Data
 - B-1 FDEP Classifications of Class V Well Construction Completion
 - B-2 Alignment and Pressure Testing Data
 - B-3 Step Test Results
 - B-4 Constant Rate Test Results
- C Geophysical Logs

Acronyms and Abbreviations

| | |
|--------|--|
| ASR | aquifer storage and recovery |
| AWWA | American Water Works Association |
| bls | below land surface |
| btoc | below top of casing |
| City | City of Cocoa |
| CUP | Consumptive Use Permit |
| DO | dissolved oxygen |
| FDEP | Florida Department of Environmental Protection |
| ft | feet |
| GST | ground storage tank |
| LSN | long-short normal |
| mgd | million gallons per day |
| mg/L | milligrams per liter |
| msl | mean sea level |
| NTU | nephelometric turbidity units |
| O&M | operations and maintenance |
| OD PVC | outside diameter polyvinyl chloride |
| PAT | performance acceptance test |
| ppm | parts per million |
| psi | pounds per square inch |
| PVC | polyvinyl chloride |
| SCADA | Supervisory Control and Data Acquisition |
| SJRWMD | St. Johns River Water Management District |
| WTP | water treatment plant |

1. Introduction

1.1 Scope

This report documents the construction and testing of four new ASR wells at the City of Cocoa's Claude H. Dyal Water Treatment Plant (WTP). The new ASR wells, designated R-7, R-8, R-9, and R-10, were constructed under Florida Department of Environmental Protection Underground Injection Control (FDEP UIC) Permit No. UC48-294600.

1.2 Project Background

Aquifer storage and recovery (ASR) is a water management technology in which freshwater is stored in a local aquifer, and later recovered for use. Typically, storage and recovery cycles are seasonal. Water is injected into the aquifer, via the ASR wells, whenever water availability exceeds water demand. The water is recovered, via the same wells, during periods of peak demand.

The first phase of ASR development for the City of Cocoa (the City) consisted of one ASR well (R-1) at the Claude H. Dyal Water Treatment Plant (WTP) site, with a recovery capacity of approximately 1.5 million gallons per day (mgd). In 1988, FDEP permitted this well for operational use.

In 1990, the ASR system was expanded to include five additional wells (R-2, R-3, R-4, R-5, and R-6). This six-well system was permitted in 1992 for a recovery capacity of approximately 8.0 mgd, and it continues to help the City meet peak demands.

In 1993, the City obtained Consumptive Use Permit (CUP) No. 2-097-0024ANG from the St. Johns River Water Management District (SJRWMD) to develop nearby Taylor Creek Reservoir for use as a water supply. The CUP also authorized construction of four additional ASR wells (R-7, R-8, R-9, and R-10) for use in conjunction with reservoir withdrawals..

1.3 Location and Site Description

The Dyal WTP is located on State Road 520 in Orange County, Florida. The six existing ASR wells are located on the Dyal plant site. Southwest of the plant site, the City acquired a 26-acre ASR parcel to accommodate the four new ASR wells. The location of the Cocoa ASR system is shown in Exhibit 1-1.

The site is located on the coastal lowlands of Florida, within the St. Johns River Valley. Surrounding topography is mostly sandy prairie and wetland marsh. Vegetation is mostly grasses, saw palmetto, palm, oak, myrtle, and cypress. The former owner, Deseret Ranches of Florida, used the 26-acre parcel for grazing cattle.




Exhibit 1-1. Cocoa ASR System.

1.4 Local Geology

The local geology beneath the Cocoa Dyal plant site was described in *Aquifer Storage Recovery Feasibility Investigation – Final Report* (CH2M HILL, 1988) and in *Results of Aquifer Storage Recovery Well Drilling and Testing* (CH2M HILL, 1990). This section briefly summarizes related information contained in these reports.

Site geology consists of Eocene-age carbonate rocks overlain by Miocene-age clay and marl, and Pleistocene to Recent unconsolidated sand and shell. The surficial sediments consist of interbedded sand, silt, shell, and clay, extending from land surface to approximately 120 feet below land surface (bls).

The Hawthorn group underlies the surficial surface, and consists of interbedded sand, clay, shell, marl, and limestone. It is characterized by abundant phosphate in both consolidated and unconsolidated deposits. It grades from dense gray-green clay to interbedded carbonates with sand and clay. It extends from approximately 120 feet bls to 250 feet bls. The Hawthorn group forms the upper confining bed of the ASR storage zone.

Below the Hawthorn group, the Ocala formation is characterized by chalky, fossiliferous limestones of the upper Eocene age. The upper part of this formation comprises the storage zone of the Cocoa ASR facility. The less pervious lower section, which was not penetrated during drilling, forms the lower confining unit for the ASR zone.

The interface between the Ocala formation and the Hawthorn group exists as an unconformity, with varying elevation across the site. The top of the Ocala formation ranges from approximately 240 to 280 feet bls, and extends to approximately 500 feet bls. Below this depth lies the porous Avon Park formation, which contains solution cavities. The Avon Park formation is the main water-producing zone in the City's raw water wellfield, located approximately 10 to 13 miles west of the Dyal WTP.

2. ASR Facility Expansion Construction

2.1 Summary of Construction Program

The four additional ASR wells were constructed as part of a major expansion of the City's Dyal WTP. The expansion includes an intake structure and raw water pump station at Taylor Creek Reservoir, a transmission pipeline, and a separate surface water treatment train on the grounds of the Dyal plant. The prime contractor for the plant expansion was the Poole and Kent Company of Miami, Florida. The subcontractor for the construction of the ASR wells was Meridith Environmental, Inc. of Orlando, Florida. On September 12, 1997, the City obtained from FDEP a UIC permit to construct the ASR wells and surface facilities. Construction activities began shortly thereafter, and all four wells were completed and tested by May 7, 1998.

2.2 Summary of Construction Methods

The mud rotary method was used to drill through the unconsolidated formations and into the upper portion of the Ocala formation. A temporary 36-inch pit casing was driven into place to seal off the first 40 feet at each borehole. Surface casing of 26-inch diameter steel with 0.312-inch wall thickness was then installed and grouted in approximately the first 120 feet of each well to stabilize the surficial formations.

After drilling had advanced to the top of the storage zone, the final casing string was installed and grouted. The final casing was approximately 300 feet of 17.4-inch outside diameter (OD) polyvinyl chloride (PVC) pipe with 1.024-inch wall thickness, manufactured by Certain-Teed Corporation. The pipe was joined with the Certa-Lok method using PVC couplings and graphite splines inserted into machined grooves in each casing joint.

Following the PVC casing's setting, cementing, and pressure testing, drilling resumed using the mud rotary method. This method continued only until enough water was produced from the borehole to sustain reverse-air drilling. The reverse-air circulation drilling method was typically started within 15 to 20 feet below the bottom of the PVC casing. During reverse-air drilling, water quality samples were obtained and then analyzed in the Cocoa WTP laboratory.

Following borehole completion, each well was acidized and then developed with air lifting. The wells were then temporarily capped until pump testing was conducted. The performance of each well was evaluated with a variable rate step test, followed by a constant rate pumping test. The pump testing is further discussed in Section 3.

Following the pumping tests, the final PVC wellheads were installed. The wellhead excavations were backfilled and compacted, and the wells were checked for plumbness and alignment in accordance with American Water Works Association (AWWA) A100. Each well was swabbed and disinfected with a chlorine solution in excess of 50 parts per million

(ppm) chlorine. The solution was allowed to remain in the well for a minimum of 12 hours before removal by pumping.

2.3 Construction of Well R-7

Construction of Well R-7 began on September 22, 1997, and was completed on November 14, 1997. Construction began with the installation of a temporary 36-inch pit casing to 38 feet. Drilling of a 9 7/8-inch pilot hole resumed to 122 ft bls. The pilot hole was then reamed to a diameter of 32 inches. After reaming, 120 feet of 26-inch surface casing was installed and grouted in place with 300 sacks of neat cement. The temporary pit casing was then removed. Pilot hole drilling resumed to a depth of 305 feet, and competent limestone was encountered at a depth of approximately 280 feet. The pilot hole was then reamed to a 25-inch diameter, and 300 feet of PVC casing was grouted in place. The grouting was completed in three stages of 126, 121, and 100 sacks of cement, respectively. The first stage was completed with neat cement, and the two remaining stages were completed with an 8 percent bentonite-cement blend.

After the cement plug was drilled out, the pilot hole drilling resumed at 310 feet. The pilot hole was advanced to 370 feet in soft to medium hard fossiliferous limestone and was then reamed to a 15-inch diameter. The well was developed by airlifting through the drill string. Well R-7 was then acidized with 3,000 gallons of 28 percent hydrochloric acid and redeveloped by airlifting and surging.

After pump testing and wellhead installation, the straightness and alignment test was conducted, which showed no significant deviations. Well R-7 was then disinfected and capped.

Exhibit 2-1 illustrates completion details for Well R-7.

2.4 Construction of Well R-8

Construction of Well R-8 began on November 17, 1997, and was completed on December 22, 1997. Construction began with the installation of a temporary 36-inch pit casing to 40 feet. Drilling of a 9 7/8-inch pilot hole resumed to 122 ft bls. The pilot hole was then reamed to a 32-inch diameter. After reaming, 120 feet of 26-inch surface casing was installed and grouted in place with 300 sacks of neat cement. The pilot hole was resumed to a depth of 305 feet and competent limestone was encountered at a depth of approximately 290 feet. The pilot hole was then reamed to a 25-inch diameter and 300 feet of PVC casing was grouted in place. The grouting was completed in three stages of 126, 91, and 60 sacks of cement, respectively. The first stage was completed with neat cement, and the two remaining stages were completed with an 8 percent bentonite-cement blend.

After the cement plug was drilled out, the pilot hole drilling resumed at 310 feet. At 317 feet, the well produced sufficient water to sustain reverse-air drilling. The pilot hole was advanced to 370 feet in tan to light gray, soft to medium hard fossiliferous limestone, and was then reamed to a 15-inch diameter. The well was developed by airlifting through the drill string. Well R-8 was then acidized with 3,000 gallons of 28 percent hydrochloric acid and redeveloped by airlifting and surging.

CH2MHILL WELL DRILLING REPORT

PROJECT NO. 140312.A1.AS
 WELL: Cocoa, R-7
 LOCATION: Dyal WTP
Sec. 20, T24S, R 34 E

COUNTY: Orange STATE: FL
 GROUND ELEVATION: ± 42 ft msl
 DIAMETER: 16 inch
 DEPTH: 370 ft bls
 STATIC WATER LEVEL: 8.7 ft btoc
 DATE: May 5, 1998
 CASING: 0-300 ft bls, PVC Certa-Lok 15.3" I.D.
 SCREEN: N/A

CONSTRUCTION: Mud-Rotary, Reverse-Air
 DRILLER: Meredith Environmental
Orlando, Florida
 DATE FINISHED: November 14, 1997

PUMPING TEST

SPECIFIC YIELD 12.9 gpm/ft @ 960 gpm

WATER ANALYSIS (ppm)

TDS 1,140
 TOTAL HARDNESS¹ 450
 M.O. ALKALINITY¹ 162
 CHLORIDE Cl 500
 IRON Fe 0.031
 SULFATE SO₄ 34.9
 COLOR (ALPHA) 10
 CALCIUM¹ 306

COMMENTS Field Parameters
D.O. = 1.7
Turbidity = 0.14
H₂S = 2.1

COMPILED BY R.J. Petersen
 DATE May 21, 1998

¹AS CaCO₃




Exhibit 2-1. Completion Details for Well R-7.

After pump testing and wellhead installation, the straightness and alignment test was conducted, which showed no significant deviations. Well R-8 was then disinfected and capped.

Exhibit 2-2 illustrates completion details for Well R-8.

2.5 Construction of Well R-9

Construction of Well R-9 began on January 5, 1998, and was completed on February 29, 1998. Construction began with the installation of a temporary 36-inch pit casing to 40 feet. Drilling of a 9 7/8-inch pilot hole resumed to 122 ft bls. The pilot hole was then reamed to a 32-inch diameter. After reaming, 120 feet of 26-inch surface casing was installed and grouted in place with 300 sacks of neat cement. The pilot hole was resumed to a depth of 305 feet, and competent limestone was encountered at a depth of approximately 285 feet. The pilot hole was then reamed to a 25-inch diameter, and 300 feet of PVC casing was grouted in place. The grouting was completed in three stages of 126, 120, and 120 sacks of cement, respectively. The first stage was completed with neat cement, and the two remaining stages were completed with an 8 percent bentonite-cement blend.

After the cement plug was drilled out, the pilot hole drilling resumed at 310 feet. At 315 feet, the well produced sufficient water to sustain reverse-air drilling. The pilot hole was advanced to 370 feet in tan to light gray, soft to medium fossiliferous limestone and then reamed to a 15-inch diameter. The well was developed by airlifting through the drill string. Well R-9 was then acidized with 3,000 gallons of 28 percent hydrochloric acid and redeveloped by airlifting and surging.

After pump testing and wellhead installation, the straightness and alignment test was conducted and showed no significant deviations. Well R-9 was then disinfected and capped.

Exhibit 2-3 illustrates completion details for Well R-9.

2.6 Construction of Well R-10

Construction of Well R-10 began on March 20, 1998, and was completed on April 10, 1998. Construction began with the installation of a temporary 36-inch pit casing to 40 feet. Drilling of a 9 7/8-inch pilot hole to was resumed to 122 ft bls. The pilot hole was then reamed to a 32-inch diameter. After reaming, 120 feet of 26-inch surface casing was installed and grouted in place with 303 sacks of neat cement. The pilot hole was resumed to a depth of 305 feet, and competent limestone was encountered at a depth of approximately 290 feet. The pilot hole was then reamed to a 25-inch diameter and 300 feet of PVC casing was grouted in place. The grouting was completed in two stages of 100 and 175 sacks of cement, respectively. The first stage was completed with neat cement, and the final stage was completed with an 8 percent bentonite-cement blend.

After the cement plug was drilled out, the pilot hole drilling resumed at 310 feet. At 316 feet, the well produced sufficient water to sustain reverse-air drilling. The pilot hole was advanced to 370 feet in tan to light gray, soft to medium fossiliferous limestone and then reamed to a 15-inch diameter. The well was developed by airlifting through the drill string.

CH2MHILL
WELL DRILLING REPORT

PROJECT NO. 140312.A1.AS

WELL: Cocoa, R-8

LOCATION: Dyal WTP

Sec. 20, T24S, R 34 E

COUNTY: Orange STATE: FL

GROUND ELEVATION: ± 43 ft msl

DIAMETER: 16 inch

DEPTH: 370 ft bls

STATIC WATER LEVEL: 8.6 ft btoc

DATE: April 27, 1998

CASING: 0-300 ft bls, PVC Certa-Lok 15.3" I.D.

SCREEN: N/A

CONSTRUCTION: Mud-Rotary, Reverse-Air

DRILLER: Meredith Environmental

Orlando, Florida

DATE FINISHED: December 23, 1997

PUMPING TEST

SPECIFIC YIELD 11.6 gpm/ft @ 920 gpm

WATER ANALYSIS (ppm)

TDS 1,070

TOTAL HARDNESS¹ 388

M.O. ALKALINITY¹ 146

CHLORIDE Cl 422

IRON Fe 0.018

SULFATE SO₄ 78.3

COLOR (ALPHA) 7

CALCIUM¹ 290

COMMENTS Field Parameters

D.O. = 1.3

Turbidity = 0.4

H₂S = 1.9

COMPILED BY R.J. Petersen

DATE May 22, 1998

¹AS CaCO₃




Exhibit 2-2. Completion Details for Well R-8.



WELL DRILLING REPORT

PROJECT NO. 140312.A1.AS

WELL: Cocoa, R-9

LOCATION: Dyal WTP

Sec. 20, T24S, R 34 E

COUNTY: Orange

STATE: FL

GROUND ELEVATION: ±45.0 ft msl

DIAMETER: 16-inch

DEPTH: 370 ft bls

STATIC WATER LEVEL: 9.5 ft btoc

DATE: April 15, 1998

CASING: 0-300 ft bls, PVC Certa-Lok 15.3" I.D.

SCREEN: N/A

CONSTRUCTION: Mud-Rotary, Reverse-Air

DRILLER: Meredith Environmental

Orlando, Florida

DATE FINISHED: February 29, 1998

PUMPING TEST

SPECIFIC YIELD 17.0 gpm/ft @ 1,060 gpm

WATER ANALYSIS (ppm)

TDS 934

TOTAL HARDNESS¹ 394

M.O. ALKALINITY¹ 144

CHLORIDE Cl 417

IRON Fe 0.027

SULFATE SO₄ 75.4

COLOR (ALPHA) 10

CALCIUM¹ 258

COMMENTS Field Parameters

H₂S = 3.3

D.O. = 1.2

Turbidity = 0.8

COMPILED BY R.J. Petersen

DATE May 26, 1998

¹AS CaCO₃





Exhibit 2-3. Completion Details for Well R-9.

Well R-10 was then acidized with 3,000 gallons of 28 percent hydrochloric acid and redeveloped by airlifting and surging.

After pump testing and wellhead installation, the straightness and alignment test was conducted, which showed no significant deviations. Well R-10 was then disinfected and capped.

Exhibit 2-4 illustrates completion details for Well R-10.



CH2MHILL WELL DRILLING REPORT

PROJECT NO. 140312.A1.AS

WELL: Cocoa, R-10

LOCATION: Dyal WTP

Sec. 20, T24S, R 34 E

COUNTY: Orange STATE: FL

GROUND ELEVATION: ±45.0 ft msl

DIAMETER: 16 inch

DEPTH: 370 ft bls

STATIC WATER LEVEL: 10.1 ft btoc

DATE: April 20, 1998

CASING: 0-300 ft bls, PVC Certa-Lok 15.3" I.D.

SCREEN: N/A

CONSTRUCTION: Mud-Rotary, Reverse-Air

DRILLER: Meredith Environmental

Orlando, Florida

DATE FINISHED: April 10, 1998

PUMPING TEST

SPECIFIC YIELD 66.3 gpm/ft @ 1,220 gpm

WATER ANALYSIS (ppm)

TDS 1,120

TOTAL HARDNESS¹ 516

M.O. ALKALINITY¹ 166

CHLORIDE Cl 572

IRON Fe 0.039

SULFATE SO₄ 83.1

COLOR (ALPHA) 10

CALCIUM¹ 358

COMMENTS Field Parameters

H₂S = 2.6

D.O. = 2.1

Turbidity = 6.6 NTU

COMPILED BY R.J. Petersen

DATE May 27, 1998

¹AS CaCO₃

Exhibit 2-4. Completion Details for Well R-10.

3. Well Performance Testing

3.1 Description of Testing

Well performance testing was conducted after all four wells had been acidized and developed. Each well was first tested with a variable rate pumping test, followed by a constant rate pumping test.

Step-injection tests will be conducted following installation of wellhead piping and instrumentation, now anticipated to be completed in early June, 1999. The step-injection tests will be conducted in conjunction with the system performance acceptance tests. Proposed procedures for conducting the system performance acceptance and step-injection tests are described in Section 5 of this report.

The variable rate pumping test (step pumping test) was conducted primarily to evaluate each well's drawdown characteristics. The information obtained from this type of test is used for proper sizing of each well's final pump. The constant rate testing was conducted to evaluate aquifer parameters and the hydraulic interference among the four new ASR wells. The City plans to operate these wells as a separate recharge and recovery system. For this reason, a limited amount of data was collected at the six ASR existing wells.

All testing was conducted with a contractor-supplied submersible pump that was powered by a portable generator. Flow rates were measured with a 6-inch propeller flowmeter. During each pumping test, electronic data loggers monitored water levels in the pumping well and in the other three new ASR wells. Water levels were also measured in selected existing ASR wells.

During each of the step tests and constant rate pumping tests, water samples were obtained for water quality analysis. The analyses included field parameters and FDEP primary and secondary drinking water scans.

3.2 Step Pumping Tests

The step pumping tests consisted of pumping each well in a series of three increasing pumping rates (steps) and measuring the resultant water level drawdown in the pumping well. Each step of the test lasted approximately two hours. Water levels in the other three new ASR wells were monitored during this time to obtain a preliminary understanding of the pumping well's effect on the local potentiometric surface. These measurements were primarily used to set up the data loggers for the constant rate tests, and are included in Appendix B.

Step test results of the four new ASR wells are presented in Exhibit 3-1. For each pumping step, drawdowns in the pumping well are reported.

EXHIBIT 3-1
Summary of Six-Hour Step Test Results

| ASR Well R7^a | | | |
|--------------------------------|------------------------------------|--|---------------------------------------|
| | Step Pumping Rate (gpm) | Drawdown^b (feet) | Specific Capacity (gpm/ft) |
| | 330 | 22.4 | 14.7 |
| | 530 | 40.1 | 13.2 |
| | 960 | 73.9 | 13.0 |
| Design Rate | 700 | 53.0 | 13.2 |

| ASR Well R8^c | | | |
|--------------------------------|--------------------------------------|----------------------------|---------------------------------------|
| | Step Discharge Rate (gpm) | Drawdown (feet) | Specific Capacity (gpm/ft) |
| | 290 | 22.4 | 12.9 |
| | 570 | 45.9 | 12.4 |
| | 940 | 79.9 | 11.8 |
| Design Rate | 700 | 58.0 | 12.1 |

| ASR Well R9^d | | | |
|--------------------------------|--------------------------------------|----------------------------|---------------------------------------|
| | Step Discharge Rate (gpm) | Drawdown (feet) | Specific Capacity (gpm/ft) |
| | 300 | 14.0 | 21.4 |
| | 600 | 31.5 | 19.0 |
| | 1,070 | 58.0 | 18.4 |
| Design Rate | 700 | 34.0 | 20.6 |

| ASR Well R10^e | | | |
|---------------------------------|--------------------------------------|----------------------------|---------------------------------------|
| | Step Discharge Rate (gpm) | Drawdown (feet) | Specific Capacity (gpm/ft) |
| | 320 | 2.2 | 145.5 |
| | 590 | 5.9 | 100.0 |
| | 1,200 | 18.5 | 64.9 |
| Design Rate | 700 | 9.0 | 77.8 |

^aMay 5, 1998; static water level was 9.51 ft below temporary MP.

^bDrawdown at design rate is interpolated for each well; it does not include effects of interference.

^cApril 22, 1998; static water level was 8.33 ft below temporary MP.

^dApril 13, 1998; static water level was 9.50 ft below temporary MP.

^eApril 17, 1998; static water level was 8.75 ft below temporary MP.

MP measuring point
gpm gallons per minute

3.3 Constant Rate Pumping Tests

The constant rate pumping tests were performed to investigate the hydraulic properties of the aquifer in the vicinity of each new well. Testing involved pumping each well at a constant rate for approximately 24 hours. Test results were used to estimate the recharge and recovery rates for each well.

During each constant rate test, drawdowns were recorded for the pumping well, each new ASR well, and selected existing ASR wells. Drawdown data from the pumping well were analyzed using the Cooper and Jacob method (1946). Drawdown data from the other three new wells (used as observation wells) were analyzed using the Hantush and Jacob method (1955) for semi-confined aquifers. The results of these analyses are summarized in Exhibits 3-2 through 3-6.

The appearance of the pumping well's drawdown curves suggests that a recharge boundary was encountered soon after pumping started. This is evident by the pronounced decrease in the slope of the drawdown curves. This effect was observed in the drawdown curves of the observation wells, indicating that steady-state conditions were reached.

The aquifer's response to the pump tests indicates that an effective recharge source exists in the vicinity of the wells. The large variations in the calculated aquifer transmissivity may reflect the proximity of each well to the recharge source. The results indicate wells R-7 and R-8 have similar transmissivity values, but are much lower than wells R-9 and R-10. The calculated aquifer parameters are summarized in Exhibit 3-2. Drawdown data for each test is summarized in Exhibits 3-2 through 3-6.

3.4 Geophysical Logging

Geophysical logging provides information on the subsurface hydrogeology and documents borehole conditions before recharge and recovery operations are conducted. After acidization, geophysical logging was conducted on each ASR well before and during pumping tests. Gamma, long-short normal (LSN) electric, spontaneous potential, temperature, fluid resistivity, and caliper logs were conducted under static conditions. Temperature, fluid resistivity, and flowmeter logs were obtained under pumping conditions.

The logs indicate that most water production originates in the borehole section between the casing bottom (300 feet), approximately 330 ft bls. A summary of the logging conducted on each well is presented in Exhibits 3-7 through 3-10. Geophysical logs are presented in their entirety in Appendix C.

3.5 Water Quality Testing

Water quality samples were obtained from the four new wells during reverse-air drilling of the open hole sections. During drilling, the water samples were obtained from the drilling discharge at 10-foot-deep intervals. These samples were analyzed for standard parameters in the Cocoa Dyal WTP laboratory and are contained in Appendix A-1.

EXHIBIT 3-2
Summary of Calculated Aquifer Properties – Pump Tests of New ASR Wells

| Parameter | ASR Well | | | |
|--|----------|--------|--------|---------|
| | R7 | R8 | R9 | R10 |
| Transmissivity Average gal/day/ft | 19,750 | 26,250 | 70,000 | 175,333 |
| Storage Coefficient Average (Dimensionless) | 0.0002 | 0.0001 | 0.0002 | 0.0005 |
| Leakance Average ft/day gal/day/ft | 0.0053 | 0.0053 | 0.0060 | 0.0138 |

gallons per day per feet

EXHIBIT 3-3
Summary of 24-Hour Constant Rate Pumping Test – ASR Well R7 (Pumping Rate 880 GPM)

| Observation Point | Distance from Pumped Well (feet) | Drawdown at End of Test (feet) | Calculated Transmissivity (gal/day/ft) | Calculated Storage Coefficient | Calculated Leakance/Day |
|-------------------|----------------------------------|--------------------------------|--|--------------------------------|-------------------------|
| R-7 | -- | 74.2 | 23,000 | NC | NC |
| R-1 | 2,170 | 0.55 | NC | NC | NC |
| R-2 | 1,210 | 1.03 | NC | NC | NC |
| R-3 | 1,830 | 0.73 | NC | NC | NC |
| R-6 | 1,460 | 1.10 | NC | NC | NC |
| R-8 | 555 | 5.76 | 31,000 | 0.0002 | 0.0034 |
| R-9 | 1,110 | 2.09 | 86,000 | 0.0002 | 0.0023 |
| R-10 | 1,665 | 0.22 | NC | NC | NC |

NC not calculated

Water samples were also obtained during the step tests and the constant rate pumping tests. Samples were collected at selected intervals for field analysis including conductivity, chloride, pH, dissolved oxygen (DO), and turbidity. The results are also presented in Appendix A-1.

At the end of the constant rate tests, an additional sample was collected from each well to conduct an FDEP primary and secondary drinking water quality scan (excluding asbestos and primary pesticides). The results are summarized in Section 4, and copies of the complete analyses are presented in Appendix A-2.

EXHIBIT 3-4

Summary of 24-Hour Constant Rate Pumping Test – ASR Well R8 (Pumping Rate 920 GPM)

| Observation Point | Distance from Pumped Well (feet) | Drawdown at End of Test (feet) | Calculated Transmissivity (gal/day/ft) | Calculated Storage Coefficient | Calculated Leakance/Day |
|-------------------|----------------------------------|--------------------------------|--|--------------------------------|-------------------------|
| R-8 | -- | 79.50 | 24,000 | NC | NC |
| R-1 | 2,730 | 0.13 | NC | NC | NC |
| R-2 | 1,730 | 0.13 | NC | NC | NC |
| R-3 | 2,320 | 0.14 | NC | NC | NC |
| R-6 | 1,880 | 0.15 | NC | NC | NC |
| R-7 | 555 | 6.37 | 31,000 | 0.0002 | 0.0033 |
| R-9 | 555 | 7.57 | 39,000 | 0.0001 | 0.0015 |
| R-10 | 1,110 | 0.79 | 180,000 | 0.0005 | 0.0095 |

EXHIBIT 3-5

Summary of 24-Hour Constant Rate Pumping Test – ASR Well R9 (Pumping Rate 1,060 GPM)

| Observation Point | Distance from Pumped Well (feet) | Drawdown at End of Test (feet) | Calculated Transmissivity (gal/day/ft) | Calculated Storage Coefficient | Calculated Leakance/Day |
|-------------------|----------------------------------|--------------------------------|--|--------------------------------|-------------------------|
| R-9 | -- | 61.9 | 27,000 | NC | NC |
| R-1 | 3,280 | 0.13 | NC | NC | NC |
| R-2 | 2,260 | 0.13 | NC | NC | NC |
| R-3 | 2,820 | 0.14 | NC | NC | NC |
| R-6 | 2,360 | 0.15 | NC | NC | NC |
| R-7 | 1,110 | 2.80 | 34,000 | 0.0002 | 0.0037 |
| R-8 | 555 | 9.11 | 24,000 | 0.0001 | 0.0026 |
| R-10 | 555 | 1.87 | 130,000 | 0.0004 | 0.014 |

EXHIBIT 3-6**Summary of 24-Hour Constant Rate Pumping Test – ASR Well R10 (Pumping Rate 1,220 GPM)**

| Observation Point | Distance from Pumped Well (feet) | Drawdown at End of Test (feet) | Calculated Transmissivity (gal/day/ft) | Calculated Storage Coefficient | Calculated Leakage/Day |
|--------------------------|---|---------------------------------------|---|---------------------------------------|-------------------------------|
| R-10 | -- | 18.3 | 181,000 | NC | NC |
| R-1 | NM | NM | NC | NC | NC |
| R-2 | NM | NM | NC | NC | NC |
| R-3 | NM | NM | NC | NC | NC |
| R-6 | NM | NM | NC | NC | NC |
| R-7 | 1,665 | 0.49 | 25,000 | 0.0004 | 0.0110 |
| R-8 | 1,110 | 1.4 | 22,000 | 0.0001 | 0.0094 |
| R-9 | 555 | 2.33 | 124,000 | 0.0003 | 0.013 |

NM not measured





Exhibit 3-7 (1 of 2). Summary of Geophysical Logs for Well R-7.

Pumping







Exhibit 3-8 (1 of 2). Summary of Geophysical Logs for Well R-8.

Pumping







Exhibit 3-9 (1 of 2). Summary of Geophysical Logs for Well R-9.

Pumping



Static





Exhibit 3-10 (1 of 2). Summary of Geophysical Logs for Well R-10.

Pumping



4. Summary and Discussion of Results

Four ASR wells were drilled and tested at the City of Cocoa Dyal WTP as part of its existing ASR facility expansion. Each well is complete with a final casing string of nominal 16-inch-diameter PVC casing set into the top of the Floridan aquifer. Each well is of open hole construction. The construction described in this report includes only the wells and the uppermost portion of the wellheads.

Pumping tests were conducted on each well, and aquifer parameters were calculated. In addition, water samples were obtained from each well location to determine water quality. Results from this project phase, and the step-injection tests to be conducted in June, 1999, will be used to obtain FDEP authorization for operational testing. The initial operational ASR cycle test is expected to begin in October, 1999.

4.1 Hydraulic Response of the Aquifer

The results of the testing indicate that the selected storage zone is semiconfined. Wells R-7, R-8, and R-9 generally exhibit transmissivities lower than the six existing ASR wells. The exception is Well R-10, where a higher transmissivity was observed. The minimal amount of drawdown observed in existing ASR wells R-1, R-2, R-3, and R-6 during constant rate testing indicates insignificant mutual interference between the two systems.

In the wells, pump test water level measurements were used to calculate drawdown and interference effects at design rates of recharge and recovery. These calculations were used to predict the recharge and recovery water levels in the new ASR wells, which are shown in Exhibit 4-1.

EXHIBIT 4-1
Target Recharge and Recovery Rates

| Well | Estimated Recovery Rate (gpm) | Estimated Drawdown ^a (feet) | Estimated Recharge Rate ^b (gpm) | Estimated Wellhead Pressure (psi) |
|--------------|-------------------------------|--|--|-----------------------------------|
| R-7 | 700 | 108 | 290 | 11 |
| R-8 | 700 | 118 | 270 | 11 |
| R-9 | 700 | 90 | 350 | 9 |
| R-10 | 700 | 22 | 350 | 1 |
| Total | 2,800 (4.0 mgd) | | 1,260 (1.8 mgd) | |

^aDrawdowns account for well interference; assume all wells pump at 700 gpm for 90 days.

^bActual recharge and recovery rates will vary as a result of hydraulic variations in the system.

4.2 Water Quality Observations

Native water quality in the ASR storage zone was observed to be fairly consistent at the four new well sites. Well R-10 exhibited the highest concentrations of dissolved constituents, with a chloride concentration of 572 milligrams per liter (mg/L) and a total dissolved solids concentration of 1,120 mg/L. The remaining wells exhibited water quality similar to existing ASR wells R-2 and R-3. Exhibit 4-2 presents a summary of each well's observed native water quality.

Water samples taken during the pumping tests indicate that water quality improved early in the pumping tests, reaching equilibrium before completion of pumping. This response is considered a result of a minimal acidization residual in the wells at the start of pumping tests. By test end, all acidization byproducts were purged from the wells.

The water produced from well R-10 exhibited elevated levels of turbidity during the step tests and the constant rate tests. At the end of the 24-hour test, the turbidity level measured 6.6 NTU, which exceeds the drinking water standard of 1.0 NTU. It is expected that turbidity levels in this well will reduce to acceptable standards with extended pumping.

4.3 Assessment of ASR Potential

Testing results indicate that the newly constructed wells are generally compatible with the ASR concept. The storage zone exhibits a satisfactory degree of confinement, and the overall aquifer response indicates a range of transmissivities acceptable for the intended recharge and recovery flows. The background water quality has apparently reached equilibrium at the pumping test rates, which further indicates adequate confinement of the storage zone.

The water quality and aquifer hydraulics near wells R-7, R-8, and R-9 appear similar to existing ASR wells R-3 and R-6. For this reason, potable water storage and recovery in these new wells is expected to be similar to wells R-3 and R-6. The water quality and aquifer hydraulics near well R-10 appear similar to existing well R-2. For this reason, the performance of well R-10 is expected to be similar to the performance of well R-2. Well R-10's relatively high specific capacity may require throttling of recharge and recovery flows.


EXHIBIT 4-2
Summary of Water Quality Testing of New ASR Wells

| Parameter | ASR Well | | | |
|--------------------------------------|------------------------------|-------|-------|-------|
| | R-7 | R-8 | R-9 | R-10 |
| pH | 7.33 | 7.97 | 7.65 | 7.09 |
| Total Alkalinity (as CaCo3) | 162 | 146 | 144 | 166 |
| Total Hardness (as CaCo3) | 450 | 388 | 394 | 516 |
| Non-Carbonate Hardness (as CaCo3) | 288 | 242 | 250 | 350 |
| Turbidity (NTU) | 0.14 | 0.4 | 0.8 | 6.6 |
| Chloride (mg/L) | 500 | 422 | 417 | 572 |
| Sulfate (mg/L) | 34.9 | 78.3 | 75.4 | 83.1 |
| Calcium (mg/L) | 306 | 290 | 258 | 358 |
| Magnesium (mg/L) | 144 | 98 | 136 | 158 |
| Sodium (mg/L) | 240 | 225 | 232 | 292 |
| Total Dissolved Solids (mg/L) | 1,140 | 1,070 | 934 | 1,120 |
| Iron (mg/L) | 0.031 | 0.018 | 0.027 | 0.039 |
| Color (mg/L) | 10 | 7 | 10 | 10 |
| Fluoride (mg/L) | 0.6 | 1.0 | 1.1 | 0.9 |
| Conductivity (µmho/cm) | 1,838 | 1,625 | 1,779 | 2,240 |
| Field Hydrogen Sulfide (mg/L) | 2.1 | 1.9 | 3.3 | 2.6 |
| Field Dissolved Oxygen (mg/L) | 1.7 | 1.3 | 1.2 | 2.1 |
| CaCo3 | calcium carbonate | | | |
| µmho/cm | micromhos per centimeter | | | |
| mg/L | milligrams per liter | | | |
| NTU | nephelometric turbidity unit | | | |

5. Recommendations

As noted previously, the four new wells are part of the Dyal WTP expansion currently under construction. Following completion of piping, pump installation, wellhead facilities, and the plantwide SCADA (Supervisory Control and Data Acquisition) system, well R-10 should be pumped to waste for one to three days to reduce turbidity levels. During this time, water quality should be frequently monitored for turbidity.

As described in CH2M HILL's *Application to Construct Four Class V, Group 7 ASR Wells – City of Cocoa Dyal WTP* (September 1996), a common piping manifold connected to Dyal plant piping will connect the four wells. The new ASR wells will use low-pressure, gravity-fed recharge flows from the available head at the ground storage tanks (GST) located on the Dyal plant site's northern side. Upon completion of these facilities, an initial system performance acceptance test (PAT) and step-injection tests of the new wells will be conducted. The system performance acceptance and step-injection testing is designed to verify overall system operation and well performance; completion will require three to five days. The tests will represent initial operation and will be designed to verify the predicted behavior of the new systems.

During testing, recharge will occur for about four hours under gravity flow from the GSTs; recovery will begin immediately after recharge. All recovered flows will be diverted to the Dyal WTP's raw water intake. Following written approval from FDEP, an initial ASR cycle testing program will be conducted. 

An initial target volume of potable water will be injected to establish a water quality buffer, followed by the first cycle storage volume. The injected water will be obtained from the onsite GSTs, and will be injected by gravity flow into the four new wells over a four- to five-week span. Following a few days of storage in the aquifer, the storage volume will be recovered to the Dyal WTP's raw water intake. Water quality will be monitored daily during the initial recovery cycle, until 100 percent recovery of the storage volume is reached. Estimates of buffer, storage, and recovery volumes will be developed following the completion of the PATs, and will be provided in the cycle test plan.

The test cycle will demonstrate each new ASR well's hydraulic and water quality response to recharge and recovery of potable water. During this time, adjustments may need to be made to the system hydraulics and control values within the piping system. The observed recovery water quality response for the wells will be used to finalize the operation plan for the ASR facility.

As per the UIC permit, an engineering report must be submitted to FDEP upon completion of testing. It must include a detailed analysis of all cycle testing, an operations and maintenance (O&M) section, with conclusions and recommendations and estimated ASR capacities for the wells.

Following FDEP acceptance of this report, it is anticipated that an "Authorization to Use Class V Well" will be issued to the City to allow routine operation of the new ASR wells as part of the public water supply system.

6. Works Cited

CH2M HILL. *Application to Construct Four Class V, Group 7 ASR Wells – City of Cocoa Dyal WTP*. September 1996.

CH2M HILL. *Aquifer Storage Recovery Feasibility Investigation – Final Report*. 1988.

CH2M HILL. *Results of Aquifer Storage Recovery Well Drilling and Testing*. 1990.

Cooper, H. H., Jr. and C.E. Jacob. A Generalized Graphical Method for Evaluating Formation Constants and Summarizing Well Field History. *Transaction, American Geophysical Union*. Vol.27. No. 4. 1946.

Hantush, M. S. and C. E. Jacob. Non-Steady Radial Flow in an Infinite Leaky Aquifer. *Transaction, American Geophysical Union*. Vol. 35. No. 6. 1955.



***Appendix A-1
Water Quality Results During
Drilling and Pumping Tests***

**CITY OF COCOA
ASR SYSTEM EXPANSION
WATER QUALITY DURING DRILLING**

ASR WELL R-7

| Date | Depth | Chlorides | Conductivity | pH | Alkalinity | Total Hardness | Calcium Hardness | Sulfates |
|------------|-------|-----------|--------------|------|------------|----------------|------------------|----------|
| Nov-6,1997 | 317 | 444 | 1698 | 8.00 | 136 | 378 | 280 | N/A |
| | 327 | 464 | 1709 | 8.02 | 140 | 376 | 240 | 40.1 |
| | 337 | 460 | 1752 | 8.24 | 134 | 356 | 248 | 43.4 |
| | 347 | 464 | 1692 | 8.12 | 130 | 376 | 282 | 39.1 |
| | 357 | 464 | 1689 | 8.10 | 130 | 366 | 266 | 75.9 |
| | 370 | 464 | 1681 | 8.10 | 136 | 370 | 246 | 33.9 |

**CITY OF COCOA
ASR SYSTEM EXPANSION
WATER QUALITY DURING DRILLING**

ASR WELL R-8

| Date | Depth | Chlorides | Conductivity | pH | Alkalinity | Total Hardness | Calcium Hardness | Sulfates |
|--------------|-------|-----------|--------------|------|------------|----------------|------------------|----------|
| Dec. 12-1997 | 317 | 438 | 1417 | 9.35 | 48 | 276 | 220 | 53.2 |
| | 327 | 447 | 1553 | 7.84 | 120 | 360 | 234 | 44.8 |
| | 337 | 450 | 1566 | 7.76 | 130 | 376 | 238 | 135 |
| | 347 | 460 | 1428 | 7.73 | 138 | 374 | 206 | 50.5 |
| | 357 | 434 | 1407 | 7.75 | 124 | 352 | 220 | 46.2 |
| | 370 | 450 | 1407 | 8.16 | 138 | 360 | 238 | 43.1 |

**CITY OF COCOA
ASR SYSTEM EXPANSION
WATER QUALITY DURING DRILLING**

ASR WELL R-9

| Date | Depth | Chlorides | Conductivity | pH | Alkalinity | Total Hardness | Calcium Hardness | Sulfates |
|---------|-------|-----------|--------------|------|------------|----------------|------------------|----------|
| 2/18/98 | 317 | 442 | 1728 | 8.16 | 132 | 346 | 240 | 34.75 |
| | 327 | 445 | 1775 | 7.81 | 146 | 374 | 246 | 39.7 |
| | 337 | 432 | 1743 | 7.90 | 130 | 356 | 224 | 38.47 |
| | 347 | 427 | 1715 | 7.98 | 118 | 354 | 248 | 36.72 |
| | 357 | 432 | 1704 | 8.09 | 110 | 340 | 256 | 38.45 |
| | 370 | 436 | 1889 | 8.07 | 154 | 376 | 256 | 28.89 |

**CITY OF COCOA
ASR SYSTEM EXPANSION
WATER QUALITY DURING DRILLING**

ASR WELL R-10

| Date | Depth | Chlorides | Conductivity | pH | Alkalinity | Total Hardness | Calcium Hardness | Sulfates |
|--------|-------|-----------|--------------|------|------------|----------------|------------------|----------|
| 4/6/98 | 317 | 530 | 1905 | 7.86 | 140 | 412 | 210 | 52.55 |
| | 327 | 532 | 1916 | 7.79 | 130 | 400 | 262 | 44.05 |
| | 337 | 530 | 1901 | 7.91 | 136 | 412 | 260 | 49.3 |
| | 347 | 560 | 1750 | 7.87 | 134 | 420 | 250 | 46.65 |
| | 357 | 540 | 1741 | 7.87 | 136 | 414 | 268 | 49.3 |
| | 370 | 508 | 1798 | 7.90 | 134 | 406 | 242 | 45.85 |

Cocoa ASR Expansion
April - May 1998
Pump Testing Water Quality

Well R-7

Step Test - May 5, 1998

| <u>Hours Pumping</u> | <u>Chlorides (mg/l)</u> | <u>Conductivity (umhos)</u> | <u>Turbidity (ntu)</u> | <u>pH</u> |
|----------------------|-------------------------|-----------------------------|------------------------|-----------|
| 2 | 780 | 2570 | 4.9 | 6.7 |
| 4 | 760 | 2440 | 8.7 | 6.7 |
| 6 | 592 | 2232 | 1.7 | 6.7 |

24 Hour Constant Rate Test - May 5-6, 1998

| <u>Hours Pumping</u> | <u>Chlorides (mg/l)</u> | <u>Conductivity (umhos)</u> | <u>Turbidity (ntu)</u> | <u>pH</u> | <u>D.O.</u> |
|----------------------|-------------------------|-----------------------------|------------------------|-----------|-------------|
| 2 | 580 | 2262 | 3.3 | 6.7 | |
| 6 | 562 | 1916 | 0.88 | 6.8 | |
| 12 | 534 | 1826 | 6.5 | 7.0 | |
| 18 | 508 | 1782 | 8.9 | 7.1 | |
| 22 | 518 | 1756 | 1.65 | 7.1 | |
| 24 | 524 | 1838 | 0.14 | 7.2 | 1.7 |

Cocoa ASR Expansion
April - May 1998
Pump Testing Water Quality

Well R-8

Step Test - April 22, 1998

| <u>Hours Pumping</u> | <u>Chlorides (mg/l)</u> | <u>Conductivity (umhos)</u> | <u>Turbidity (ntu)</u> | <u>pH</u> |
|----------------------|-------------------------|-----------------------------|------------------------|-----------|
| 2 | 616 | 2690 | 3.9 | 6.7 |
| 4 | 554 | 2360 | 2 | 6.8 |
| 6 | 532 | 2150 | 0.44 | 6.9 |

24 Hour Constant Rate Test - April 27-28, 1998

| <u>Hours Pumping</u> | <u>Chlorides (mg/l)</u> | <u>Conductivity (umhos)</u> | <u>Turbidity (ntu)</u> | <u>pH</u> | <u>D.O.</u> |
|----------------------|-------------------------|-----------------------------|------------------------|-----------|-------------|
| 6 | 496 | 1828 | 0.34 | 7.2 | |
| 12 | 480 | 1767 | 0.72 | 7.2 | |
| 18 | 480 | 1729 | 5.47 | 7.3 | |
| 22 | 476 | 1700 | 0.18 | 7.4 | |
| 24 | 458 | 1625 | 0.4 | 7.5 | 1.3 |

Cocoa ASR Expansion
April - May 1998
Pump Testing Water Quality

Well R-9

Step Test - April 13, 1998

| <u>Hours Pumping</u> | <u>Chlorides (mg/l)</u> | <u>Conductivity (umhos)</u> | <u>Turbidity (ntu)</u> |
|----------------------|-------------------------|-----------------------------|------------------------|
| 2 | 680 | 2900 | 3.4 |
| 4 | 662 | 2450 | 2.9 |
| 5 | 628 | 2200 | 1.6 |

24 Hour Constant Rate Test - April 14-15, 1998

| <u>Hours Pumping</u> | <u>Chlorides (mg/l)</u> | <u>Conductivity (umhos)</u> | <u>Turbidity (ntu)</u> | <u>pH</u> | <u>D.O.</u> |
|----------------------|-------------------------|-----------------------------|------------------------|-----------|-------------|
| 6 | 492 | 2050 | 0.8 | 7.1 | |
| 12 | 476 | 1860 | 0.8 | 7.2 | |
| 18 | 460 | 1828 | 1.1 | | |
| 22 | 462 | 1782 | 0.9 | | |
| 24 | 462 | 1779 | 0.8 | 7.4 | 1.2 |

**Cocoa ASR Expansion
 April - May 1998
 Pump Testing Water Quality**


Well R-10

Step Test - April 17, 1998

| <u>Hours Pumping</u> | <u>Chlorides (mg/l)</u> | <u>Conductivity (umhos)</u> | <u>Turbidity (ntu)</u> |
|----------------------|-------------------------|-----------------------------|------------------------|
| 2 | 836 | 3040 | 478 |
| 4 | 942 | 3190 | 39 |
| 6 | 850 | 3120 | 105 |

24 Hour Constant Rate Test - April 20-21, 1998

| <u>Hours Pumping</u> | <u>Chlorides (mg/l)</u> | <u>Conductivity (umhos)</u> | <u>Turbidity (ntu)</u> | <u>pH</u> | <u>D.O</u> |
|----------------------|-------------------------|-----------------------------|------------------------|-----------|------------|
| 8 | 630 | 2516 | 19 | 6.7 | |
| 12 | 624 | 2504 | 6.6 | 6.9 | |
| 16 | 597 | 2376 | 17.4 | 7.1 | |
| 20 | 578 | NA | NA | 7.1 | |
| 22 | 576 | NA | 5.2 | NA | |
| 23 | 586 | 2280 | 5.8 | NA | |
| 24 | 610 | 2240 | 6.6 | 7.1 | 2.1 |



***Appendix A-2
FDEP Primary and Secondary
Drinking Water Analyses***

LAB FORMAT FOR REPORTING DRINKING WATER ANALYSES

PUBLIC WATER SYSTEM INFORMATION (to be completed by system or lab)

System Name: CITY OF COCA I.D. #: 3050223
 A: 600 SCHOOL ST, COCOA, FL 32922 Phone #: 568-5867
 Type (check one) Community Nontransient Noncommunity Noncommunity

SAMPLE INFORMATION (to be completed by sampler)

Sample Date (MMDDYY): 05/07/98 Sample Time: 0845
 Sample Location (be specific): R-7
 Sampler Name and Phone: MARY KRALJ
 Sampler's Signature: *Mary Kralj* Title: Laboratory Technician
 Check Types(s) Distribution Recheck of MCL Resample of Lab Invalidated Sample
 Clearance Thm Max Res Time Plant Tap
 Distrib entry pt Raw Composite of Multiple Sites--Attach a format for each site

LABORATORY CERTIFICATION INFORMATION (to be completed by lab) - attach HRS Analyte Sheet *

Lab Name: BIONOMICS LABORATORY HRS#: 83331 Expiration Date: 06/30/98
 Address: 4310 E. Anderson Rd., Orlando, FL 32812 Phone: 851-2560
 Subcontracted Lab HRS#: 83141 -ATTACH HRS ANALYTE SHEET FOR SUBCONTRACTED LAB, TOO *

ANALYSIS INFORMATION: (to be completed by lab)

Work Order Number: B805110-01

Date Sample(s) Received: 05/07/98 Group(s) Analyzed & Results attached for compliance with 62-550, F.A.C.:

- | | | | |
|---|---|--|--|
| <input type="checkbox"/> Nitrate Only | <input type="checkbox"/> Nitrite Only | <input type="checkbox"/> Asbestos Only | <input type="checkbox"/> Trihalomethanes |
| Inorganics-- | Volatile Organics-- | Secondaries-- | Pesticide/PCBs-- |
| <input type="checkbox"/> All 17 <input checked="" type="checkbox"/> Partial | <input checked="" type="checkbox"/> All 21 <input type="checkbox"/> Partial | <input type="checkbox"/> All <input checked="" type="checkbox"/> Partial | <input type="checkbox"/> All 30 <input checked="" type="checkbox"/> Partial |
| Group I Unregulateds-- | Group II Unregulateds-- | Group III Unregulateds-- | Radiochemicals-- |
| <input type="checkbox"/> All 13 <input type="checkbox"/> Partial | <input type="checkbox"/> All 23 <input type="checkbox"/> Partial | <input type="checkbox"/> All <input type="checkbox"/> Partial | <input checked="" type="checkbox"/> Single Sample <input type="checkbox"/> Qtrly Composite ** |

**Provide radiochemical sample dates & locations for each quarter

I, MARK RUSLER, do HEREBY CERTIFY that all attached analytical data are correct.
 Signature: *Mark Rusler*
 Title: CHEMIST Date: 6/1/98

COMPLIANCE INFORMATION (to be completed by State)

Sample Collection Satisfactory: _____ Sample Analysis Satisfactory: _____
 Resample Requested For: _____ Reason: _____
 Date Notified to resample: _____ Date Notified: _____
 DEP/HRS Reviewing Official: _____

*All HRS lab #s and their HRS Analyte Sheet for labs performing the attached water analyses must be provided. Failure to do so will result in rejection of the analyses and possible enforcement against the public water system for failure to sample.

BIONOMICS LABORATORY

4310 E. Anderson Rd.

Orlando, FL 32812

DHRS/DEP #83331; E83012

(407) 851-2560 FAX:(407) 856-0886

For Lab Use Only

Date Received: 05/07/98

Time Received: 0955

Signature of Lab Official:

Mark Kusler

**DRINKING WATER
BACTERIOLOGICAL ANALYSIS**

System Name: CITY OF COCOA System ID #: 3050223 System Phone#: (407)568-5867
Address: 600 SCHOOL ST. County: _____ DEP District: _____
Collector: MARY KRALJ Collector Phone#: (407)568-5867

Sample Site (locality or subdivision): R-7

Date and Time Collected: 05/7/98 @ 0845

Type of Supply: Community water system Noncommunity water system Nontransient-noncommunity water sys.
Private well Swimming pool Bottled water Other public water system

Type of Sample: Compliance Repeat Replacement Main Clearance Well Survey Other: _____
(circle one) (check box) (check box) (specify)
[] Distribution [] TNTC or C
[] Raw [] Turbid

Remarks:

| BE COMPLETED BY COLLECTOR OF SAMPLE | | | |
|-------------------------------------|---------------------------------|--------|----|
| Coll No: | Sample Point (Specific Address) | Cl Res | pH |
| | R-7 | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| TO BE COMPLETED BY LAB: | | | | |
|---|--------------|--------|---------------|---------------|
| Date & time of analysis: 05/07/98 @ 1759 | | by: LH | | |
| Analysis Method: MF MTF MMO-MUG PA | | | | |
| Sample Number: | Non Coliform | *Total | Confirm Total | Confirm Fecal |
| B805110-01 | | A | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

* Results in this column are preliminary. Fecal coliform confirmation on community and noncommunity water systems and total coliform confirmation on all types of water systems will follow in 24-48 hours.

P - Coliforms are present C - Confluent growth TA - Turbid, Absence of gas or acid
A - Coliforms are absent TNTC - Too numerous to count

INTERPRETATIONS - REMARKS BY PROGRAM REVIEWER

Name and Mailing Address of Person/Firm to Receive Report:

CITY OF COCOA
600 SCHOOL ST.
COCO A, FL 32922
ATTN: MARY KRALJ

- []
- [] Satisfactory
- [] Incomplete collection information
- [] Repeat samples
- [] Replacement samples

Reviewing Official: _____

Title: _____

INORGANIC ANALYSIS

62-550-310(1)

(PWS030)

| ID | Name | (MCL mg/L) | Sample Number | Analysis | | Analysis Method | Analysis Date | MDL(mg/L) | Lab ID |
|------|-----------|------------|---------------|--------------|---|-----------------|---------------|-----------|--------|
| | | | | Result(mg/L) | Q | | | | |
| 1005 | Arsenic | (0.05) | B805110-01 | < 0.0034 | U | 200.9 | 5/11/98 | 0.0034 | 83331 |
| 1010 | Barium | (2) | B805110-01 | 0.05 | | 200.7 | 5/11/98 | 0.002 | 83331 |
| 1015 | Cadmium | (.005) | B805110-01 | < 0.0001 | | 200.9 | 5/11/98 | 0.0001 | 83331 |
| 1020 | Chromium | (0.1) | B805110-01 | < 0.0002 | U | 200.9 | 5/11/98 | 0.0002 | 83331 |
| 1024 | Cyanide | (0.2) | B805110-01 | < 0.006 | U | SM4500CN E | 5/11/98 | 0.006 | 83331 |
| 1025 | Fluoride | (4) | B805110-01 | 0.606 | | SM 4500F C | 5/7/98 | 0.027 | 83331 |
| 1030 | Lead | (0.015) | B805110-01 | < 0.001 | U | 200.9 | 5/11/98 | 0.001 | 83331 |
| 1035 | Mercury | (0.002) | B805110-01 | < 0.00005 | | 245.1 | 5/12/98 | 0.00005 | 83331 |
| 1036 | Nickel | (0.1) | B805110-01 | < 0.012 | U | 200.7 | 5/12/98 | 0.012 | 83331 |
| 1040 | Nitrate | (10) | B805110-01 | < 0.006 | U | 300.0A | 5/7/98 | 0.006 | 83331 |
| 1041 | Nitrite | (1) | B805110-01 | < 0.004 | U | 300.0A | 5/7/98 | 0.004 | 83331 |
| 1045 | Selenium | (0.05) | B805110-01 | < 0.002 | U | 200.9 | 5/11/98 | 0.002 | 83331 |
| 1052 | Sodium | (160) | B805110-01 | 240 | | 200.7 | 5/12/98 | 0.1 | 83331 |
| 1074 | Antimony | (0.006) | B805110-01 | 0.002 | I | 200.9 | 5/12/98 | 0.0017 | 83331 |
| 1075 | Beryllium | (0.004) | B805110-01 | 0.0013 | | 200.7 | 5/11/98 | 0.0003 | 83331 |
| 1085 | Thallium | (0.002) | B805110-01 | < 0.0006 | U | 200.9 | 5/12/98 | 0.0006 | 83331 |
| 1094 | Asbestos | (7 MFL) | | | | NA | | | |

SECONDARY CHEMICAL ANALYSIS

62-550.320

(PWS031)

| ID | Name | (MCL mg/L) | Sample Number | Analysis | | Analysis Method | Analysis Date | MDL(mg/L) | Lab ID |
|------|------------------------|-----------------|---------------|--------------|---|-----------------|---------------|-----------|--------|
| | | | | Result(mg/L) | Q | | | | |
| 1002 | Aluminum | (0.2) | B805110-01 | < 0.036 | U | 200.7 | 5/11/98 | 0.036 | 83331 |
| 1017 | Chloride | (250) | B805110-01 | 500 | | 300.0A | 5/7/98 | 0.074 | 83331 |
| 1022 | Copper | (1) | B805110-01 | < 0.004 | U | 200.7 | 5/12/98 | 0.004 | 83331 |
| 1025 | Fluoride | (2.0) | B805110-01 | 0.606 | | SM 4500F C | 5/7/98 | 0.027 | 83331 |
| 1028 | Iron | (0.3) | B805110-01 | 0.031 | | 200.7 | 5/12/98 | 0.006 | 83331 |
| 1032 | Manganese | (0.05) | B805110-01 | < 0.002 | U | 200.7 | 5/12/98 | 0.002 | 83331 |
| 1050 | Silver | (0.1) | B805110-01 | < 0.009 | U | 200.7 | 5/11/98 | 0.009 | 83331 |
| 1055 | Sulfate | (250) | B805110-01 | 34.9 | | 300.0A | 5/7/98 | 0.03 | 83331 |
| 1095 | Zinc | (5) | B805110-01 | 0.006 | I | 200.7 | 5/12/98 | 0.006 | 83331 |
| 1905 | Color | (15color units) | B805110-01 | 10 | | SM2120B | 5/7/98 | 5 | 83331 |
| 1920 | Odor | (3 T.O.N.) | B805110-01 | > 32 | | SM2150B | 5/7/98 | 1 | 83331 |
| 1925 | pH | (6.5-8.5) | B805110-01 | 7.33 | | 150.1 | 5/7/98 | | 83331 |
| 1927 | Total Dissolved Solids | (500) | B805110-01 | 1140 | | SM2540C | 5/12/98 | 4.41 | 83331 |
| 2 | Foaming Agents | (0.5) | B805110-01 | < 0.02 | U | SM5540C | 5/9/98 | 0.02 | 83331 |

TRIALOMETHANE ANALYSIS

62-550-310(a)

(PWS027)

| ID | Name | Sample Number | CL Resid | Analysis Result(mg/L) | Q | Analysis Method | Analysis Date | MDL(mg/L) | Lab ID |
|------|------------|---------------|----------|-----------------------|---|-----------------|---------------|-----------|--------|
| 2950 | Total THMs | | | | | 524.2 | | 0.0011 | |

RADIOCHEMICAL ANALYSIS*

62-550.310(5)

(PWS033)

| ID | Name | Sample Number | Analysis Result(pCi/l) | Analysis Method | Analysis Date | Error | Lab ID |
|------|-----------------|---------------|------------------------|-----------------|---------------|-------|--------|
| 4000 | Gross Alpha | B805110-01 | 4.4 | 900.0 | 5/14/98 | ±2.7 | 83141 |
| 4012 | Photon Emitters | | | | | | |
| 4020 | Radium-226 | B805110-01 | 1.1 | 903.1 | 5/18/98 | ±0.2 | 83141 |
| 4030 | Radium-228 | B805110-01 | < 0.9 | RA-5 | 5/18/98 | ±0.6 | 83141 |
| 4101 | Man-made beta | | | | | | |

*(Gross alpha generally only requirement, see 62-550.519,(FAC)

VOLATILE ORGANIC ANALYSIS

62-550.310(2)(b)

(PWS028)

| ID | Name | (MCL ug/L) | Sample Number | Analysis Result(µg/L) | Q | Analysis Method | Analysis Date | MDL(µg/L) | Lab ID |
|------|----------------------------|------------|---------------|-----------------------|---|-----------------|---------------|-----------|--------|
| 2370 | 1,2,4-Trichlorobenzene | (70) | B805110-01 | < 0.22 | U | 524.2 | 5/7/98 | 0.22 | 83331 |
| 2380 | Cis-1,2-dichloroethylene | (70) | B805110-01 | < 0.03 | U | 524.2 | 5/7/98 | 0.03 | 83331 |
| 2955 | Xylenes (total) | (10000) | B805110-01 | < 0.24 | U | 524.2 | 5/7/98 | 0.24 | 83331 |
| 2964 | Dichloromethane | (5) | B805110-01 | < 0.31 | U | 524.2 | 5/7/98 | 0.31 | 83331 |
| 2968 | O-dichlorobenzene | (600) | B805110-01 | < 0.05 | U | 524.2 | 5/7/98 | 0.05 | 83331 |
| 2969 | Para-dichlorobenzene | (75) | B805110-01 | < 0.02 | U | 524.2 | 5/7/98 | 0.02 | 83331 |
| 2976 | Vinyl Chloride | (1) | B805110-01 | < 0.29 | U | 524.2 | 5/7/98 | 0.29 | 83331 |
| 2977 | 1,1-dichloroethylene | (7) | B805110-01 | < 0.02 | U | 524.2 | 5/7/98 | 0.02 | 83331 |
| 2979 | Trans-1,2-dichloroethylene | (100) | B805110-01 | < 0.12 | U | 524.2 | 5/7/98 | 0.12 | 83331 |
| 2980 | 1,2-dichloroethane | (3) | B805110-01 | < 0.02 | U | 524.2 | 5/7/98 | 0.02 | 83331 |
| 2981 | 1,1,1-trichloroethane | (200) | B805110-01 | < 0.21 | U | 524.2 | 5/7/98 | 0.21 | 83331 |
| 2982 | Carbon tetrachloride | (3) | B805110-01 | < 0.29 | U | 524.2 | 5/7/98 | 0.29 | 83331 |
| 2983 | 1,2-dichloropropane | (5) | B805110-01 | < 0.33 | U | 524.2 | 5/7/98 | 0.33 | 83331 |
| 2984 | Trichloroethylene | (3) | B805110-01 | < 0.02 | U | 524.2 | 5/7/98 | 0.02 | 83331 |
| 2985 | 1,1,2-trichloroethane | (5) | B805110-01 | < 0.23 | U | 524.2 | 5/7/98 | 0.23 | 83331 |
| 2987 | Tetrachloroethylene | (3) | B805110-01 | < 0.21 | U | 524.2 | 5/7/98 | 0.21 | 83331 |
| 2989 | Monochlorobenzene | (100) | B805110-01 | < 0.23 | U | 524.2 | 5/7/98 | 0.23 | 83331 |
| 2990 | Benzene | (1) | B805110-01 | < 0.05 | U | 524.2 | 5/7/98 | 0.05 | 83331 |
| 2991 | Toluene | (1000) | B805110-01 | < 0.41 | U | 524.2 | 5/7/98 | 0.41 | 83331 |
| | Ethylbenzene | (700) | B805110-01 | < 0.47 | U | 524.2 | 5/7/98 | 0.47 | 83331 |
| 2990 | Styrene | (100) | B805110-01 | < 0.2 | U | 524.2 | 5/7/98 | 0.2 | 83331 |

PESTICIDE/PCB CHEMICAL ANALYSIS

62-550-310(2)(c)

(PWS029)

| ID | Name | (MCL ug/L) | Sample Number | Analysis | | Analysis Method | Analysis Date | MDL(µg/L) | Lab ID |
|------|---------------------------|------------|---------------|--------------|---|-----------------|---------------|-----------|--------|
| | | | | Result(µg/L) | Q | | | | |
| 2005 | Endrin | (2) | | | | 508 | | 0.002 | |
| 2010 | Lindane | (.2) | | | | 508 | | 0.002 | |
| 2015 | Methoxychlor | (40) | | | | 508 | | 0.052 | |
| 2020 | Toxaphene | (3) | | | | 508 | | 0.309 | |
| 2031 | Dalapon | (200) | | | | 515.1 | | 0.036 | |
| 2032 | Diquat | (20) | | | | 549.1 | | 0.26 | |
| 2033 | Endothall | (100) | | | | 548.1 | | 15.4 | |
| 2034 | Glyphosate | (700) | | | | 547 | | 9.44 | |
| 2035 | Di(2-ethylhexyl)adipate | (400) | | | | 525.2 | | 0.71 | |
| 2036 | Oxamyl (Vydate) | (200) | | | | 531.1 | | 2.57 | |
| 2037 | Simazine | (4) | | | | 507 | | 0.078 | |
| 2039 | Di(2-ethylhexyl)phthalate | (6) | | | | 525.2 | | 1.15 | |
| 2040 | Picloram | (500) | | | | 515.1 | | 0.029 | |
| 2041 | Dinoseb | (7) | | | | 515.1 | | 0.055 | |
| 2042 | Hexachlorocyclopentadiene | (50) | | | | 525.2 | | 0.292 | |
| 2046 | Carbofuran | (40) | | | | 531.1 | | 7.04 | |
| 2050 | Atrazine | (3) | | | | 507 | | 0.035 | |
| 2051 | Alachlor | (2) | | | | 507 | | 0.012 | |
| 2063 | 2,3,7,8-TCDD(Dioxin) | (.00003) | | | | --- | | | |
| 2065 | Heptachlor | (.4) | | | | 508 | | 0.004 | |
| 2067 | Heptachlor Epoxide | (.2) | | | | 508 | | 0.002 | |
| 2100 | 2,4-D | (70) | | | | 515.1 | | 0.026 | |
| 2102 | 2,4,5-TP (Silvex) | (50) | | | | 515.1 | | 0.017 | |
| 2274 | Hexachlorobenzene | (1) | | | | 508 | | 0.008 | |
| 2306 | Benzo(a)pyrene | (.2) | | | | 550.1 | | 0.013 | |
| 2326 | Pentachlorophenol | (1) | | | | 515.1 | | 0.007 | |
| 2383 | PCB | (.5) | B805110-01 | < 0.1 | U | 508 | 5/27/98 | 0.1 | 83331 |
| 2931 | Dibromochloropropane | (.2) | | | | 504.1 | | 0.004 | |
| 2946 | Ethylene Dibromide | (.02) | | | | 504.1 | | 0.006 | |
| 2959 | Chlordane | (2) | | | | 508 | | 0.446 | |

UNREGULATED GROUP I ANALYSIS

62-550.405

(PWS035)

| ID | Name | Sample Number | Analysis | | Analysis Method | Analysis Date | MDL(µg/L) | Lab ID |
|------|---------------------|---------------|--------------|---|-----------------|---------------|-----------|--------|
| | | | Result(µg/L) | Q | | | | |
| 2021 | Carbaryl | | | | 531.1 | | 3.89 | |
| 2022 | Methomyl | | | | 531.1 | | 3.20 | |
| 2043 | Aldicarb Sulfoxide | | | | 531.1 | | 1.88 | |
| 2044 | Aldicarb Sulfone | | | | 531.1 | | 5.57 | |
| 2045 | Metolachlor | | | | 507 | | 0.108 | |
| 2047 | Aldicarb | | | | 531.1 | | 5.95 | |
| 2066 | 3-Hydroxycarbofuran | | | | 531.1 | | 3.35 | |
| 2077 | Butachlor | | | | 507 | | 0.021 | |
| 2102 | Propachlor | | | | 508 | | 0.110 | |
| 2300 | Aldrin | | | | 508 | | 0.003 | |
| 2364 | Dieldrin | | | | 508 | | 0.002 | |
| 2440 | Dicamba | | | | 515.1 | | 0.005 | |
| 2595 | Metribuzin | | | | 507 | | 0.024 | |

LAB FORMAT FOR REPORTING DRINKING WATER ANALYSES

PUBLIC WATER SYSTEM INFORMATION (to be completed by system or lab)

System Name: CITY OF COCA I.D. #: 3050223
Address: 600 SCHOOL ST, COCOA, FL 32922 Phone #: 407-568-5867
Type (check one) (X) Community () Nontransient Noncommunity () Noncommunity

SAMPLE INFORMATION (to be completed by sampler)

Sample Date (MMDDYY): 04/28/98 Sample Time: 1120
Sample Location (be specific): R-8
Sampler Name and Phone: MARY KRALJ
Sampler's Signature: [Signature] Title: Laboratory Technician
Check Types(s) () Distribution () Recheck of MCL () Resample of Lab Invalidated Sample
() Clearance () Thm Max Res Time () Plant Tap
() Distrib entry pt (X) Raw () Composite of Multiple Sites--Attach a format for each site

LABORATORY CERTIFICATION INFORMATION (to be completed by lab) -- attach HRS Analyte Sheet *

Lab Name: BIONOMICS LABORATORY HRS#: 83331 Expiration Date: 06/30/98
Address: 4310 E. Anderson Rd., Orlando, FL 32812 Phone: 851-2560
Subcontracted Lab HRS#: 83141 --ATTACH HRS ANALYTE SHEET FOR SUBCONTRACTED LAB, TOO *

ANALYSIS INFORMATION: (to be completed by lab)

Work Order Number: B804622-01
Date Sample(s) Received: 04/28/98 Group(s) Analyzed & Results attached for compliance with 62-550, F.A.C.:
() Nitrate Only () Nitrite Only () Asbestos Only () Trihalomethanes
Inorganics-- Volatile Organics-- Secondaries-- Pesticide/PCBs--
() All 17 (X) Partial (X) All 21 () Partial () All (X) Partial () All 30 (X) Partial
Group I Unregulated-- Group II Unregulated-- Group III Unregulated-- Radiochemicals--
() All 13 () Partial () All 23 () Partial () All () Partial (X) Single Sample
() Qtrly Composite **
**Provide radiochemical sample dates & locations for each quarter

I, MARK RUSLER, do HEREBY CERTIFY that all attached analytical data are correct.
Signature: [Signature]
Title: CHEMIST Date: 5/18/98

COMPLIANCE INFORMATION (to be completed by State)

Sample Collection Satisfactory: Sample Analysis Satisfactory:
Reason Requested For: Reason:
Notified to resample: Date Notified:
DEP/HRS Reviewing Official:

*All HRS lab #s and their HRS Analyte Sheet for labs performing the attached water analyses must be provided. Failure to do so will result in rejection of the analyses and possible enforcement against the public water system for failure to sample.

INORGANIC ANALYSIS

62-550-310(1)

(PWS030)

| ID | Name | (MCL mg/L) | Sample Number | Analysis | | Analysis Method | Analysis Date | MDL(mg/L) | Lab ID |
|------|-----------|------------|---------------|--------------|---|-----------------|---------------|-----------|--------|
| | | | | Result(mg/L) | Q | | | | |
| 1005 | Arsenic | (0.05) | B804622-01 | < 0.0034 | U | 200.9 | 5/5/98 | 0.0034 | 83331 |
| 1010 | Barium | (2) | B804622-01 | 0.403 | | 200.7 | 4/30/98 | 0.002 | 83331 |
| 1015 | Cadmium | (.005) | B804622-01 | < 0.0001 | | 200.9 | 5/4/98 | 0.0001 | 83331 |
| 1020 | Chromium | (0.1) | B804622-01 | < 0.0002 | U | 200.9 | 5/4/98 | 0.0002 | 83331 |
| 1024 | Cyanide | (0.2) | B804622-01 | < 0.006 | U | SM4500CN E | 4/30/98 | 0.006 | 83331 |
| 1025 | Fluoride | (4) | B804622-01 | 1 | | SM 4500F C | 5/5/98 | 0.027 | 83331 |
| 1030 | Lead | (0.015) | B804622-01 | < 0.001 | U | 200.9 | 5/4/98 | 0.001 | 83331 |
| 1035 | Mercury | (0.002) | B804622-01 | < 0.00005 | | 245.1 | 4/30/98 | 0.00005 | 83331 |
| 1036 | Nickel | (0.1) | B804622-01 | < 0.012 | U | 200.7 | 5/1/98 | 0.012 | 83331 |
| 1040 | Nitrate | (10) | B804622-01 | < 0.006 | U | 300.0A | 4/29/98 | 0.006 | 83331 |
| 1041 | Nitrite | (1) | B804622-01 | < 0.004 | U | 300.0A | 4/29/98 | 0.004 | 83331 |
| 1045 | Selenium | (0.05) | B804622-01 | 0.003 | I | 200.9 | 5/5/98 | 0.002 | 83331 |
| 1052 | Sodium | (160) | B804622-01 | 225 | | 200.7 | 5/1/98 | 0.1 | 83331 |
| 1074 | Antimony | (0.006) | B804622-01 | 0.002 | I | 200.9 | 5/5/98 | 0.0017 | 83331 |
| 1075 | Beryllium | (0.004) | B804622-01 | 0.0012 | | 200.7 | 5/4/98 | 0.0003 | 83331 |
| 1085 | Thallium | (0.002) | B804622-01 | < 0.0006 | U | 200.9 | 5/5/98 | 0.0006 | 83331 |
| 1094 | Asbestos | (7 MFL) | | | | NA | | | |

SECONDARY CHEMICAL ANALYSIS

62-550.320

(PWS031)

| ID | Name | (MCL mg/L) | Sample Number | Analysis | | Analysis Method | Analysis Date | MDL(mg/L) | Lab ID |
|------|------------------------|-----------------|---------------|--------------|----|-----------------|---------------|-----------|--------|
| | | | | Result(mg/L) | Q | | | | |
| 1002 | Aluminum | (0.2) | B804622-01 | < 0.036 | U | 200.7 | 5/4/98 | 0.036 | 83331 |
| 1017 | Chloride | (250) | B804622-01 | 422 | | 300.0A | 4/29/98 | 0.074 | 83331 |
| 1022 | Copper | (1) | B804622-01 | < 0.004 | U | 200.7 | 5/1/98 | 0.004 | 83331 |
| 1025 | Fluoride | (2.0) | B804622-01 | 1 | | SM 4500F C | 5/5/98 | 0.027 | 83331 |
| 1028 | Iron | (0.3) | B804622-01 | 0.018 | I | 200.7 | 5/1/98 | 0.006 | 83331 |
| 1032 | Manganese | (0.05) | B804622-01 | < 0.002 | U | 200.7 | 5/1/98 | 0.002 | 83331 |
| 1050 | Silver | (0.1) | B804622-01 | 0.04 | | 200.7 | 4/30/98 | 0.009 | 83331 |
| 1055 | Sulfate | (250) | B804622-01 | 78.3 | | 300.0A | 4/29/98 | 0.03 | 83331 |
| 1095 | Zinc | (5) | B804622-01 | < 0.006 | U | 200.7 | 5/1/98 | 0.006 | 83331 |
| 1905 | Color | (15color units) | B804622-01 | 7 | | SM2120B | 4/28/98 | 5 | 83331 |
| 1920 | Odor | (3 T.O.N.) | B804622-01 | > 32 | | SM2150B | 4/28/98 | 1 | 83331 |
| 1925 | pH | (6.5-8.5) | B804622-01 | 7.97 | | 150.1 | 4/28/98 | | 83331 |
| 1 | Total Dissolved Solids | (500) | B804622-01 | 1070 | | SM2540C | 5/1/98 | 4.41 | 83331 |
| 2 | Foaming Agents | (0.5) | B804622-01 | < 0.02 | J3 | SM5540C | 4/30/98 | 0.02 | 83331 |

TRIHALOMETHANE ANALYSIS

62-550-310(a)

(PWS027)

| ID | Name | Sample Number | CL Resid | Analysis Result(mg/L) | Q | Analysis Method | Analysis Date | MDL(mg/L) | Lab ID |
|------|------------|---------------|----------|-----------------------|---|-----------------|---------------|-----------|--------|
| 2950 | Total THMs | | | | | 524.2 | | 0.0011 | |

RADIOCHEMICAL ANALYSIS*

62-550.310(5)

(PWS033)

| ID | Name | Sample Number | Analysis Result(pCi/l) | Analysis Method | Analysis Date | Error | Lab ID |
|------|-----------------|---------------|------------------------|-----------------|---------------|-------|--------|
| 4000 | Gross Alpha | B804622-01 | 4.2 | 900.0 | 4/30/98 | ±2.1 | 83141 |
| 4012 | Photon Emitters | | | | | | |
| 4020 | Radium-226 | B804622-01 | 1.1 | 903.1 | 5/5/98 | ±0.2 | 83141 |
| 4030 | Radium-228 | B804622-01 | < 0.9 | RA-5 | 5/5/98 | ±0.5 | 83141 |
| 4101 | Man-made beta | | | | | | |

*(Gross alpha generally only requirement, see 62-550.519,(FAC)

VOLATILE ORGANIC ANALYSIS

62-550.310(2)(b)

(PWS028)

| ID | Name | (MCL ug/L) | Sample Number | Analysis Result(µg/L) | Q | Analysis Method | Analysis Date | MDL(µg/L) | Lab ID |
|------|----------------------------|------------|---------------|-----------------------|---|-----------------|---------------|-----------|--------|
| 2378 | 1,2,4-Trichlorobenzene | (70) | B804622-01 | < 0.22 | U | 524.2 | 4/30/98 | 0.22 | 83331 |
| 2380 | Cis-1,2-dichloroethylene | (70) | B804622-01 | < 0.03 | U | 524.2 | 4/30/98 | 0.03 | 83331 |
| 2955 | Xylenes (total) | (10000) | B804622-01 | < 0.24 | U | 524.2 | 4/30/98 | 0.24 | 83331 |
| 2964 | Dichloromethane | (5) | B804622-01 | < 0.31 | U | 524.2 | 4/30/98 | 0.31 | 83331 |
| 2968 | O-dichlorobenzene | (600) | B804622-01 | < 0.05 | U | 524.2 | 4/30/98 | 0.05 | 83331 |
| 2969 | Para-dichlorobenzene | (75) | B804622-01 | < 0.02 | U | 524.2 | 4/30/98 | 0.02 | 83331 |
| 2976 | Vinyl Chloride | (1) | B804622-01 | < 0.29 | U | 524.2 | 4/30/98 | 0.29 | 83331 |
| 2977 | 1,1-dichloroethylene | (7) | B804622-01 | < 0.02 | U | 524.2 | 4/30/98 | 0.02 | 83331 |
| 2979 | Trans-1,2-dichloroethylene | (100) | B804622-01 | < 0.12 | U | 524.2 | 4/30/98 | 0.12 | 83331 |
| 2980 | 1,2-dichloroethane | (3) | B804622-01 | < 0.02 | U | 524.2 | 4/30/98 | 0.02 | 83331 |
| 2981 | 1,1,1-trichloroethane | (200) | B804622-01 | < 0.21 | U | 524.2 | 4/30/98 | 0.21 | 83331 |
| 2982 | Carbon tetrachloride | (3) | B804622-01 | < 0.29 | U | 524.2 | 4/30/98 | 0.29 | 83331 |
| 2983 | 1,2-dichloropropane | (5) | B804622-01 | < 0.33 | U | 524.2 | 4/30/98 | 0.33 | 83331 |
| 2984 | Trichloroethylene | (3) | B804622-01 | < 0.02 | U | 524.2 | 4/30/98 | 0.02 | 83331 |
| 2985 | 1,1,2-trichloroethane | (5) | B804622-01 | < 0.23 | U | 524.2 | 4/30/98 | 0.23 | 83331 |
| 2987 | Tetrachloroethylene | (3) | B804622-01 | < 0.21 | U | 524.2 | 4/30/98 | 0.21 | 83331 |
| 2989 | Monochlorobenzene | (100) | B804622-01 | < 0.23 | U | 524.2 | 4/30/98 | 0.23 | 83331 |
| 2990 | Benzene | (1) | B804622-01 | < 0.05 | U | 524.2 | 4/30/98 | 0.05 | 83331 |
| 2991 | Toluene | (1000) | B804622-01 | < 0.41 | U | 524.2 | 4/30/98 | 0.41 | 83331 |
| 2992 | Ethylbenzene | (700) | B804622-01 | < 0.47 | U | 524.2 | 4/30/98 | 0.47 | 83331 |
| 2996 | Styrene | (100) | B804622-01 | < 0.2 | U | 524.2 | 4/30/98 | 0.2 | 83331 |

PESTICIDE/PCB CHEMICAL ANALYSIS

62-550-310(2)(c)
(PWS029)

| P | Name | (MCL ug/L) | Sample Number | Analysis | | Analysis Method | Analysis Date | MDL(µg/L) | Lab ID |
|------|---------------------------|------------|---------------|--------------|---|-----------------|---------------|-----------|--------|
| | | | | Result(µg/L) | Q | | | | |
| 2005 | Endrin | (2) | | | | 508 | | 0.002 | |
| 2010 | Lindane | (.2) | | | | 508 | | 0.002 | |
| 2015 | Methoxychlor | (40) | | | | 508 | | 0.052 | |
| 2020 | Toxaphene | (3) | | | | 508 | | 0.309 | |
| 2031 | Dalapon | (200) | | | | 515.1 | | 0.036 | |
| 2032 | Diquat | (20) | | | | 549.1 | | 0.26 | |
| 2033 | Endothall | (100) | | | | 548.1 | | 15.4 | |
| 2034 | Glyphosate | (700) | | | | 547 | | 9.44 | |
| 2035 | Di(2-ethylhexyl)adipate | (400) | | | | 525.2 | | 0.71 | |
| 2036 | Oxamyl (Vydate) | (200) | | | | 531.1 | | 2.57 | |
| 2037 | Simazine | (4) | | | | 507 | | 0.078 | |
| 2039 | Di(2-ethylhexyl)phthalate | (6) | | | | 525.2 | | 1.15 | |
| 2040 | Picloram | (500) | | | | 515.1 | | 0.029 | |
| 2041 | Dinoseb | (7) | | | | 515.1 | | 0.055 | |
| 2042 | Hexachlorocyclopentadiene | (50) | | | | 525.2 | | 0.292 | |
| 2046 | Carbofuran | (40) | | | | 531.1 | | 7.04 | |
| 2050 | Atrazine | (3) | | | | 507 | | 0.035 | |
| 2051 | Alachlor | (2) | | | | 507 | | 0.012 | |
| 2063 | 2,3,7,8-TCDD(Dioxin) | (.00003) | — | | | — | | | |
| 2065 | Heptachlor | (.4) | | | | 508 | | 0.004 | |
| 2067 | Heptachlor Epoxide | (.2) | | | | 508 | | 0.002 | |
| 2 | 2,4-D | (70) | | | | 515.1 | | 0.026 | |
| 2 | 2,4,5-TP (Silvex) | (50) | | | | 515.1 | | 0.017 | |
| 2274 | Hexachlorobenzene | (1) | | | | 508 | | 0.008 | |
| 2306 | Benzo(a)pyrene | (.2) | | | | 550.1 | | 0.013 | |
| 2326 | Pentachlorophenol | (1) | | | | 515.1 | | 0.007 | |
| 2383 | PCB | (.5) | B804622-01 | < 0.1 | U | 508 | 5/8/98 | 0.1 | 83331 |
| 2931 | Dibromochloropropane | (.2) | | | | 504.1 | | 0.004 | |
| 2946 | Ethylene Dibromide | (.02) | | | | 504.1 | | 0.006 | |
| 2959 | Chlordane | (2) | | | | 508 | | 0.446 | |

UNREGULATED GROUP I ANALYSIS

62-550.405
(PWS035)

| ID | Name | Sample Number | Analysis | | Analysis Method | Analysis Date | MDL(µg/L) | Lab ID |
|------|---------------------|---------------|--------------|---|-----------------|---------------|-----------|--------|
| | | | Result(µg/L) | Q | | | | |
| 2021 | Carbaryl | | | | 531.1 | | 3.89 | |
| 2022 | Methomyl | | | | 531.1 | | 3.20 | |
| 2043 | Aldicarb Sulfoxide | | | | 531.1 | | 1.88 | |
| 2044 | Aldicarb Sulfone | | | | 531.1 | | 5.57 | |
| 2045 | Metolachlor | | | | 507 | | 0.108 | |
| 2047 | Aldicarb | | | | 531.1 | | 5.95 | |
| 2066 | 3-Hydroxycarbofuran | | | | 531.1 | | 3.35 | |
| | Butachlor | | | | 507 | | 0.021 | |
| | Propachlor | | | | 508 | | 0.110 | |
| 2356 | Aldrin | | | | 508 | | 0.003 | |
| 2364 | Dieldrin | | | | 508 | | 0.002 | |
| 2440 | Dicamba | | | | 515.1 | | 0.005 | |
| 2595 | Metribuzin | | | | 507 | | 0.024 | |

REPORT COMMENTS

CASE NARRATIVE

WE ARE EXPERIENCING A PROBLEM WITH THE RECOVERY OF THE THE STANDARDS (CCVs) FOR MBAS. THE STOCK STANDARD USED TO MAKE THE WORKING STANDARD MAY HAVE BEEN CONTAMINATED OR HAS GONE BAD. THE RESULTS REPORTED HAVE BEEN QUALIFIED WITH A "J3" INDICATING THE ASSOCIATED QC FAILS TO MEET ESTABLISHED CRITERIA. THE REPORTED RESULTS MAY BE LOWER THAN ANTICIPATED.

THE CORRECTIVE ACTION, ALREADY IN PLACE, IS THE USE OF A NEW MBAS STOCK SOLUTION AND TO GENERATE A NEW 10 POINT CURVE. WE FEEL THESE MEASURES WILL ELIMINATE ANY FURTHER PROBLEMS.

NOTE: RADIOCHEMICAL ANALYSIS SUBCONTRACTED TO FL DW LAB ID #83141

BIONOMICS LABORATORY

4310 E. Anderson Rd.
 Orlando, FL 32812
 DHRS/DEP #83331; E83012
 (407) 851-2560 FAX:(407) 856-0886

| | |
|----------------------------|-------------------|
| For Lab Use Only | |
| Date Received: | <u>04/28/98</u> |
| Time Received: | <u>1220</u> |
| Signature of Lab Official: | <u>Mark Puder</u> |

**DRINKING WATER
 BACTERIOLOGICAL ANALYSIS**

System Name: CITY OF COCOA System ID #: 3050223 System Phone#: (407)568-5867
 Address: 600 SCHOOL ST. County: _____ DEP District: _____
 Collector: MARY KRALJ Collector Phone#: (407)568-5867
 Sample Site (locality or subdivision): R-8
 Date and Time Collected: 04/28/98 @ 1120

Type of Supply: Community water system Noncommunity water system Nontransient-noncommunity water sys.
 Private well Swimming pool Bottled water Other public water system

Type of Sample: Compliance Repeat Replacement Main Clearance Well Survey Other: _____
 (circle one) (check box) (check box) (specify)
 Distribution TNTC or C
 Raw Turbid

Remarks:

| TO BE COMPLETED BY COLLECTOR OF SAMPLE | | | |
|--|------------------------------------|-----------|----|
| No: | Sample Point (Specific Address) | Cl Res | pH |
| | R-8 | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| TO BE COMPLETED BY LAB: | | | | | |
|--------------------------|-----------------|------------------------|------------------|------------------|----|
| Date & time of analysis: | | <u>04/28/98 @ 1750</u> | by: <u>LH</u> | | |
| Analysis Method: | | MF | MTF | MMO-MUG | PA |
| Sample Number: | Non Coliform | *Total | Confirm Total | Confirm Fecal | |
| <u>B804622-01</u> | | <u>P</u> | <u>P</u> | <u>A</u> | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

* Results in this column are preliminary. Fecal coliform confirmation on community and noncommunity water systems and total coliform confirmation on all types of water systems will follow in 24-48 hours.

P - Coliforms are present C - Confluent growth TA - Turbid, Absence of gas or acid
 A - Coliforms are absent TNTC - Too numerous to count

INTERPRETATIONS - REMARKS BY PROGRAM REVIEWER

Name and Mailing Address of Person/Firm to Receive Report:

| | | |
|--|--|--|
| CITY OF COCOA 600 SCHOOL ST. COCOA, FL 32922 ATTN: MARY KRALJ | | |
|--|--|--|

- _____
- Satisfactory
- Incomplete collection information
- Repeat samples
- Replacement samples

Reviewing Official: _____

Title: _____

LAB FORMAT FOR REPORTING DRINKING WATER ANALYSES

PUBLIC WATER SYSTEM INFORMATION (to be completed by system or lab)

System Name: CITY OF COCA I.D. #: 3050223
600 SCHOOL ST, COCOA, FL 32922 Phone #: 568-5867
 Type (check one) Community Nontransient Noncommunity Noncommunity

SAMPLE INFORMATION (to be completed by sampler)

Sample Date (MMDDYY): 04/15/98 Sample Time: 0900
 Sample Location (be specific): R-9
 Sampler Name and Phone: MARY KRALJ
 Sampler's Signature: *Mary Kralj* Title: Laboratory Technician
 Check Types(s) Distribution Recheck of MCL Resample of Lab Invalidated Sample
 Clearance Thm Max Res Time Plant Tap
 Distrib entry pt Raw Composite of Multiple Sites--Attach a format for each site

LABORATORY CERTIFICATION INFORMATION (to be completed by lab) -- attach HRS Analyte Sheet *

Lab Name: BIONOMICS LABORATORY HRS#: 83331 Expiration Date: 06/30/98
 Address: 4310 E. Anderson Rd., Orlando, FL 32812 Phone: 851-2560
 Subcontracted Lab HRS#: 83141 --ATTACH HRS ANALYTE SHEET FOR SUBCONTRACTED LAB, TOO *

ANALYSIS INFORMATION: (to be completed by lab)

Work Order Number: B804357-01

Date Sample(s) Received: 04/15/98 Group(s) Analyzed & Results attached for compliance with 62-550, F.A.C.:

- | | | | |
|---|--|---|--|
| <input type="checkbox"/> Nitrate Only | <input type="checkbox"/> Nitrite Only | <input type="checkbox"/> Asbestos Only | <input type="checkbox"/> Trihalomethanes |
| Inorganics-- <input type="checkbox"/> All 17 <input checked="" type="checkbox"/> Partial | Volatile Organics-- <input checked="" type="checkbox"/> All 21 <input type="checkbox"/> Partial | Secondaries-- <input checked="" type="checkbox"/> All <input type="checkbox"/> Partial | Pesticide/PCBs-- <input type="checkbox"/> All 30 <input checked="" type="checkbox"/> Partial |
| Group I Unregulateds-- <input type="checkbox"/> All 13 <input type="checkbox"/> Partial | Group II Unregulateds-- <input type="checkbox"/> All 23 <input type="checkbox"/> Partial | Group III Unregulateds-- <input type="checkbox"/> All <input type="checkbox"/> Partial | Radiochemicals-- <input checked="" type="checkbox"/> Single Sample <input type="checkbox"/> Qtrly Composite ** |

**Provide radiochemical sample dates & locations for each quarter

I, MARK RUSLER, do HEREBY CERTIFY that all attached analytical data are correct.

Signature: *Mark Rusler*

Title: CHEMIST Date: 6/2/98

COMPLIANCE INFORMATION (to be completed by State)

Sample Collection Satisfactory: _____ Sample Analysis Satisfactory: _____
 Reason Requested For: _____ Reason: _____
 Date Notified to Resample: _____ Date Notified: _____
 DEP/HRS Reviewing Official: _____

*All HRS lab #'s and their HRS Analyte Sheet for labs performing the attached water analyses must be provided. Failure to do so will result in rejection of the analyses and possible enforcement against the public water system for failure to sample.

INORGANIC ANALYSIS

62-550-310(1)

(PWS030)

| ID | Name | (MCL mg/L) | Sample Number | Analysis Result(mg/L) | Q | Analysis Method | Analysis Date | MDL(mg/L) | Lab ID |
|------|-----------|------------|---------------|-----------------------|---|-----------------|---------------|-----------|--------|
| 1005 | Arsenic | (0.05) | B804357-01 | < 0.0034 | U | 200.9 | 4/17/98 | 0.0034 | 83331 |
| 1010 | Barium | (2) | B804357-01 | 0.014 | | 200.7 | 4/21/98 | 0.002 | 83331 |
| 1015 | Cadmium | (.005) | B804357-01 | < 0.0001 | U | 200.9 | 4/20/98 | 0.0001 | 83331 |
| 1020 | Chromium | (0.1) | B804357-01 | < 0.0002 | U | 200.9 | 4/20/98 | 0.0002 | 83331 |
| 1024 | Cyanide | (0.2) | B804357-01 | < 0.006 | U | SM4500CN E | 4/24/98 | 0.006 | 83331 |
| 1025 | Fluoride | (4) | B804357-01 | 1.1 | | SM 4500F C | 4/20/98 | 0.027 | 83331 |
| 1030 | Lead | (0.015) | B804357-01 | < 0.001 | U | 200.9 | 4/20/98 | 0.001 | 83331 |
| 1035 | Mercury | (0.002) | B804357-01 | < 0.00005 | U | 245.1 | 4/22/98 | 0.00005 | 83331 |
| 1036 | Nickel | (0.1) | B804357-01 | < 0.012 | U | 200.7 | 4/20/98 | 0.012 | 83331 |
| 1040 | Nitrate | (10) | B804357-01 | < 0.006 | U | 300.0A | 4/15/98 | 0.006 | 83331 |
| 1041 | Nitrite | (1) | B804357-01 | < 0.004 | U | 300.0A | 4/15/98 | 0.004 | 83331 |
| 1045 | Selenium | (0.05) | B804357-01 | 0.003 | I | 200.9 | 4/17/98 | 0.002 | 83331 |
| 1052 | Sodium | (160) | B804357-01 | 232 | | 200.7 | 4/20/98 | 0.1 | 83331 |
| 1074 | Antimony | (0.006) | B804357-01 | < 0.0017 | U | 200.9 | 4/27/98 | 0.0017 | 83331 |
| 1075 | Beryllium | (0.004) | B804357-01 | < 0.0003 | U | 200.7 | 4/21/98 | 0.0003 | 83331 |
| 1085 | Thallium | (0.002) | B804357-01 | < 0.0006 | U | 200.9 | 4/17/98 | 0.0006 | 83331 |
| 1094 | Asbestos | (7 MFL) | | | | NA | | | |

SECONDARY CHEMICAL ANALYSIS

62-550.320

(PWS031)

| ID | Name | (MCL mg/L) | Sample Number | Analysis Result(mg/L) | Q | Analysis Method | Analysis Date | MDL(mg/L) | Lab ID |
|------|------------------------|-----------------|---------------|-----------------------|---|-----------------|---------------|-----------|--------|
| 1002 | Aluminum | (0.2) | B804357-01 | < 0.036 | U | 200.7 | 4/21/98 | 0.036 | 83331 |
| 1017 | Chloride | (250) | B804357-01 | 417 | | 300.0A | 4/15/98 | 0.074 | 83331 |
| 1022 | Copper | (1) | B804357-01 | < 0.004 | U | 200.7 | 4/20/98 | 0.004 | 83331 |
| 1025 | Fluoride | (2.0) | B804357-01 | 1.1 | | SM 4500F C | 4/20/98 | 0.027 | 83331 |
| 1028 | Iron | (0.3) | B804357-01 | 0.027 | I | 200.7 | 4/20/98 | 0.006 | 83331 |
| 1032 | Manganese | (0.05) | B804357-01 | < 0.002 | U | 200.7 | 4/20/98 | 0.002 | 83331 |
| 1050 | Silver | (0.1) | B804357-01 | < 0.009 | U | 200.7 | 4/21/98 | 0.009 | 83331 |
| 1055 | Sulfate | (250) | B804357-01 | 75.4 | | 300.0A | 4/15/98 | 0.03 | 83331 |
| 1095 | Zinc | (5) | B804357-01 | 0.026 | | 200.7 | 4/20/98 | 0.006 | 83331 |
| 1905 | Color | (15color units) | B804357-01 | 10 | | SM2120B | 4/15/98 | 5 | 83331 |
| 1920 | Odor | (3 T.O.N.) | B804357-01 | 32 | | SM2150B | 4/15/98 | 1 | 83331 |
| 1925 | pH | (6.5-8.5) | B804357-01 | 7.65 | | 150.1 | 4/15/98 | | 83331 |
| 1 | Total Dissolved Solids | (500) | B804357-01 | 934 | | SM2540C | 4/20/98 | 4.41 | 83331 |
| 2 | Foaming Agents | (0.5) | B804357-01 | 0.02 | I | SM5540C | 4/16/98 | 0.02 | 83331 |

TRIHALOMETHANE ANALYSIS

62-550-310(a)

(PWS027)

| I | Name | Sample Number | CL Resid | Analysis | | Analysis Method | Analysis Date | MDL(mg/L) | Lab ID |
|------|------------|---------------|----------|--------------|---|-----------------|---------------|-----------|--------|
| | | | | Result(mg/L) | Q | | | | |
| 2950 | Total THMs | | | | | 524.2 | | 0.0011 | |

RADIOCHEMICAL ANALYSIS*

62-550.310(5)

(PWS033)

| ID | Name | Sample Number | Analysis Result(pCi/l) | Analysis Method | Analysis Date | Error | Lab ID |
|------|-----------------|---------------|------------------------|-----------------|---------------|-------|--------|
| 4000 | Gross Alpha | B804357-01 | < 4.6 | 900.0 | 4/21/98 | ±2.9 | 83141 |
| 4012 | Photon Emitters | | | | | | |
| 4020 | Radium-226 | B804357-01 | 1.9 | 903.1 | 4/21/98 | ±0.3 | 83141 |
| 4030 | Radium-228 | B804357-01 | < 0.9 | RA-5 | 4/21/98 | ±0.6 | 83141 |
| 4101 | Man-made beta | | | | | | |

*(Gross alpha generally only requirement, see 62-550.519,(FAC)

VOLATILE ORGANIC ANALYSIS

62-550.310(2)(b)

(PWS028)

| I | Name | (MCL ug/L) | Sample Number | Analysis | | Analysis Method | Analysis Date | MDL(µg/L) | Lab ID |
|------|----------------------------|------------|---------------|--------------|---|-----------------|---------------|-----------|--------|
| | | | | Result(µg/L) | Q | | | | |
| 2. | 1,2,4-Trichlorobenzene | (70) | B804357-01 | < 0.22 | U | 524.2 | 4/20/98 | 0.22 | 83331 |
| 2380 | Cis-1,2-dichloroethylene | (70) | B804357-01 | < 0.03 | U | 524.2 | 4/20/98 | 0.03 | 83331 |
| 2955 | Xylenes (total) | (10000) | B804357-01 | < 0.24 | U | 524.2 | 4/20/98 | 0.24 | 83331 |
| 2964 | Dichloromethane | (5) | B804357-01 | < 0.31 | U | 524.2 | 4/20/98 | 0.31 | 83331 |
| 2968 | O-dichlorobenzene | (600) | B804357-01 | < 0.05 | U | 524.2 | 4/20/98 | 0.05 | 83331 |
| 2969 | Para-dichlorobenzene | (75) | B804357-01 | < 0.02 | U | 524.2 | 4/20/98 | 0.02 | 83331 |
| 2976 | Vinyl Chloride | (1) | B804357-01 | < 0.29 | U | 524.2 | 4/20/98 | 0.29 | 83331 |
| 2977 | 1,1-dichloroethylene | (7) | B804357-01 | < 0.02 | U | 524.2 | 4/20/98 | 0.02 | 83331 |
| 2979 | Trans-1,2-dichloroethylene | (100) | B804357-01 | < 0.12 | U | 524.2 | 4/20/98 | 0.12 | 83331 |
| 2980 | 1,2-dichloroethane | (3) | B804357-01 | < 0.02 | U | 524.2 | 4/20/98 | 0.02 | 83331 |
| 2981 | 1,1,1-trichloroethane | (200) | B804357-01 | < 0.21 | U | 524.2 | 4/20/98 | 0.21 | 83331 |
| 2982 | Carbon tetrachloride | (3) | B804357-01 | < 0.29 | U | 524.2 | 4/20/98 | 0.29 | 83331 |
| 2983 | 1,2-dichloropropane | (5) | B804357-01 | < 0.33 | U | 524.2 | 4/20/98 | 0.33 | 83331 |
| 2984 | Trichloroethylene | (3) | B804357-01 | < 0.02 | U | 524.2 | 4/20/98 | 0.02 | 83331 |
| 2985 | 1,1,2-trichloroethane | (5) | B804357-01 | < 0.23 | U | 524.2 | 4/20/98 | 0.23 | 83331 |
| 2987 | Tetrachloroethylene | (3) | B804357-01 | < 0.21 | U | 524.2 | 4/20/98 | 0.21 | 83331 |
| 2989 | Monochlorobenzene | (100) | B804357-01 | < 0.23 | U | 524.2 | 4/20/98 | 0.23 | 83331 |
| 2990 | Benzene | (1) | B804357-01 | < 0.05 | U | 524.2 | 4/20/98 | 0.05 | 83331 |
| 2991 | Toluene | (1000) | B804357-01 | < 0.41 | U | 524.2 | 4/20/98 | 0.41 | 83331 |
| 2 | Ethylbenzene | (700) | B804357-01 | < 0.47 | U | 524.2 | 4/20/98 | 0.47 | 83331 |
| 2990 | Styrene | (100) | B804357-01 | < 0.2 | U | 524.2 | 4/20/98 | 0.2 | 83331 |

PESTICIDE/PCB CHEMICAL ANALYSIS

62-550-310(2)(c)

(PWS029)

| E | Name | (MCL ug/L) | Sample Number | Analysis | | Analysis Method | Analysis Date | MDL(µg/L) | Lab ID |
|------|---------------------------|------------|---------------|--------------|---|-----------------|---------------|-----------|--------|
| | | | | Result(µg/L) | Q | | | | |
| 2005 | Endrin | (2) | | | | 508 | | 0.002 | |
| 2010 | Lindane | (.2) | | | | 508 | | 0.002 | |
| 2015 | Methoxychlor | (40) | | | | 508 | | 0.052 | |
| 2020 | Toxaphene | (3) | | | | 508 | | 0.309 | |
| 2031 | Dalapon | (200) | | | | 515.1 | | 0.036 | |
| 2032 | Diquat | (20) | | | | 549.1 | | 0.26 | |
| 2033 | Endothall | (100) | | | | 548.1 | | 15.4 | |
| 2034 | Glyphosate | (700) | | | | 547 | | 9.44 | |
| 2035 | Di(2-ethylhexyl)adipate | (400) | | | | 525.2 | | 0.71 | |
| 2036 | Oxamyl (Vydate) | (200) | | | | 531.1 | | 2.57 | |
| 2037 | Simazine | (4) | | | | 507 | | 0.078 | |
| 2039 | Di(2-ethylhexyl)phthalate | (6) | | | | 525.2 | | 1.15 | |
| 2040 | Picloram | (500) | | | | 515.1 | | 0.029 | |
| 2041 | Dinoseb | (7) | | | | 515.1 | | 0.055 | |
| 2042 | Hexachlorocyclopentadiene | (50) | | | | 525.2 | | 0.292 | |
| 2046 | Carbofuran | (40) | | | | 531.1 | | 7.04 | |
| 2050 | Atrazine | (3) | | | | 507 | | 0.035 | |
| 2051 | Alachlor | (2) | | | | 507 | | 0.012 | |
| 2063 | 2,3,7,8-TCDD(Dioxin) | (.00003) | -- | | | -- | | | |
| 2065 | Heptachlor | (.4) | | | | 508 | | 0.004 | |
| 2067 | Heptachlor Epoxide | (.2) | | | | 508 | | 0.002 | |
| 207 | 2,4-D | (70) | | | | 515.1 | | 0.026 | |
| 208 | 2,4,5-TP (Silvex) | (50) | | | | 515.1 | | 0.017 | |
| 209 | Hexachlorobenzene | (1) | | | | 508 | | 0.008 | |
| 2306 | Benzo(a)pyrene | (.2) | | | | 550.1 | | 0.013 | |
| 2326 | Pentachlorophenol | (1) | | | | 515.1 | | 0.007 | |
| 2383 | PCB | (.5) | B804357-01 | < 0.1 | U | 508 | 4/25/98 | 0.1 | 83331 |
| 2931 | Dibromochloropropane | (.2) | | | | 504.1 | | 0.004 | |
| 2946 | Ethylene Dibromide | (.02) | | | | 504.1 | | 0.006 | |
| 2959 | Chlordane | (2) | | | | 508 | | 0.446 | |

UNREGULATED GROUP I ANALYSIS

62-550.405

(PWS035)

| ID | Name | Sample Number | Analysis | | Analysis Method | Analysis Date | MDL(µg/L) | Lab ID |
|------|---------------------|---------------|--------------|---|-----------------|---------------|-----------|--------|
| | | | Result(µg/L) | Q | | | | |
| 2021 | Carbaryl | | | | 531.1 | | 3.89 | |
| 2022 | Methomyl | | | | 531.1 | | 3.20 | |
| 2043 | Aldicarb Sulfoxide | | | | 531.1 | | 1.88 | |
| 2044 | Aldicarb Sulfone | | | | 531.1 | | 5.57 | |
| 2045 | Metolachlor | | | | 507 | | 0.108 | |
| 2047 | Aldicarb | | | | 531.1 | | 5.95 | |
| 2066 | 3-Hydroxycarbofuran | | | | 531.1 | | 3.35 | |
| 207 | Butachlor | | | | 507 | | 0.021 | |
| 208 | Propachlor | | | | 508 | | 0.110 | |
| 209 | Aldrin | | | | 508 | | 0.003 | |
| 2364 | Dieldrin | | | | 508 | | 0.002 | |
| 2440 | Dicamba | | | | 515.1 | | 0.005 | |
| 2595 | Metribuzin | | | | 507 | | 0.024 | |

BIONOMICS LABORATORY

4310 E. Anderson Rd.
 Orlando, FL 32812
 DHRS/DEP #83331; E83012
 (407) 851-2560 FAX:(407) 856-0886

| For Lab Use Only | |
|------------------|-----------------|
| Date Received: | <u>04/15/98</u> |
| Time Received: | <u>1005</u> |
| Signature of | _____ |
| Lab Official: | _____ |

**DRINKING WATER
 BACTERIOLOGICAL ANALYSIS**

System Name: CITY OF COCOA System ID #: 3050223 System Phone#: (407)568-5867
 Address: 600 SCHOOL ST. County: _____ DEP District: _____
 Collector: MARY KRALJ Collector Phone#: (407)568-5867
 Sample Site (locality or subdivision): R-9
 Date and Time Collected: 04/15/98 @ 0900

Type of Supply: Community water system Noncommunity water system Nontransient-noncommunity water sys.
 Private well Swimming pool Bottled water Other public water system

Type of Sample: Compliance Repeat Replacement Main Clearance Well Survey Other: _____
 (circle one) (check box) (check box) (specify)
 Distribution TNTC or C
 Raw Turbid

Remarks:

| TO BE COMPLETED BY COLLECTOR OF SAMPLE | | | |
|--|------------------------------------|-----------|----|
| No. | Sample Point (Specific Address) | Cl Res | pH |
| | R-9 | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| TO BE COMPLETED BY LAB: | | | | |
|--|-----------------|---------------|------------------|------------------|
| Date & time of analysis: <u>4/15/98 @ 1058</u> | | by: <u>LH</u> | | |
| Analysis Method: MF | | MTF | MMO-MUG | PA |
| Sample Number: | Non Coliform | *Total | Confirm Total | Confirm Fecal |
| <u>B804357-01</u> | | <u>A</u> | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

* Results in this column are preliminary. Fecal coliform confirmation on community and noncommunity water systems and total coliform confirmation on all types of water systems will follow in 24-48 hours.

P - Coliforms are present C - Confluent growth TA - Turbid, Absence of gas or acid
 A - Coliforms are absent TNTC - Too numerous to count

INTERPRETATIONS - REMARKS BY PROGRAM REVIEWER

Name and Mailing Address of Person/Firm to Receive Report:

| |
|--|
| CITY OF COCOA 600 SCHOOL ST. COCOA, FL 32922 ATTN: MARY KRALJ |
|--|

- _____
- Satisfactory
- Incomplete collection information
- Repeat samples
- Replacement samples

Reviewing Official: _____

Title: _____

LAB FORMAT FOR REPORTING DRINKING WATER ANALYSES

PUBLIC WATER SYSTEM INFORMATION (to be completed by system or lab)

System Name: CITY OF COCA I.D. #: 3050223
 Ac: 600 SCHOOL ST, COCOA, FL 32922 Phone #: 407-568-5867
 Type (check one) Community Nontransient Noncommunity Noncommunity

SAMPLE INFORMATION (to be completed by sampler)

Sample Date (MMDDYY): 04/21/98 Sample Time: 1000
 Sample Location (be specific): R-10
 Sampler Name and Phone: MARY KRALJ
 Sampler's Signature: *Mary Kralj* Title: Laboratory Technician
 Check Types(s) Distribution Recheck of MCL Resample of Lab Invalidated Sample
 Clearance Thm Max Res Time Plant Tap
 Distrib entry pt Raw Composite of Multiple Sites--Attach a format for each site

LABORATORY CERTIFICATION INFORMATION (to be completed by lab) -- attach HRS Analyte Sheet *

Lab Name: BIONOMICS LABORATORY HRS#: 83331 Expiration Date: 06/30/98
 Address: 4310 E. Anderson Rd., Orlando, FL 32812 Phone: 851-2560
 Subcontracted Lab HRS#: 83141 --ATTACH HRS ANALYTE SHEET FOR SUBCONTRACTED LAB, TOO *

ANALYSIS INFORMATION: (to be completed by lab)

Work Order Number: B804478-01

Date Sample(s) Received: 04/21/98 Group(s) Analyzed & Results attached for compliance with 62-550, F.A.C.:

Nitrate Only Nitrite Only Asbestos Only Trihalomethanes

Inorganics-- Volatile Organics-- Secondaries-- Pesticide/PCBs--
 All 17 Partial All 21 Partial All Partial All 30 Partial

Group I Unregulateds-- Group II Unregulateds-- Group III Unregulateds-- Radiochemicals--
 All 13 Partial All 23 Partial All Partial Single Sample
 Qtrly Composite **

**Provide radiochemical sample dates & locations for each quarter

I, MARK RUSLER, do HEREBY CERTIFY that all attached analytical data are correct.

Signature *Mark Rusler*

Title: CHEMIST

Date: 5/18/98

COMPLIANCE INFORMATION (to be completed by State)

Sample Collection Satisfactory: _____ Sample Analysis Satisfactory: _____
 Resample Requested For: _____ Reason: _____
 Permitted to resample: _____ Date Notified: _____
 DEP/HRS Reviewing Official: _____

*All HRS lab #s and their HRS Analyte Sheet for labs performing the attached water analyses must be provided. Failure to do so will result in rejection of the analyses and possible enforcement against the public water system for failure to sample.

INORGANIC ANALYSIS

62-550-310(1)

(PWS030)

| ID | Name | (MCL mg/L) | Sample Number | Analysis | | Analysis Method | Analysis Date | MDL(mg/L) | Lab ID |
|------|-----------|------------|---------------|--------------|---|-----------------|---------------|-----------|--------|
| | | | | Result(mg/L) | Q | | | | |
| 1005 | Arsenic | (0.05) | B804478-01 | < 0.0034 | U | 200.9 | 4/22/98 | 0.0034 | 83331 |
| 1010 | Barium | (2) | B804478-01 | 0.104 | | 200.7 | 4/30/98 | 0.002 | 83331 |
| 1015 | Cadmium | (.005) | B804478-01 | < 0.0001 | | 200.9 | 4/27/98 | 0.0001 | 83331 |
| 1020 | Chromium | (0.1) | B804478-01 | < 0.0002 | U | 200.9 | 4/27/98 | 0.0002 | 83331 |
| 1024 | Cyanide | (0.2) | B804478-01 | < 0.006 | U | SM4500CN E | 4/24/98 | 0.006 | 83331 |
| 1025 | Fluoride | (4) | B804478-01 | 0.878 | | SM 4500F C | 4/28/98 | 0.027 | 83331 |
| 1030 | Lead | (0.015) | B804478-01 | < 0.001 | U | 200.9 | 4/27/98 | 0.001 | 83331 |
| 1035 | Mercury | (0.002) | B804478-01 | < 0.00005 | | 245.1 | 4/30/98 | 0.00005 | 83331 |
| 1036 | Nickel | (0.1) | B804478-01 | < 0.012 | U | 200.7 | 5/1/98 | 0.012 | 83331 |
| 1040 | Nitrate | (10) | B804478-01 | < 0.006 | U | 300.0A | 4/22/98 | 0.006 | 83331 |
| 1041 | Nitrite | (1) | B804478-01 | < 0.004 | U | SM4500NO2B | 4/22/98 | 0.004 | 83331 |
| 1045 | Selenium | (0.05) | B804478-01 | 0.003 | I | 200.9 | 4/22/98 | 0.002 | 83331 |
| 1052 | Sodium | (160) | B804478-01 | 292 | | 200.7 | 5/1/98 | 0.1 | 83331 |
| 1074 | Antimony | (0.006) | B804478-01 | < 0.0017 | U | 200.9 | 4/27/98 | 0.0017 | 83331 |
| 1075 | Beryllium | (0.004) | B804478-01 | 0.0004 | I | 200.7 | 4/28/98 | 0.0003 | 83331 |
| 1085 | Thallium | (0.002) | B804478-01 | 0.0006 | I | 200.9 | 4/27/98 | 0.0006 | 83331 |
| 1094 | Asbestos | (7 MFL) | | | | NA | | | |

SECONDARY CHEMICAL ANALYSIS

62-550.320

(PWS031)

| ID | Name | (MCL mg/L) | Sample Number | Analysis | | Analysis Method | Analysis Date | MDL(mg/L) | Lab ID |
|------|------------------------|-----------------|---------------|--------------|----|-----------------|---------------|-----------|--------|
| | | | | Result(mg/L) | Q | | | | |
| 1002 | Aluminum | (0.2) | B804478-01 | < 0.036 | U | 200.7 | 4/28/98 | 0.036 | 83331 |
| 1017 | Chloride | (250) | B804478-01 | 572 | | 300.0A | 4/22/98 | 0.074 | 83331 |
| 1022 | Copper | (1) | B804478-01 | < 0.004 | U | 200.7 | 5/1/98 | 0.004 | 83331 |
| 1025 | Fluoride | (2.0) | B804478-01 | 0.878 | | SM 4500F C | 4/28/98 | 0.027 | 83331 |
| 1028 | Iron | (0.3) | B804478-01 | 0.039 | | 200.7 | 5/1/98 | 0.006 | 83331 |
| 1032 | Manganese | (0.05) | B804478-01 | 0.005 | I | 200.7 | 5/1/98 | 0.002 | 83331 |
| 1050 | Silver | (0.1) | B804478-01 | < 0.009 | U | 200.7 | 4/30/98 | 0.009 | 83331 |
| 1055 | Sulfate | (250) | B804478-01 | 83.1 | | 300.0A | 4/22/98 | 0.03 | 83331 |
| 1095 | Zinc | (5) | B804478-01 | 0.01 | I | 200.7 | 5/1/98 | 0.006 | 83331 |
| 1905 | Color | (15color units) | B804478-01 | 10 | | SM2120B | 4/21/98 | 5 | 83331 |
| 1920 | Odor | (3 T.O.N.) | B804478-01 | > 32 | | SM2150B | 4/21/98 | 1 | 83331 |
| 1925 | pH | (6.5-8.5) | B804478-01 | 7.09 | | 150.1 | 4/21/98 | | 83331 |
| 1 | Total Dissolved Solids | (500) | B804478-01 | 1120 | | SM2540C | 4/22/98 | 4.41 | 83331 |
| 2 | Foaming Agents | (0.5) | B804478-01 | < 0.02 | J3 | SM5540C | 4/30/98 | 0.02 | 83331 |

TRIHALOMETHANE ANALYSIS

62-550-310(a)

(PWS027)

| IL | Name | Sample Number | CL Resid | Analysis | | Analysis Method | Analysis Date | MDL(mg/L) | Lab ID |
|------|------------|---------------|----------|--------------|---|-----------------|---------------|-----------|--------|
| | | | | Result(mg/L) | Q | | | | |
| 2950 | Total THMs | | | | | 524.2 | | 0.0011 | |

RADIOCHEMICAL ANALYSIS*

62-550.310(5)

(PWS033)

| ID | Name | Sample Number | Analysis Result(pCi/l) | Analysis Method | Analysis Date | Error | Lab ID |
|------|-----------------|---------------|------------------------|-----------------|---------------|-------|--------|
| 4000 | Gross Alpha | B804478-01 | < 4.9 | 900.0 | 4/26/98 | ±2.9 | 83141 |
| 4012 | Photon Emitters | | | | | | |
| 4020 | Radium-226 | B804478-01 | 2.2 | 903.1 | 4/30/98 | ±0.3 | 83141 |
| 4030 | Radium-228 | B804478-01 | 1.1 | RA-5 | 4/30/98 | ±2.9 | 83141 |
| 4101 | Man-made beta | | | | | | |

*(Gross alpha generally only requirement, see 62-550.519,(FAC)

VOLATILE ORGANIC ANALYSIS

62-550.310(2)(b)

(PWS028)

| ID | Name | (MCL ug/L) | Sample Number | Analysis Result(ug/L) | Q | Analysis Method | Analysis Date | MDL(ug/L) | Lab ID |
|------|----------------------------|------------|---------------|-----------------------|---|-----------------|---------------|-----------|--------|
| 2380 | 1,2,4-Trichlorobenzene | (70) | B804478-01 | < 0.22 | U | 524.2 | 4/24/98 | 0.22 | 83331 |
| 2380 | Cis-1,2-dichloroethylene | (70) | B804478-01 | < 0.03 | U | 524.2 | 4/24/98 | 0.03 | 83331 |
| 2955 | Xylenes (total) | (10000) | B804478-01 | < 0.24 | U | 524.2 | 4/24/98 | 0.24 | 83331 |
| 2964 | Dichloromethane | (5) | B804478-01 | < 0.31 | U | 524.2 | 4/24/98 | 0.31 | 83331 |
| 2968 | O-dichlorobenzene | (600) | B804478-01 | < 0.05 | U | 524.2 | 4/24/98 | 0.05 | 83331 |
| 2969 | Para-dichlorobenzene | (75) | B804478-01 | < 0.02 | U | 524.2 | 4/24/98 | 0.02 | 83331 |
| 2976 | Vinyl Chloride | (1) | B804478-01 | < 0.29 | U | 524.2 | 4/24/98 | 0.29 | 83331 |
| 2977 | 1,1-dichloroethylene | (7) | B804478-01 | < 0.02 | U | 524.2 | 4/24/98 | 0.02 | 83331 |
| 2979 | Trans-1,2-dichloroethylene | (100) | B804478-01 | < 0.12 | U | 524.2 | 4/24/98 | 0.12 | 83331 |
| 2980 | 1,2-dichloroethane | (3) | B804478-01 | < 0.02 | U | 524.2 | 4/24/98 | 0.02 | 83331 |
| 2981 | 1,1,1-trichloroethane | (200) | B804478-01 | < 0.21 | U | 524.2 | 4/24/98 | 0.21 | 83331 |
| 2982 | Carbon tetrachloride | (3) | B804478-01 | < 0.29 | U | 524.2 | 4/24/98 | 0.29 | 83331 |
| 2983 | 1,2-dichloropropane | (5) | B804478-01 | < 0.33 | U | 524.2 | 4/24/98 | 0.33 | 83331 |
| 2984 | Trichloroethylene | (3) | B804478-01 | < 0.02 | U | 524.2 | 4/24/98 | 0.02 | 83331 |
| 2985 | 1,1,2-trichloroethane | (5) | B804478-01 | < 0.23 | U | 524.2 | 4/24/98 | 0.23 | 83331 |
| 2987 | Tetrachloroethylene | (3) | B804478-01 | < 0.21 | U | 524.2 | 4/24/98 | 0.21 | 83331 |
| 2989 | Monochlorobenzene | (100) | B804478-01 | < 0.23 | U | 524.2 | 4/24/98 | 0.23 | 83331 |
| 2990 | Benzene | (1) | B804478-01 | < 0.05 | U | 524.2 | 4/24/98 | 0.05 | 83331 |
| 2991 | Toluene | (1000) | B804478-01 | < 0.41 | U | 524.2 | 4/24/98 | 0.41 | 83331 |
| | Ethylbenzene | (700) | B804478-01 | < 0.47 | U | 524.2 | 4/24/98 | 0.47 | 83331 |
| 2991 | Styrene | (100) | B804478-01 | < 0.2 | U | 524.2 | 4/24/98 | 0.2 | 83331 |

PESTICIDE/PCB CHEMICAL ANALYSIS

62-550-310(2)(c)

(PWS029)

| E | Name | (MCL ug/L) | Sample Number | Analysis Result(µg/L) | Q | Analysis Method | Analysis Date | MDL(µg/L) | Lab ID |
|------|---------------------------|------------|---------------|-----------------------|---|-----------------|---------------|-----------|--------|
| 2005 | Endrin | (2) | | | | 508 | | 0.002 | |
| 2010 | Lindane | (.2) | | | | 508 | | 0.002 | |
| 2015 | Methoxychlor | (40) | | | | 508 | | 0.052 | |
| 2020 | Toxaphene | (3) | | | | 508 | | 0.309 | |
| 2031 | Dalapon | (200) | | | | 515.1 | | 0.036 | |
| 2032 | Diquat | (20) | | | | 549.1 | | 0.26 | |
| 2033 | Endothall | (100) | | | | 548.1 | | 15.4 | |
| 2034 | Glyphosate | (700) | | | | 547 | | 9.44 | |
| 2035 | Di(2-ethylhexyl)adipate | (400) | | | | 525.2 | | 0.71 | |
| 2036 | Oxamyl (Vydate) | (200) | | | | 531.1 | | 2.57 | |
| 2037 | Simazine | (4) | | | | 507 | | 0.078 | |
| 2039 | Di(2-ethylhexyl)phthalate | (6) | | | | 525.2 | | 1.15 | |
| 2040 | Picloram | (500) | | | | 515.1 | | 0.029 | |
| 2041 | Dinoseb | (7) | | | | 515.1 | | 0.055 | |
| 2042 | Hexachlorocyclopentadiene | (50) | | | | 525.2 | | 0.292 | |
| 2046 | Carbofuran | (40) | | | | 531.1 | | 7.04 | |
| 2050 | Atrazine | (3) | | | | 507 | | 0.035 | |
| 2051 | Alachlor | (2) | | | | 507 | | 0.012 | |
| 2063 | 2,3,7,8-TCDD(Dioxin) | (.00003) | — | | | — | | | |
| 2065 | Heptachlor | (.4) | | | | 508 | | 0.004 | |
| 2067 | Heptachlor Epoxide | (.2) | | | | 508 | | 0.002 | |
| 2 | 2,4-D | (70) | | | | 515.1 | | 0.026 | |
| 2. | 2,4,5-TP (Silvex) | (50) | | | | 515.1 | | 0.017 | |
| 2274 | Hexachlorobenzene | (1) | | | | 508 | | 0.008 | |
| 2306 | Benzo(a)pyrene | (.2) | | | | 550.1 | | 0.013 | |
| 2326 | Pentachlorophenol | (1) | | | | 515.1 | | 0.007 | |
| 2383 | PCB | (.5) | B804478-01 | < 0.1 | U | 508 | 4/25/98 | 0.1 | 83331 |
| 2931 | Dibromochloropropane | (.2) | | | | 504.1 | | 0.004 | |
| 2946 | Ethylene Dibromide | (.02) | | | | 504.1 | | 0.006 | |
| 2959 | Chlordane | (2) | | | | 508 | | 0.446 | |

UNREGULATED GROUP I ANALYSIS

62-550.405

(PWS035)

| ID | Name | Sample Number | Analysis Result(µg/L) | Q | Analysis Method | Analysis Date | MDL(µg/L) | Lab ID |
|------|---------------------|---------------|-----------------------|---|-----------------|---------------|-----------|--------|
| 2021 | Carbaryl | | | | 531.1 | | 3.89 | |
| 2022 | Methomyl | | | | 531.1 | | 3.20 | |
| 2043 | Aldicarb Sulfoxide | | | | 531.1 | | 1.88 | |
| 2044 | Aldicarb Sulfone | | | | 531.1 | | 5.57 | |
| 2045 | Metolachlor | | | | 507 | | 0.108 | |
| 2047 | Aldicarb | | | | 531.1 | | 5.95 | |
| 2066 | 3-Hydroxycarbofuran | | | | 531.1 | | 3.35 | |
| 2 | Butachlor | | | | 507 | | 0.021 | |
| 2. | Propachlor | | | | 508 | | 0.110 | |
| 2356 | Aldrin | | | | 508 | | 0.003 | |
| 2364 | Dieldrin | | | | 508 | | 0.002 | |
| 2440 | Dicamba | | | | 515.1 | | 0.005 | |
| 2595 | Metribuzin | | | | 507 | | 0.024 | |

BIONOMICS LABORATORY
 4310 E. Anderson Rd.
 Orlando, FL 32812
 DHRS/DEP #83331; E83012
 (407) 851-2560 FAX:(407) 856-0886

| For Lab Use Only | |
|----------------------------|-------------------|
| Date Received: | <u>04/21/98</u> |
| Time Received: | <u>1107</u> |
| Signature of Lab Official: | <u>Mark Rules</u> |

**DRINKING WATER
 BACTERIOLOGICAL ANALYSIS**

System Name: CITY OF COCOA System ID #: 3050223 System Phone#: (407)568-5867
 Address: 600 SCHOOL ST. County: _____ DEP District: _____
 Collector: MARY KRALJ Collector Phone#: (407)568-5867

Sample Site (locality or subdivision): R-10

Date and Time Collected: 04/21/98 @ 1000

Type of Supply: Community water system Noncommunity water system Nontransient-noncommunity water sys.
 Private well Swimming pool Bottled water Other public water system

Type of Sample: Compliance Repeat Replacement Main Clearance Well Survey Other: _____
 (circle one) (check box) (check box) (specify)
 Distribution TNTC or C
 Raw Turbid

Remarks:

| 9E COMPLETED BY COLLECTOR OF SAMPLE | | | |
|-------------------------------------|---------------------------------|--------|----|
| Coll No: | Sample Point (Specific Address) | Cl Res | pH |
| | R-10 | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| TO BE COMPLETED BY LAB: | | | | |
|---|--------------|---------------|---------------|---------------|
| Date & time of analysis: <u>04/21/98 @ 1225</u> | | by: <u>LH</u> | | |
| Analysis Method: MF | | MTF | MMO-MUG | PA |
| Sample Number: | Non Coliform | *Total | Confirm Total | Confirm Fecal |
| <u>B804478-01</u> | | <u>A</u> | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

* Results in this column are preliminary. Fecal coliform confirmation on community and noncommunity water systems and total coliform confirmation on all types of water systems will follow in 24-48 hours.

P - Coliforms are present C - Confluent growth TA - Turbid, Absence of gas or acid
 A - Coliforms are absent TNTC - Too numerous to count

INTERPRETATIONS - REMARKS BY PROGRAM REVIEWER

Name and Mailing Address of Person/Firm to Receive Report:

| |
|--|
| CITY OF COCOA 600 SCHOOL ST. COCOA, FL 32922 ATTN: MARY KRALJ |
|--|

- Satisfactory
- Incomplete collection information
- Repeat samples
- Replacement samples

Reviewing Official: _____

Title: _____



Appendix B-1
FDEP Certification of Class V
Well Construction Completion



CH2MHILL

June 4, 1998

CH2M HILL
3011 S.W. Williston Road
Gainesville, FL
32608-3928
Mailing address:
P.O. Box 147009
Gainesville, FL
32614-7009
Tel 352.335.7991
Fax 352.335.2959

Duane Watroba, TAC Chairman
Florida Department of Environmental Protection
Central District
3319 Maguire Boulevard
Suite 232
Orlando, FL 32803-3767

Subject: Cocoa ASR Facility – UIC Permit UC48-294600

Dear Mr. Watroba:

In accordance with Specific Condition E, page 7, of the City of Cocoa's UIC permit, we are submitting the Certification of Class V Well Construction Completion and SJRWMD well construction permits and well completion reports for the four newly completed ASR wells – R-7, R-8, R-9, and R-10. At this time, no wellhead facilities have been constructed. Final construction of the Dyal Water Treatment Plant expansion, including the wellhead facilities and the SCADA system are expected to be complete in the next 12-18 months.

As we recently discussed on the telephone, we are requesting that signed and sealed as-built drawings be submitted when wellhead facilities are completed and operational cycle testing of the four new wells has been conducted. This is in accordance with UIC permit specific condition D(3), page 10.

Please call if you have any questions .

Sincerely,

CH2M HILL

Michael B. Dykes, P.E.
Project Manager

GNV\Document2

c: Ed Wegerif, City of Cocoa
Ed Davis, CH2M HILL



Department of Environmental Protection

| | |
|----------------------|---|
| DEP Form No.: | 62-528.900(4) |
| Form Title: | Certification of Class V Well Construction Completion |
| Effective Date: | |
| DEP Application No.: | |
| (Filed in by DEP) | |

CERTIFICATION OF CLASS V WELL CONSTRUCTION COMPLETION

INSTRUCTIONS: Submit this certification to the Department along with a signed copy of the Well Completion Report from the appropriate Water Management District.

DEP Construction Permit No. UC48-294600, issued on 9/12/97. County Orange
(Date)

Owner's Name City of Cocoa

Owner's Address 600 School Street, Cocoa, FL 32922
(Street) (City) (State) (Zip Code)

Well Contractor's Name Meridith Environmental No.: 2200
(Title) (State License No.)

Well Contractor's Address 5654 N. Apopka Vineland, Orlando, FL 32858-5648
(Street) (City) (State) (Zip Code)

Well Location Well R-7, Dyal Water Treatment Plant

Deviations from the application and plans approved by the Department:
None Noted

Actual Dimensions:
Diameter 16 inches
Well depth 370' BLS feet
Casing depth 300' BLS feet

This is to certify that, with the exception of the deviations noted above, the construction of this well has been completed in accordance with the plans authorized by Construction Permit No. 3-095-0820-AWG, dated 7/13/97.

Date: May 28, 1998
Michael B. Dyke
(Contractor's Signature)
(Engineer's Signature)



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.


Permit No. 3-095-0820AWG
Florida Unique I.D.
Permit Stipulations Required (See attached)
62-524 well
CUP/WUP Application No.

Fold at this line in order that address is visible through envelope window


1. City of Cocoa 155 North Wilson Avenue Cocoa 32922 352-639-7651
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number
2. Claude H. Dyal Water Treatment Plant 28400 S.R. 520 Orange County
Well Location - Address, Road Name or Number, City
3. Meridith Environmental Services, Inc. 2200 407-291-4755
Well Drilling Contractor License No. Telephone No.
P.O. Box 585648
Address 4. NE 1/4 of NW 1/4 of Section 20
Orlando, FL 32858-5648 (Indicate Well on Chart)
City State Zip 5. Township 24 Range 34

7. Number of proposed wells 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type)
Irrigation (type) Public Water Supply (type) ASR (community) Other
Distance from septic system n/a ft. Description of facility R7 Estimated start of construction date 7-23-97

8. Application for: XX New Construction Repair/Modify Abandonment
9. Estimated: Well Depth 370 Casing Depth 300 26 inch hole Screen Interval from
Casing Material: Blk-Steel / PVC Casing Diameter 16 Seal Material
If applicable: Proposed From 300 to 0 Seal Material neat cement grout
Grouting Interval From to Seal Material



11. Telescope Casing or Liner (check one) Diameter
Blk-Steel / Galvanized / PVC Other (specify)
12. Method of Construction: X Rotary Cable Tool Combination
Auger Other (specify)
13. Indicate total No. of wells on site n/a List number of unused wells on site
14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive/Water Use Permit (CUP/WUP) or CUP/WUP Application? No Yes
District well I.D. No. 3048M05271 2-095-0005AUGMR
Latitude 28° 23' 00" N Longitude 81° 56' 00" W
Data obtained from GPS or map or survey (map datum NAD 27 NAD 83)



15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code... I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 373, Florida Statutes...

Signature of Contractor License No. 2200
Signature of Agent Date 6-24-97
Approval Granted By: E. J. - Energy Advisor Issue Date: 9/17/97 Hydrologist Approval
Owner Number: Fee Received: \$ 120.00 Receipt No.: 21022 Check No.: 15465

MERIDITH ENVIRONMENTAL SERVICES, INC.

JOB NAME: POOLE AND KENT P.O.# 8188

JOB LOCATION: WELL R-7 COMPLETED 11-14-98

DIAMETER OF CASINGS: 9 5/8" STATIC WATER LEVEL: 65"

TOTAL DEPTH OF WELL: 370'

TOTAL DEPTH OF CASING: 300' OF 16" PVC

| FROM FEET | TO FEET | TYPE MATERIAL ENCOUNTERED |
|-----------|---------|---|
| 0 | 10 | SAND |
| 10 | 12 | WHITE CLAY |
| 12 | 18 | SAND, SHELL |
| 18 | 40 | CEMENT, SHELL |
| 40 | 90 | SHELL, CLAY |
| 90 | 92 | ROCK |
| 92 | 114 | SHELL, SAND, LITTLE CLAY |
| 114 | 126 | CLAY, SHELL |
| 126 | 140 | SHELL, CEMENT |
| 140 | 145 | SHELL, CEMENT, CEMENTED SANDSTONE |
| 145 | 170 | SHELL, CEMENT, TRACES GREEN CLAY, CEMENTED SANDSTONE |
| 170 | 175 | SHELL, GREEN CLAY, CEMENTED SANDSTONE |
| 175 | 185 | SHELL, GREEN CLAY, CEMENTED SANDSTONE, TRACES OF WHITE |
| 185 | 195 | SHELL, GREEN CLAY, CEMENTED SANDSTONE, TRACES WHITE & GRAY |
| 195 | 205 | GREEN & GRAY CLAY, CEMENTED SANDSTONE, SOME SHELL |
| 205 | 215 | GREEN & GRAY CLAY, TRACES OF WHITE CLAY, CEMENTED SANDSTONE, SOME SHELL |

| | | |
|-----|-----|---|
| 215 | 220 | GRAY & WHITE CLAY, SOME GREEN, CEMENTED SANDSTONE, SOME SHELL |
| 220 | 235 | WHITE LIME ROCK, GRAY SANDSTONE, SOME WHITISH CLAY, SOME SHELL |
| 235 | 245 | GRAYISH WHITE SANDSTONE, SOME WHITISH TAN CLAY, GRAY LIMESTONE, SOME SHELL |
| 245 | 255 | LIGHT TAN & GRAY LIMESTONE, GREENISH GRAY CLAY, WHITISH GRAY SANDSTONE, SHELL |
| 255 | 260 | LIGHT TAN & GRAY LIMESTONE, GRAY SANDSTONE, GREENISH GRAY CLAY, TRACE OF BROWN |
| 260 | 270 | LIGHT TAN & GRAY LIMESTONE, GRAY SANDSTONE, GREENISH GRAY CLAY, GRAYISH WHITE CLAY, SHELL |
| 270 | 280 | LIGHT TAN & GRAY LIMESTONE, GRAY SANDSTONE, GRAYISH WHITE CLAY, SHELL |
| 280 | 285 | LIGHT TAN & GRAY LIMESTONE, GRAYISH WHITE SANDSTONE, SHELL, BROWN LIMESTONE |
| 285 | 305 | SOFT WHITE TO LIGHT TAN LIMESTONE, GRAYISH SANDSTONE, SHELL |
| 305 | 310 | SOFT LIGHT TAN LIMESTONE |
| 310 | 320 | SOFT LIGHT TAN LIMESTONE, TRACES OF CHERT |
| 320 | 325 | HARD LIGHT TAN LIMESTONE |
| 325 | 330 | MEDIUM HARD LIGHT GRAY LIMESTONE, TRACES OF LIGHT TAN |
| 330 | 335 | MEDIUM HARD LIGHT TAN LIME, TRACES OF LIGHT GRAY |
| 335 | 340 | MEDIUM HARD LIGHT TAN AND LIGHT GRAY LIMESTONE |
| 340 | 345 | MEDIUM HARD LIGHT TAN AND GRAY LIMESTONE |



Department of Environmental Protection

| | |
|----------------------|--|
| DEP Form No.: | 62-528.800(4) |
| Form Title: | Certification of Class V Well Construction Completion |
| Effective Date: | |
| DEP Application No.: | |
| (Filled in by DEP) | |

CERTIFICATION OF CLASS V WELL CONSTRUCTION COMPLETION

INSTRUCTIONS: Submit this certification to the Department along with a signed copy of the Well Completion Report from the appropriate Water Management District.

DEP Construction Permit No. UC48-294600, issued on 9/12/97. County Orange
(Date)

Owner's Name City of Cocoa

Owner's Address 600 School Street, Cocoa, FL 32922
(Street) (City) (State) (Zip)

Code)

Well Contractor's Name Meridith Environmental No.: 2200
(Title) (State License No.)

Well Contractor's Address 5654 N. Apopka Vineland, Orlando, FL 32858-5648
(Street) (City) (State) (Zip Code)

Well Location Well R-8, Dyal Water Treatment Plant

Deviations from the application and plans approved by the Department:

None Noted

Actual Dimensions:

Diameter 16 inches

Well depth 370' BLS feet

Casing depth 300' BLS feet

This is to certify that, with the exception of the deviations noted above, the construction of this well has been completed in accordance with the plans authorized by Construction Permit No. 3-095-0819-AWG, dated 9/30/97.

Date: May 28, 1998

Michael B. Dyke
(Contractor's Signature)
(Engineer's Signature)



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.


CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 3-095-0819AWG
Florida Unique I.D.
Permit Stipulations Required (See attached)
62-524 well
CUP/WUP Application No.


Fold at this line in order that address is visible through envelope window

1. City of Cocoa 155 North Wilson Avenue Cocoa 32922 352-639-7651
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number
2. Claude H. Dyal Water Treatment Plant 28400 S.R. 520 Orange County
Well Location - Address, Road Name or Number, City
3. Meridith Environmental Services, Inc. 2200 407-291-4755
Well Drilling Contractor License No. Telephone No.
P.O. Box 585648
Address 4. NE 1/4 of NW 1/4 of Section 20
Orlando, FL 32858-5648 (smallest) (biggest) (Indicate Well on Chart)
City State Zip 5. Township 24 Range 34
6. Orange
County Subdivision Name Lot Block Unit SW SE

7. Number of proposed wells 1 Check the use of well: (See back of permit for additional choices) Domestic Monitor (type)
Irrigation (type) Public Water Supply (type) ASR (community) List Other
(See Back) (See Back)
Distance from septic system n/a ft. Description of facility R8 Estimated start of construction date 7-23-97
8. Application for: X New Construction Repair/Modify Abandonment (Reason for Abandonment)
9. Estimated: Well Depth 370 Casing Depth 300-26" Screen Interval from
Casing Material: Bk-Steel/Gal/PVC Casing Diameter 16" Seal Material
If applicable: Proposed From 300 to 0 Seal Material neat cement grout
Grouting Interval From to Seal Material
From to Seal Material



11. Telescope Casing or Liner (check one) Diameter
Bk-Steel / Galvanized / PVC Other (specify):
12. Method of Construction: X Rotary Cable Tool Combination
Auger Other (specify):
13. Indicate total No. of wells on site n/a List number of unused wells on site
14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive/Water Use Permit (CUP/WUP) or CUP/WUP Application? No Yes
(if yes, complete the following) CUP/WUP No. 0048294500
District well I.D. No. 3048M05271 2-095-0005AUGMR
Latitude 28° 23' 00" N Longitude 81° 56' 00" W
Data obtained from GPS or map or survey (map datum NAD 27 NAD 83)



15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code, and that a water use permit or artificial recharge permit, if needed, has been or will be obtained prior to commencement of well construction. I further certify that all information provided on this application is accurate and that I will obtain necessary approval from other federal, state, or local governments, if applicable. I agree to provide a well completion report to the District within 30 days after drilling or the permit expires, whichever occurs first.
I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 373, Florida Statutes, to maintain or properly abandon this well; or, I certify that I am the agent for the owner, that the information provided is accurate, and that I have informed the owner of his responsibilities as stated above. Owner consents to personnel of the WMD or a representative access to the well site.
Signature of Contractor License No. 2200
Signature of Owner or Agent's Signature Date 6-24-97
CITY OF COCOA

DO NOT WRITE BELOW THIS LINE - FOR OFFICIAL USE ONLY

Approval Granted By: [Signature] Issue Date: 9/30/97 Hydrologist Approval: [Signature]
Owner Number: Fee Received: \$ 120.00 Receipt No.: 21022 Check No.: 15465

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.

WELL COMPLETION REPORT (Please complete in black ink or type.)

PERMIT # 3-095-0819W SUP # _____ DID # _____

Number of wells drilled 1 / WUP # _____

Indicate remaining wells to be cancelled _____
 (All wells drilled need an individual completion report)

WATER WELL CONTRACT # _____ License # 2200

SIGNATURE [Signature]


I certify that the information provided in this report is accurate and true!

| Grout | No. of Bags | From (ft.) | To (ft.) |
|--------------|-------------|------------|------------|
| Neat Cement: | 437 | 26", 0-120 | 16", 300-0 |
| Bentonite: | 240 | | |

WELL LOCATION: Site Address 28400 SR 520 County Orange
 Qtr: _____ Rge: 34
 Latitude _____ Longitude _____

DATE STAMP

Official Use Only



CHEMICAL ANALYSIS

Iron: _____ ppm Sulfate: _____ ppm
 Chlorides: _____ ppm
 [] Lab Test [] Field Test Kit
 Pump Type
 [] Centrifugal [] Jet [] Submersible
 [] Turbine
 Horsepower _____ Capacity _____ G.P.M. _____
 Pump Depth _____ Ft. Intake Depth _____ Ft.

OWNER'S NAME City of Cocoa R-8

COMPLETION DATE 1-25-98 Florida Unique I.D. _____

WELL USE: DEP/Public ASR X Irrigation _____ Domestic _____ Monitor _____

HRS Limited _____ 62-524 _____ Other _____

DRILL METHOD Rotary Cable Tool Combination
 Jet Auger Other _____

Measured Static Water Level 7 Measured Pumping Water Level 87

After 24 Hours at 920 G.P.M. Measuring Pt. (Describe): _____

Which is _____ Ft. Above Below Land Surface

Casing: Black Steel Galv. PVC Other _____

| Casing Diameter & Depth (Ft.) | Depth (Ft.) | | DRILL CUTTINGS LOG Examine cuttings every 20 ft. or at formation changes. Give color, grain size, and type of material. Note cavities, depth to producing zones. |
|--|-------------|-----|--|
| | From | To | |
| <input checked="" type="checkbox"/> Open Hole <input type="checkbox"/> Screen | 300 | 370 | |
| Diameter <u>26"</u> | | | |
| From <u>0</u> | | | |
| To <u>120</u> | | | |
| Diameter <u>16"</u> | | | |
| From <u>0</u> | | | |
| To <u>300</u> | | | |
| Liner <input type="checkbox"/> or Casing <input type="checkbox"/> | | | |
| Diameter _____ | | | |
| From _____ | | | |
| To _____ | | | |
| | | | see attached |

Driller's Name: David Adkins
 (print or type)

MERIDITH ENVIRONMENTAL SERVICES, INC.

JOB NAME: POOLE AND KENT

P.O.# 8188

JOB LOCATION: Well #8
COCOA COMPLETED

DIAMETER OF CASINGS: 9" PILOT HOLE STATIC WATER LEVEL:

TOTAL DEPTH OF WELL: TOTAL DEPTH OF CASING: 40'

| FROM FEET | TO FEET | TYPE MATERIAL ENCOUNTERED |
|-----------|---------|----------------------------------|
| 0 | 5 | BROWN SAND & BARK |
| 5 | 10 | BROWN SANDSTONE & BARK |
| 10 | 15 | BROWN SANDSTONE |
| 15 | 20 | BROWN SANDSTONE & SOME SHELL |
| 20 | 25 | SHELL & SOME CLAY |
| 25 | 30 | SHELL & SOME CLAY |
| 30 | 35 | SHELL & SOME CLAY |
| 35 | 40 | SHELL & SOME CLAY |
| 40 | 45 | SHELL, SOME CLAY & SANDSTONE |
| 45 | 50 | SHELL & TRACES OF SANDSTONE |
| 50 | 55 | SHELL & TRACES OF SANDSTONE |
| 55 | 60 | SHELL & TRACES OF SANDSTONE |
| 60 | 65 | SHELL & TRACES OF SANDSTONE |
| 65 | 70 | SHELL, SANDSTONE, TRACES OF CLAY |
| 70 | 75 | SHELL & GRAY CLAY |
| 75 | 80 | SHELL & GRAY CLAY |
| 80 | 85 | SHELL & GRAY CLAY |
| 85 | 90 | SHELL, SANDSTONE & GRAY CLAY |
| 90 | 95 | SHELL, SANDSTONE & GRAY CLAY |

MERIDITH ENVIRONMENTAL SERVICES, INC.

JOB NAME: POOLE AND KENT P.O.# 8188

JOB LOCATION: WELL R-8 COMPLETED 12-10-97

DIAMETER OF CASINGS: 9 5/8" STATIC WATER LEVEL: 0

TOTAL DEPTH OF WELL: _____ TOTAL DEPTH OF CASING: 300' OF 16" PVC

| FROM FEET | TO FEET | TYPE MATERIAL ENCOUNTERED |
|-----------|---------|--|
| 125 | 130 | CEMENT, SHELL, CEMENTED SANDSTONE |
| 130 | 135 | CEMENT, SHELL, CEMENTED SANDSTONE |
| 135 | 140 | DIRT, CEMENT, SHELL, CEMENTED SANDSTONE |
| 140 | 155 | SHELL, GREEN CLAY, CEMENTED SANDSTONE, CEMENT |
| 155 | 160 | GREEN CLAY, SHELL, CEMENTED SANDSTONE |
| 160 | 190 | SHELL, GREEN CLAY, CEMENTED SANDSTONE |
| 190 | 205 | GREEN CLAY, SOME SHELL AND CEMENTED SANDSTONE |
| 205 | 240 | GREEN CLAY, SOME SHELL AND CEMENTED SANDSTONE, TRACES OF WHITE CLAY |
| 240 | 250 | GREEN CLAY, SOME SHELL AND CEMENTED SANDSTONE, TRACES OF WHITE LIMESTONE |
| 250 | 260 | GREEN CLAY, SHELL AND CEMENTED SANDSTONE, TRACE OF WHITE LIMESTONE |
| 260 | 275 | SHELL, GREEN CLAY, CEMENTED SANDSTONE, SOME WHITE LIMESTONE |
| 275 | 285 | SHELL, SANDSTONE, SOME WHITE LIMESTONE |



Department of Environmental Protection

| | |
|----------------------|---|
| DEP Form No.: | 62-528.900(4) |
| Form Title: | Certification of Class V Well Construction Completion |
| Effective Date: | |
| DEP Application No.: | |
| (Filled in by DEP) | |

CERTIFICATION OF CLASS V WELL CONSTRUCTION COMPLETION

INSTRUCTIONS: Submit this certification to the Department along with a signed copy of the Well Completion Report from the appropriate Water Management District.

DEP Construction Permit No. UC48-294600, issued on 9/12/97. County Orange
(Date)

Owner's Name City of Cocoa

Owner's Address 600 School Street, Cocoa, FL 32922
(Street) (City) (State) (Zip Code)

Well Contractor's Name Meridith Environmental No.: 2200
(Title) (State License No.)

Well Contractor's Address 5654 N. Apopka Vineland, Orlando, FL 32858-5648
(Street) (City) (State) (Zip Code)

Well Location R-9, Dyal Water Treatment Plant

Deviations from the application and plans approved by the Department:

None Noted

Actual Dimensions:

| | | |
|--------------|-----------------|--------|
| Diameter | <u>16</u> | inches |
| Well depth | <u>370' BLS</u> | feet |
| Casing depth | <u>300' BLS</u> | feet |

This is to certify that, with the exception of the deviations noted above, the construction of this well has been completed in accordance with the plans authorized by Construction Permit No. 3-095-0817-AWG, dated 9/30/97.

Date: May 28, 1998

Michael B. Dyle
(Contractor's Signature)
(Engineer's Signature)



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.

CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.


Permit No. 3-095-0817AW5
Florida Unique I.D.
Permit Stipulations Required (See attached)
62-524 well
CUP/WUP Application No.

Fold at this line in order that address is visible through envelope window


1. City of Cocoa 155 North Wilson Avenue Cocoa 32922 352-639-7651
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number
2. Claude H Dyal Water Treatment Plant 28400 S.R. 520 Orange County
Well Location - Address, Road Name or Number, City
3. Meridith Environmental Services, Inc. 2200 407-291-4755
Well Drilling Contractor License No. Telephone No.
P.O. Box 585648
Address 4. NE 1/4 of NW 1/4 of Section 20
Orlando, FL 32858-5648 (Indicate Well on Chart)
City State Zip 5. Township 24 Range 34
6. Orange
County Subdivision Name Lot Block Unit SW SE

7. Number of proposed wells 1 Check the use of well: Domestic Monitor (type)
Irrigation (type) Public Water Supply (type) ASR (community) List Other
Distance from septic system n/a ft. Description of facility R9 Estimated start of construction date 7-23-97

8. Application for: XX New Construction Repair/Modify Abandonment
9. Estimated: Well Depth 370 Casing Depth 300-26" BREXIDE Screen Interval from to
Casing Material: Blk-Steel/ Gal / PVC Casing Diameter 1.6" Seal Material
If applicable: Proposed From 300 to 0 Seal Material neat cement grout
Grouting Interval From to Seal Material



11. Telescope Casing or Liner (check one) Diameter
Blk-Steel / Galvanized / PVC Other (specify:
12. Method of Construction: X Rotary Cable Tool Combination
Auger Other (specify:
13. Indicate total No. of wells on site n/a List number of unused wells on site
14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive Water Use Permit (CUP/WUP) or CUP/WUP Application? No Yes
District well I.D. No. 3048M05271 2-095-0005AUGMR
Latitude 28° 23' 00" N Longitude 81° 56' 00" W
Data obtained from GPS or map or survey (map datum NAD 27 NAD 83)



15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code... I certify that I am the owner of the property, that the information provided is accurate, and that I am aware of my responsibilities under Chapter 373, Florida Statutes...
Signature of Contractor License No. 2200
City of Cocoa Owner's or Agent's Signature Date 6-24-97

Approval Granted By: Issue Date: 9/30/97 Hydrologist Approval
Owner Number: Fee Received: \$ 120.00 Receipt No.: 21022 Check No.: 15465

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.

Meridith Enviro Servs Fax:407-578-8649 Jun 4 '98 14:05 P.02

WELL COMPLETION REPORT (Fill out completely in black ink or type)

PERMIT # 3-095-0817WG DID # _____
 Number of wells drilled 1 / SWUP _____
 Indicate remaining wells to be cancelled _____
 (All wells drilled need an individual completion report)
WATER WELL CONTRACTORS
 SIGNATURE [Signature] _____ 2200
I hereby certify that the information furnished on this report is accurate and true.

OWNER'S NAME City of Cocoa R-9

COMPLETION DATE 3-18-98 Florida Unique I.D. _____

WELL USE: DEPPublic Irrigation _____ Domestic _____ Monitor _____
 ASR
 HRS Limited _____ 62-524 _____ Other _____


DRILL METHOD Rotary Cable Tool Combination
 Jet Auger Other _____

| Grout | No. of Bags | From (ft.) | To (ft.) |
|--------------|-------------|------------|------------|
| Neat Cement: | 441 | 26", 120-0 | 16", 300-0 |
| Bentonite: | 187 | | |

WELL LOCATION: Site Address 28400 SR 520 County Orange
 Ow: _____ Or: _____ Sec: 20 Twp: 24 Rge: 34
 Latitude _____ Longitude _____

DATE STAMP

 Official Use Only

Sketch of well location on property: N

 Give distances from septic tank and house or other reference points

CHEMICAL ANALYSIS
 Iron: _____ ppm Sulfate: _____ ppm
 Chlorides: _____ ppm
 Lab Test Field Test Kit
 Pump Type
 Centrifugal Jet Submersible
 Turbine
 Horsepower _____ Capacity _____ G.P.M.
 Pump Depth _____ Ft. Intake Depth _____ Ft.

Measured Static Water Level 9 Measured Pumping Water Level 71
 After 24 Hours at 1060 G.P.M. Measuring Pt. (Describe): _____
 Which is _____ Ft. Above Below Land Surface
 Casing: Black Steel Galv. PVC Other _____

| Casing Diameter & Depth (ft.) | 300 Depth 370 (ft.) | | DRILL CUTTINGS LOG Examine cuttings every 20 ft. or at formation changes. Give color, grain size, and type of material. Note cavities, depth to producing zones. |
|---|---------------------|----|--|
| | From | To | |
| Diameter <u>26"</u> From <u>0</u> To <u>120</u> | | | |
| Diameter <u>16"</u> From <u>0</u> To <u>300</u> | | | see attached |
| Liner <input type="checkbox"/> or Casing <input type="checkbox"/> Diameter _____ From _____ To _____ | | | |

Driller's Name: (print or type) David Adkins



Department of Environmental Protection

| | |
|----------------------|---|
| DEP Form No.: | 62-528.900(4) |
| Form Title: | Certification of Class V Well Construction Completion |
| Effective Date: | |
| DEP Application No.: | |
| (Filled in by DEP) | |

CERTIFICATION OF CLASS V WELL CONSTRUCTION COMPLETION

INSTRUCTIONS: Submit this certification to the Department along with a signed copy of the Well Completion Report from the appropriate Water Management District.

DEP Construction Permit No. UC48-294600, issued on 9/12/97. County Orange
(Date)

Owner's Name City of Cocoa

Owner's Address 600 School Street, Cocoa, FL 32922
(Street) (City) (State) (Zip Code)

Well Contractor's Name Meridith Environmental No.: 2200
(Title) (State License No.)

Well Contractor's Address 5654 N. Apopka Vineland, Orlando, FL 32858-5648
(Street) (City) (State) (Zip Code)

Well Location Well R-10, Dyal Water Treatment Plant

Deviations from the application and plans approved by the Department:

None Noted

Actual Dimensions:

| | | |
|--------------|-----------------|--------|
| Diameter | <u>16</u> | inches |
| Well depth | <u>370' BLS</u> | feet |
| Casing depth | <u>300' BLS</u> | feet |

This is to certify that, with the exception of the deviations noted above, the construction of this well has been completed in accordance with the plans authorized by Construction Permit No. 3-095-0818-AWG, dated 9/30/97.

Date: May 28, 1998

Michael B. DePa
(Contractor's Signature)
(Engineer's Signature)



STATE OF FLORIDA PERMIT APPLICATION TO CONSTRUCT, REPAIR, MODIFY, OR ABANDON A WELL

- Southwest
Northwest
St. Johns River
South Florida
Suwannee River

THIS FORM MUST BE FILLED OUT COMPLETELY. The water well contractor is responsible for completing this form and forwarding the permit to the appropriate delegated county where applicable.


CHECK BOX FOR APPROPRIATE DISTRICT. ADDRESS ON BACK OF PERMIT FORM.

Permit No. 3-095-0818AWG
Florida Unique I.D.
Permit Stipulations Required (See attached)
62-524 well
CUP/WUP Application No.


ABOVE THIS LINE FOR OFFICIAL USE ONLY

1. City of Cocoa 155 North Wilson Avenue Cocoa 32922 352-639-7651
Owner, Legal Name of Entity if Corporation Address City Zip Telephone Number
2. Claude H. Dyal Water Treatment Plant 28400 S.R. 520, Orange County, FL
Well Location - Address, Road Name or Number, City
3. Meredith Environmental Services, Inc. 2200 407-291-4755
Well Drilling Contractor License No. Telephone No.
P.O. Box 585648
Address
Orlando, FL 32858-5648
City State Zip
5. Township 24 Range 34
6. Orange
County Subdivision Name Lot Block Unit SW SE

7. Number of proposed wells 1 Check the use of well: Domestic Monitor (type)
Irrigation (type) Public Water Supply (type) XX community List Other
Distance from septic system n/a ft. Description of facility ASR R10 Estimated start of construction date 7-23-97
8. Application for: X New Construction Repair/Modify Abandonment
9. Estimated: Well Depth 370 Casing Depth 300-26" to 26" holes Screen Interval from
Casing Material: Blk-Steel/Gal / PVC Casing Diameter 16" Seal Material
If applicable: Proposed From 300 to 0 Seal Material neat cement grout
Grouting Interval From to Seal Material
From to Seal Material



11. Telescope Casing or Liner (check one) Diameter
Blk-Steel / Galvanized / PVC Other (specify:
12. Method of Construction: X Rotary Cable Tool Combination
Auger Other (specify:
13. Indicate total No. of wells on site n/a List number of unused wells on site n/a
14. Is this well or any other well or water withdrawal on the owner's contiguous property covered under a Consumptive/Water Use Permit (CUP/WUP) or CUP/WUP Application? No Yes
District well I.D. No. 3048M05271
Latitude 28° 23' 00" N Longitude 81° 56' 00" W
Data obtained from GPS or map or survey (map datum NAD 27 NAD 83)



15. I hereby certify that I will comply with the applicable rules of Title 40, Florida Administrative Code, and that a water use permit or artificial recharge permit, if needed, has been or will be obtained prior to commencement of well construction. I further certify that all information provided on this application is accurate and that I will obtain necessary approval from other federal, state, or local governments, if applicable. I agree to provide a well completion report to the District within 30 days after drilling or the permit expiration, whichever occurs first.
Signature of Contractor License No. 2200
City of Cocoa Owner's or Agent's Signature Date 6-24-97

Approval Granted By: Issue Date: 9/30/97 Hydrologist Approval
Owner Number: Fee Received: \$ 120.00 Receipt No.: 21022 Check No.: 15465

THIS PERMIT NOT VALID UNTIL PROPERLY SIGNED BY AN AUTHORIZED OFFICER OR REPRESENTATIVE OF THE WMD. IT SHALL BE AVAILABLE AT THE WELL SITE DURING ALL DRILLING OPERATIONS. This permit is valid for 90 days from date of issue.

WELL COMPLETION REPORT (Please complete in black ink or type.)

PERMIT # 3-095-0818WG CUP # _____ DID # _____

Number of wells drilled 1 /WUP # _____

Indicate remaining wells to be cancelled _____
 (All wells drilled need an individual completion report)

WATER WELL CONTRACT # 2200
 SIGNATURE [Signature] License # _____

I certify that the information provided in this report is accurate and true.

OWNER'S NAME City of Cocoa R-10

COMPLETION DATE 4-21-98 Florida Unique I.D. _____

WELL USE: DEP/Public Irrigation _____ Domestic _____ Monitor _____

ASR
 HRS Limited _____ 62-524 _____ Other _____

DRILL METHOD Rotary Cable Tool Combination


Jet Auger Other _____

| Grout | No. of Bags | From (ft.) | To (ft.) |
|--------------|-------------|------------|------------|
| Neat Cement: | 437 | 26", 0-120 | 16", 300-0 |
| Bentonite: | 157 | | |

WELL LOCATION: Site Address 28400 SR 520 County Orange
 Qtr: _____ Qtr: _____ Sec: 20 Twp: 24 Rge: 34
 Latitude _____ Longitude _____

DATE STAMP

 Official Use Only



CHEMICAL ANALYSIS

Iron: _____ ppm Sulfate: _____ ppm
 Chlorides: _____ ppm
 Lab Test Field Test Kit
 Pump Type
 Centrifugal Jet Submersible
 Turbine
 Horsepower _____ Capacity _____ G.P.M. _____
 Pump Depth _____ Ft. Intake Depth _____ Ft.

Measured Static Water Level 10 Measured Pumping Water Level 28
 After 24 Hours at 1220 G.P.M. Measuring Pt. (Describe): _____
 Which is _____ Ft. Above Below Land Surface
 Casing: Black Steel Galv. PVC Other _____

| Casing Diameter & Depth (ft.) | 300 Depth 370 (ft.) | | DRILL CUTTINGS LOG Examine cuttings every 20 ft. or at formation changes. Give color, grain size, and type of material. Note cavities, depth to producing zones. |
|-----------------------------------|---------------------|----|--|
| | From | To | |
| Diameter <u>26"</u> | | | |
| From <u>0</u> | | | |
| To <u>120</u> | | | |
| Diameter <u>16"</u> | | | |
| From <u>0</u> | | | |
| To <u>300</u> | | | see attached |
| Liner <input type="checkbox"/> or | | | |
| Casing <input type="checkbox"/> | | | |
| Diameter _____ | | | |
| From _____ | | | |
| To _____ | | | |

Driller's Name: David Adkins
 (print or type)



***Appendix B-2
Alignment and Pressure
Testing Data***

MERIDITH ENVIRONMENTAL SERVICES, INC.**PLUMBNESS AND ALIGNMENT TEST
COCOA WELL R-7**

| DEPTH | PLUMBNESS |
|--------------|------------------|
| 10' | CENTER |
| 20' | CENTER |
| 30' | CENTER |
| 40' | CENTER |
| 50' | CENTER |
| 60' | 0" X 1/4" EAST |
| 70' | 0" X 1/4" EAST |
| 80' | 0" X 1/2" EAST |
| 90' | 0" X 3/4" EAST |
| 100 | 0" X 3/4" EAST |
| 110' | 0" X 3/4" EAST |
| 120' | 0" X 3/4" EAST |
| 130' | 0" X 3/4" EAST |
| 140' | 0" X 7/8" EAST |
| 150' | 0" X 1" EAST |

MERIDITH ENVIRONMENTAL SERVICES, INC.

PLUMBNESS AND ALIGNMENT TEST
COCOA WELL R-8

| DEPTH | PLUMBNESS |
|-------|------------------------|
| 10' | CENTER |
| 20' | CENTER |
| 30' | CENTER |
| 40' | CENTER |
| 50' | CENTER |
| 60' | CENTER |
| 70' | CENTER |
| 80' | CENTER |
| 90' | CENTER |
| 100 | 1/2" SOUTH X 0" |
| 110' | 1/2" SOUTH X 0" |
| 120' | 1/2" SOUTH X 1/4" WEST |
| 130' | 3/4" SOUTH X 1/4" WEST |
| 140' | 7/8" SOUTH X 1/2" WEST |
| 150' | 1" SOUTH X 1/2" WEST |

MERIDITH ENVIRONMENTAL SERVICES, INC.**PLUMBNESS AND ALIGNMENT TEST
COCOA WELL R-9**

| DEPTH | PLUMBNESS |
|--------------|------------------|
| 10' | CENTER |
| 20' | CENTER |
| 30' | 1/2" NORTH X 0" |
| 40' | 1/2" NORTH X 0" |
| 50' | 1/2" NORTH X 0" |
| 60' | 1/2" NORTH X 0" |
| 70' | 1/2" NORTH X 0" |
| 80' | 1/2" NORTH X 0" |
| 90' | 1/2" NORTH X 0" |
| 100 | 1/2" NORTH X 0" |
| 110' | 1/2" NORTH X 0" |
| 120' | 1/2" NORTH X 0" |
| 130' | 3/4" NORTH X 0" |
| 140' | 1/2" NORTH X 0" |
| 150' | 1/2" NORTH X 0" |

MERIDITH ENVIRONMENTAL SERVICES, INC.**PLUMBNESS AND ALIGNMENT TEST
COCOA WELL R-10**

| DEPTH | PLUMBNESS |
|--------------|------------------------|
| 10' | CENTER |
| 20' | CENTER |
| 30' | 1/4" EAST X 1/4" SOUTH |
| 40' | 1/4" EAST X 1/4" SOUTH |
| 50' | 1/2" EAST X 1/2" SOUTH |
| 60' | 1/2" EAST X 1/2" SOUTH |
| 70' | 3/8" EAST X 3/8" SOUTH |
| 80' | 1/4" EAST X 3/8" SOUTH |
| 90' | 1/4" EAST X 1/4" SOUTH |
| 100 | 0" X 1/2" SOUTH |
| 110' | 1/4" EAST X 1/2" SOUTH |
| 120' | 1/4" EAST X 1/2" SOUTH |
| 130' | 1/2" EAST X 1/2" SOUTH |
| 140' | 1/2" EAST X 1/4" SOUTH |
| 150' | 3/4" EAST X 1/4" SOUTH |

Cocoa ASR Wells R-7, R-8, R-9 & R-10
Final Casing Pressure Testing

Well R-7
Date of Test: Nov. 3, 1997

| Time (mins.) | Casing Pressure (psi) |
|--------------|-----------------------|
| 0 | 77 |
| 10 | 75 |
| 20 | 73 |
| 30 | 71 |
| 40 | 71 |
| 50 | 71 |
| 60 | 70 |

2.88 = 5.10
100 lbs
9/10 chert
7.55 / 197 =

Well R-8
Date of Test: Dec. 15, 1997

| Time (mins.) | Casing Pressure (psi) |
|--------------|-----------------------|
| 0 | 76 |
| 10 | 75 |
| 20 | 74 |
| 30 | 72 |
| 40 | 72 |
| 50 | 72 |
| 60 | 71 |

6.6% chert

Well R-9
Date of Test: Feb. 16, 1998

| Time (mins.) | Casing Pressure (psi) |
|--------------|-----------------------|
| 0 | 75 |
| 10 | 75 |
| 20 | 74 |
| 30 | 72 |
| 40 | 71 |
| 50 | 70 |
| 60 | 70 |

6.6%

Well R-10
Date of Test: April 2, 1998

| Time (mins.) | Casing Pressure (psi) |
|--------------|-----------------------|
| 0 | 78 |
| 10 | 75 |
| 20 | 73 |
| 30 | 73 |
| 40 | 72 |
| 50 | 71 |
| 60 | 71 |

5.
8.97% chert


CITY OF **COCOA** FLORIDA



Appendix B-3 ***Step Test Results***

New ASR Well R-7 Step-Drawdown Test
Test Performed May 5, 1998

| Step | Pumping Rate, Q (gpm) | Observed Drawdown, s (ft.) | Specific Capacity (gpm/ft) | 1/Specific Capacity (ft/gpm) |
|------|-----------------------|----------------------------|----------------------------|------------------------------|
| 1 | 320 | 22.5 | 14.3 | 0.0702 |
| 2 | 530 | 40.3 | 13.2 | 0.0760 |
| 3 | 960 | 74.2 | 12.9 | 0.0773 |



From Inverse Specific Capacity vs. Flowrate chart (above):


Turbulent Drawdown Coefficient, C= 9.93 (10⁻⁶) ft/gpm²
 Laminar Drawdown Coefficient, B= .0685 ft/gpm

| Step | ¹ Turbulent Component of Drawdown, CQ ² (ft) | ² Laminar Component of Drawdown, BQ (ft) | Percent of Drawdown Attributable of Laminar Flow 100% X BQ/(CQ ² + BQ) |
|------|--|---|--|
| 1 | 1.02 | 21.9 | 95.6% |
| 2 | 2.79 | 36.3 | 92.9% |
| 3 | 9.15 | 65.8 | 87.8% |

Note 1 This is the Well Loss term of Jacob (1946) where drawdown = CQ² + BQ


Note 2 This is the Laminar term of Jacob (1946) where drawdown = CQ² + BQ

ASR R7 Step Test



New ASR Well R-8 Step-Drawdown Test
Test Performed April 22, 1998

| Step | Pumping Rate, Q (gpm) | Observed Drawdown, s (ft.) | Specific Capacity (gpm/ft) | 1/Specific Capacity (ft/gpm) |
|------|-----------------------|----------------------------|----------------------------|------------------------------|
| 1 | 290 | 22.5 | 12.9 | 0.0776 |
| 2 | 570 | 46.1 | 12.4 | 0.0809 |
| 3 | 940 | 80.2 | 11.7 | 0.0853 |




From Inverse Specific Capacity vs. Flowrate chart (above):
 Turbulent Drawdown Coefficient, C= 1.19 (10⁻⁵) ft/gpm²
 Laminar Drawdown Coefficient, B= .0741 ft/gpm

| Step | ¹ Turbulent Component of Drawdown, CQ ² (ft) | ² Laminar Component of Drawdown, BQ (ft) | Percent of Drawdown Attributable of Laminar Flow 100% X BQ/(CQ ² + BQ) |
|------|--|---|---|
| 1 | 1.0 | 21.5 | 95.6% |
| 2 | 3.9 | 42.2 | 91.6% |
| 3 | 10.5 | 69.7 | 86.9% |

Note 1 This is the Well Loss term of Jacob (1946) where drawdown = CQ² + BQ
 Note 2 This is the Laminar term of Jacob (1946) where drawdown = CQ² + BQ


ASR R8 Step Test



New ASR Well R-9 Step-Drawdown Test
Test Performed April 4, 1998

| Step | Pumping Rate, Q (gpm) | Observed Drawdown, s (ft.) | Specific Capacity (gpm/ft) | 1/Specific Capacity (ft/gpm) |
|----------------|-----------------------|----------------------------|----------------------------|------------------------------|
| 1 | 300 | 14.0 | 21.5 | 0.0465 |
| 2 | 600 | 31.6 | 19.0 | 0.0526 |
| 3 | 1000 | 58.2 | 17.2 | 0.0582 |
| 4 ^A | 1060 | 62.3 | 17.0 | 0.0588 |

Note A: Drawdown from constant-rate test substituted for 4th step of the step-test



From Inverse Specific Capacity vs. Flowrate chart (above):


Turbulent Drawdown Coefficient, C= $1.59 (10^{-5}) \text{ ft/gpm}^2$
 Laminar Drawdown Coefficient, B= $.0423 \text{ ft/gpm}$

| Step | ¹ Turbulent Component of Drawdown, CQ^2 (ft) | ² Laminar Component of Drawdown, BQ (ft) | Percent of Drawdown Attributable of Laminar Flow $100\% \times BQ/(CQ^2 + BQ)$ |
|----------------|---|---|--|
| 1 | 1.4 | 12.7 | 89.9% |
| 2 | 5.7 | 25.4 | 81.6% |
| 3 | 15.9 | 42.3 | 72.7% |
| 4 ^A | 17.9 | 44.8 | 71.5% |

Note 1 This is the Well Loss term of Jacob (1946) where drawdown = $CQ^2 + BQ$


Note 2 This is the Laminar term of Jacob (1946) where drawdown = $CQ^2 + BQ$

ASR R9 Step Test



New ASR Well R-10 Step-Drawdown Test
Test Performed April 17, 1998

| Step | Pumping Rate, Q (gpm) | Observed Drawdown, s (ft.) | Specific Capacity (gpm/ft) | 1/Specific Capacity (ft/gpm) |
|------|-----------------------|----------------------------|----------------------------|------------------------------|
| 1 | 310 | 1.9 | 162.3 | 0.0062 |
| 2 | 590 | 5.8 | 102.1 | 0.0098 |
| 3 | 1200 | 18.4 | 65.1 | 0.0154 |




From Inverse Specific Capacity vs. Flowrate chart (above):
 Turbulent Drawdown Coefficient, C= $1.01 (10^{-5})$ ft/gpm²
 Laminar Drawdown Coefficient, B= .00335 ft/gpm

| Step | ¹ Turbulent Component of Drawdown, CQ ² (ft) | ² Laminar Component of Drawdown, BQ (ft) | Percent of Drawdown Attributable of Laminar Flow 100% X BQ/(CQ ² + BQ) |
|------|--|---|--|
| 1 | 0.973 | 1.04 | 51.6% |
| 2 | 3.53 | 1.97 | 35.9% |
| 3 | 14.6 | 4.02 | 21.6% |

Note 1 This is the Well Loss term of Jacob (1946) where drawdown = CQ² + BQ

Note 2 This is the Laminar term of Jacob (1946) where drawdown = CQ² + BQ

ASR R10 Step Test






CITY OF COCOA FLORIDA

Appendix B-4
Constant Rate Test Results

ASR R7 Pump Test



CH2M HILL
3011 S.W. Williston Road
Gainesville, Florida
ph.(352) 335-7991

Pumping test analysis
Time-Drawdown-method after
COOPER & JACOB
Confined aquifer

Date: May 12, 1998 Page 1

Project: City of Cocoa, Florida


Evaluated by: M. Weatherby

Pumping Test No. Test 1

Test conducted on: May 6, 1998

New ASR Well - R7

Discharge 880.00 U.S.gal/min



o R7 (new ASR well)

Transmissivity [ft^2/min]: 2.13×10^0

Storativity: 1.49×10^{-4}

Transmissivity [gpd/ft]: 22,942

CH2M HILL
 3011 S.W. Williston Road
 Gainesville, Florida
 ph.(352) 335-7991

Pumping test analysis
 HANTUSH's method
 Leaky aquifer, no aquitard storage

Date: May 12, 1998 Page 1

Project: City of Cocoa, Florida


Evaluated by: M. Weatherby

Pumping Test No. Test 1

Test conducted on: May 6, 1998

New ASR Well - R7

Discharge 880.00 U.S.gal/min



o R8 (new ASR well)

Transmissivity [ft^2/min]: 2.90×10^0

Storativity: 2.21×10^{-4}

Transmissivity [gpd/ft]: 31,236

CH2M HILL
 3011 S.W. Williston Road
 Gainesville, Florida
 ph.(352) 335-7991

Pumping test analysis
 HANTUSH's method
 Leaky aquifer, no aquitard storage

Date: May 12, 1998 Page 1

Project: City of Cocoa, Florida


Evaluated by: M. Weatherby

Pumping Test No. Test 1

Test conducted on: May 6, 1998

New ASR Well - R7

Discharge 880.00 U.S.gal/min




Transmissivity [ft²/min]: 8.02×10^0

Storativity: 2.07×10^{-4}

Transmissivity [gpd/ft]: 86,385

ASR R8 Pump Test



CH2M HILL
3011 S.W. Williston Road
Gainesville, Florida
ph. (352) 335-7991

Pumping test analysis
Time-Drawdown-method after
COOPER & JACOB
Confined aquifer

Date: May 12, 1998 Page 1

Project: City of Cocoa, Florida


Evaluated by: M. Weatherby

Pumping Test No. Test 1

Test conducted on: April 27, 1998

New ASR Well - R8

Discharge 920.00 U.S.gal/min



o R8 (new ASR Well)

Transmissivity [ft²/min]: 2.26×10^0

Storativity: 9.39×10^{-6}

Transmissivity [gpd/ft]: 24,343

CH2M HILL
 3011 S.W. Williston Road
 Gainesville, Florida
 ph.(352) 335-7991

Pumping test analysis
 HANTUSH's method
 Leaky aquifer, no aquitard storage

Date: May 12, 1998 Page 1

Project: City of Cocoa, Florida


Evaluated by: M. Weatherby

Pumping Test No. Test 1

Test conducted on: April 27, 1998

New ASR Well - R8

Discharge 920.00 U.S.gal/min



Transmissivity [ft²/min]: 2.86×10^0

Storativity: 2.09×10^{-4}

Transmissivity [gpd/ft]: 30,806

CH2M HILL
 3011 S.W. Williston Road
 Gainesville, Florida
 ph.(352) 335-7991

Pumping test analysis
 HANTUSH's method
 Leaky aquifer, no aquitard storage

Date: May 12, 1998 Page 1

Project: City of Cocoa, Florida


Evaluated by: M. Weatherby

Pumping Test No. Test 1

Test conducted on: April 27, 1998

New ASR Well - R8

Discharge 920.00 U.S.gal/min



o R9 (new ASR well)

Transmissivity [ft^2/min]: 3.60×10^0

Storativity: 9.34×10^{-5}

Transmissivity [gpd/ft]: 38,776

CH2M HILL
 3011 S.W. Williston Road
 Gainesville, Florida
 ph. (352) 335-7991

Pumping test analysis
 HANTUSH's method
 Leaky aquifer, no aquitard storage

Date: May 12, 1998 Page 1

Project: City of Cocoa, Florida


Evaluated by: M. Weatherby

Pumping Test No. Test 1

Test conducted on: April 27, 1998

New ASR Well - R8

Discharge 920.00 U.S.gal/min




o R10 (new ASR well)

Transmissivity [ft^2/min]: 1.67×10^1

Storativity: 5.43×10^{-4}

Transmissivity [gpd/ft]: 179,879

ASR R9 Pump Test



CH2M HILL
3011 S.W. Williston Road
Gainesville, Florida
ph.(352) 335-7991

Pumping test analysis
Time-Drawdown-method after
COOPER & JACOB
Confined aquifer

Date: May 12, 1998 Page 1

Project: City of Cocoa, Florida


Evaluated by: M. Weatherby

Pumping Test No. Test 1

Test conducted on: April 14, 1998

New ASR Well - R9

Discharge 1060.00 U.S.gal/min



o R9 (new ASR well)

Transmissivity [ft²/min]: 2.50×10^0

Storativity: 3.79×10^{-4}

Transmissivity [gpd/ft]: 26,928

CH2M HILL
 3011 S.W. Williston Road
 Gainesville, Florida
 ph.(352) 335-7991

Pumping test analysis
 HANTUSH's method
 Leaky aquifer, no aquitard storage

Date: May 12, 1998 Page 1

Project: City of Cocoa, Florida


Evaluated by: M. Weatherby

Pumping Test No. Test 1

Test conducted on: April 14, 1998

New ASR Well - R9

Discharge 1060.00 U.S.gal/min



o R8 (new ASR well)

Transmissivity [ft²/min]: 2.24×10^0

Storativity: 8.23×10^{-5}

Transmissivity [gpd/ft]: 24,127



CH2MHILL

3011 S.W. Williston Road
Gainesville, Florida 32608
ph.(352) 335-7991

Pumping test analysis
HANTUSH's method
Leaky aquifer, no aquitard storage

Date: May 12, 1998 Page 1

Project: City of Cocoa, Florida


Evaluated by: M. Weatherby

Pumping Test No. Test 1

Test conducted on: April 14, 1998

New ASR Well - R9

Discharge 1060.00 U.S.gal/min



Transmissivity [ft²/min]: 3.17×10^0

Storativity: 2.59×10^{-4}

Transmissivity [gpd/ft]: 34,144

CH2M HILL
 3011 S.W. Williston Road
 Gainesville, Florida
 ph.(352) 335-7991

Pumping test analysis
 HANTUSH's method
 Leaky aquifer, no aquitard storage

Date: May 12, 1998 Page 1

Project: City of Cocoa, Florida


Evaluated by: M. Weatherby

Pumping Test No. Test 1

Test conducted on: April 14, 1998

New ASR Well - R9

Discharge 1060.00 U.S.gal/min




o R10 (new ASR well)

Transmissivity [ft²/min]: 1.21×10^1

Storativity: 3.53×10^{-4}

Transmissivity [gpd/ft]: 130,331

ASR R10 Pump Test



CH2M HILL
3011 S.W. Williston Road
Gainesville, Florida
ph.(352) 335-7991

Pumping test analysis
Time-Drawdown-method after
COOPER & JACOB
Confined aquifer

Date: May 13, 1998 Page 1

Project: City of Cocoa, Florida


Evaluated by: M. Weatherby

Pumping Test No. Test 1

Test conducted on: April 20, 1998

New ASR Well - R10

Discharge 1220.00 U.S.gal/min



o R10 (new ASR well)

Transmissivity [ft^2/min]: 1.68×10^1

Storativity: 7.17×10^{-8}

Transmissivity [gpd/ft]: 180,956

CH2M HILL
 3011 S.W. Williston Road
 Gainesville, Florida
 ph.(352) 335-7991

Pumping test analysis
 HANTUSH's method
 Leaky aquifer, no aquitard storage

Date: May 13, 1998 Page 1

Project: City of Cocoa, Florida


Evaluated by: M. Weatherby

Pumping Test No. Test 1

Test conducted on: April 20, 1998

New ASR Well - R10

Discharge 1220.00 U.S.gal/min



Transmissivity [ft²/min]: 2.05×10^0

Storativity: 1.23×10^{-4}


Transmissivity [gpd/ft]: 22,081

Pumping Test No. Test 1

Test conducted on: April 20, 1998

New ASR Well - R10

Discharge 1220.00 U.S.gal/min



Transmissivity [ft²/min]: 1.15×10^1

Storativity: 3.23×10^{-4}

Transmissivity [gpd/ft]: 123,869

The logs that came with this document are to be filed in OCULUS as follows:

Catalog Underground Injection Control

Profile Permitting_Authorization

County BREVARD

District CD

Facility-Site ID 16670 - CITY OF COCOA, CLAUDE H. DYAL (ASR)

Document Date 03-16-1999

Received Date 03-17-1999

Document Type ENGINEERING REPORTS

Contractor ID

PSD Number

Permit Type CONSTRUCTION

Facility Type CLASS V - ASR

Application Number

Permit Number

Document Subject *Log Type LOG ID Log Date Eng RPT ASR Wells 1999*